

Understanding Construction Drawings

7th Edition



Mark W. Huth

UNDERSTANDING CONSTRUCTION DRAWINGS

Mark W. Huth

UNDERSTANDING CONSTRUCTION DRAWINGS

Mark W. Huth



Australia • Brazil • Japan • Korea • Mexico • Singapore • Spain • United Kingdom • United States

This is an electronic version of the print textbook. Due to electronic rights restrictions, some third party content may be suppressed. Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. The publisher reserves the right to remove content from this title at any time if subsequent rights restrictions require it. For valuable information on pricing, previous editions, changes to current editions, and alternate formats, please visit www.cengage.com/highered to search by ISBN#, author, title, or keyword for materials in your areas of interest.

Important Notice: Media content referenced within the product description or the product text may not be available in the eBook version.

**Understanding Construction Drawings,
Seventh Edition**

Mark W. Huth

SVP, GM Skills & Global Product Management:
Jonathan Lau

Product Director: Matt Seeley

Senior Product Manager: Vanessa Myers

Executive Director, Development:
Marah Bellegarde

Senior Content Development Manager:
Larry Main

Content Developer:
Katie Ostler, Lumina Datamatics

Product Assistant: Jason Koumourdias

Vice President, Strategic Marketing Services:
Jennifer Ann Baker

Marketing Manager: Scott Chrysler

Senior Content Project Manager:
Kara A. DiCaterino

Senior Digital Project Manager: Amanda Ryan

Designer: Angela Sheehan

Cover Designer: Joe Devine

Cover & Interior Design Image(s):
Hitdelight/Shutterstock.com
istock.com/suprun

Additional Interior Design Image(s):
BorisShevchuk/Shutterstock.com
Bloomicon/Shutterstock.com

© 2019, 2014 Cengage Learning

WCN: 02-300

ALL RIGHTS RESERVED. No part of this work covered by the copyright herein may be reproduced or distributed in any form or by any means, except as permitted by U.S. copyright law, without the prior written permission of the copyright owner.

For product information and technology assistance, contact us at
Cengage Learning Customer & Sales Support, 1-800-354-9706

For permission to use material from this text or product,
submit all requests online at **www.cengage.com/permissions**.

Further permissions questions can be e-mailed to
permissionrequest@cengage.com

Library of Congress Control Number: 2017950099

Book Only ISBN: 978-1-337-40864-6

Package ISBN: 978-1-337-40863-9

Cengage Learning

20 Channel Center Street
Boston, MA 02210
USA

Cengage Learning is a leading provider of customized learning solutions with employees residing in nearly 40 different countries and sales in more than 125 countries around the world. Find your local representative at **www.cengage.com**.

Cengage Learning products are represented in Canada by Nelson Education, Ltd.

To learn more about Cengage Learning, visit **www.cengage.com**
Purchase any of our products at your local college store or at our preferred online store **www.cengagebrain.com**

Notice to the Reader

Publisher does not warrant or guarantee any of the products described herein or perform any independent analysis in connection with any of the product information contained herein. Publisher does not assume, and expressly disclaims, any obligation to obtain and include information other than that provided to it by the manufacturer. The reader is expressly warned to consider and adopt all safety precautions that might be indicated by the activities described herein and to avoid all potential hazards. By following the instructions contained herein, the reader willingly assumes all risks in connection with such instructions. The publisher makes no representations or warranties of any kind, including but not limited to, the warranties of fitness for particular purpose or merchantability, nor are any such representations implied with respect to the material set forth herein, and the publisher takes no responsibility with respect to such material. The publisher shall not be liable for any special, consequential, or exemplary damages resulting, in whole or part, from the readers' use of, or reliance upon, this material.



Contents

Preface	vii
Part 1 DRAWINGS: TWO-UNIT APARTMENT	
Unit 1 The Design-Construction Sequence and the Design Professions	2
Unit 2 Views	8
Unit 3 Scales	15
Unit 4 Alphabet of Lines	19
Unit 5 Use of Symbols	25
Unit 6 Plan Views	35
Unit 7 Elevations	41
Unit 8 Sections and Detail	47
Part 1 Test	55
Part 2 READING DRAWINGS: LAKE HOUSE	
Unit 9 Clearing and Rough Grading the Site	60
Unit 10 Locating the Building	65
Unit 11 Site Utilities	71
Unit 12 Footings	76
Unit 13 Foundation Walls	84
Unit 14 Drainage, Insulation, and Concrete Slabs	90
Unit 15 Framing Systems	95
Unit 16 Columns, Piers, and Girders	109
Unit 17 Floor Framing	116
Unit 18 Laying Out Walls and Partitions	128
Unit 19 Framing Openings in Walls	133
Unit 20 Roof Construction Terms	140
Unit 21 Roof Trusses	144
Unit 22 Common Rafters	155
Unit 23 Hip and Valley Framing	162
Unit 24 Cornices	171
Unit 25 Windows and Doors	180
Unit 26 Exterior Wall Coverings	188
Unit 27 Decks	197
Unit 28 Finishing Site Work	202

Unit 29	Fireplaces	211
Unit 30	Stairs	219
Unit 31	Insulation and Room Finishing	224
Unit 32	Cabinets	236
Unit 33	Lake House Specifications	240
	Part 2 Test	249

Part 3 **MULTIFAMILY CONSTRUCTION: URBAN COURTS**

Unit 34	Orienting the Drawings	252
Unit 35	Fire-Rated and Acoustical Considerations	262
Unit 36	Seismic Considerations	269
	Part 3 Test	279

Part 4 **HEAVY COMMERCIAL CONSTRUCTION: SCHOOL ADDITION**

Unit 37	Heavy Commercial Construction	283
Unit 38	Coordination of Drawings	296
Unit 39	Structural Drawings	304
Unit 40	HVAC & Plumbing Drawings	312
Unit 41	Electrical Drawings	324
	Part 4 Test	344

APPENDICES

Appendix A	School Addition Master Keynotes	347
Appendix B	Math Reviews	357
Appendix C	Material Symbols in Sections	373
Appendix D	Plumbing Symbols	374
Appendix E	Electrical Symbols	375
Appendix F	Common Abbreviations	376

GLOSSARY **378**

INDEX **383**

DRAWING PACKET

Two-Unit Apartment Building Drawings

Lake House Drawings

Urban Courts Drawings

School Addition Drawings

Preface

Intended Audience

Understanding Construction Drawings is designed for students in construction programs in two- and four-year colleges and technical institutes, as well as apprentice training. Designed for a course in print reading focused on both residential and commercial construction, the book helps you learn to read the drawings that are used to communicate information about buildings. It includes drawings for buildings that were designed for construction in several parts of North America. The diversity of building classifications and geographic locations ensures that you are ready to work on construction jobs anywhere in the industry. Everyone who works in building construction should be able to read and understand the drawings of the major trades.

How to Use This Book

The book is divided into four major parts and several units within each part. Each part relates to the prints in the separate drawing packet:

- **Part 1, Drawings: Two-Unit Apartment**, introduces you to the basics of print reading by covering views, scales, lines, and symbols, as well as the various plan views, elevations, and sections and details.
- **Part 2, Reading Drawings: Lake House**, provides information on how to interpret drawings for project specifics—everything from footings and foundation walls to room finishing and cabinets.
- **Part 3, Multifamily Construction: Urban Courts**, details more advanced residential print reading and applies the skills learned in Parts 1 and 2 to other types of construction, as well as mechanical and electrical trades.
- **Part 4, Heavy Commercial Construction: School Addition**, presents the need-to-know information on interpreting prints for large commercial

construction including structural drawings, mechanical drawings, and electrical drawings.

Features of the Units

The individual units are made up of four elements: Objectives, the main body of the unit, Using What You Learned, and Assignment.

- The **Objectives** appear at the beginning of the unit so that you will know what to look for as you study the unit.
- The **main body** is the presentation of content with many illustrations and references to the prints for the building being studied in that part.
- **Using What You Learned** gives you an opportunity to do a practice exercise that is similar to the exercises found in the assignment questions for that unit. The real-world need to be able to do the exercise is explained first. The exercise is presented and followed by a detailed explanation of how to find the specified information. **Each unit contains 10 to 20 Assignment** questions that require you to both understand the content of the unit and apply that understanding to reading the drawings. There are more than 600 questions in all.

The book is divided into four parts, corresponding with the four buildings. At the end of each part there is a test. Additionally units include one or more **Green Notes**, which provide insights and suggestions for green home construction.

The Drawing Packet, Glossary, and Appendix

At the back of the text you will find several helpful aids for studying construction drawings.

- The **drawing packet** that is conveniently packaged with the book contains 22 sheets with separate

drawings that relate to each of the parts within the book. The drawing packet contains prints for four buildings: a simple two-family duplex that is very easy to understand, a more complex single-family home, one building in an urban development located in an earthquake zone, and an addition to a school.

- The **Glossary** defines all the new technical terms introduced throughout the textbook. Each of these terms is defined where it is first used, but if you need to refresh your memory, turn to the Glossary.
- The **Math Reviews** in Appendix B are an innovative feature that has helped many construction students through a difficult area. These are concise reviews of the basic math you are likely to encounter throughout the building construction field. As math is required in this textbook, reference is made to the appropriate Math Review. All the math skills needed to complete the end-of-unit assignments in this book are covered in the Math Reviews.
- The **Appendix** also includes a complete list of construction abbreviations commonly used on prints, along with their meaning. There is also a section that explains the most commonly used symbols for materials and small equipment.

New to This Edition

Understanding Construction Drawings, Seventh Edition, represents a major revision of the book. Part 3 is all new, based on a 4-story residential building in an area known to have high seismic activity. One of the new units is entirely devoted to the special considerations that are encountered in areas with seismic activity.

MindTap For Understanding Construction Drawings, 7e

NEW! The MindTap for Understanding Construction Drawings, 7th Edition features an integrated course offering a complete digital experience for the student and teacher. This MindTap is highly customizable and combines assignments, videos, interactivities, and quizzing along with the enhanced ebook to enable students to directly analyze and apply what

they are learning and allow teachers to measure skills and outcomes with ease.

- A Guide: Relevant interactivities combined with prescribed readings, featured multimedia, and quizzing to evaluate progress, will guide students from basic knowledge and comprehension to analysis and application.
- Personalized Teaching: Teachers are able to control course content—hiding, rearranging existing content, or adding and creating own content to meet the needs of their specific program.
- Promote Better Outcomes: Through relevant and engaging content, assignments and activities, students are able to build the confidence they need to ultimately lead them to success. Likewise, teachers are able to view analytics and reports that provide a snapshot of class progress, time in course, engagement and completion rates.

Supplements to the Text

Along with the *Understanding Construction Drawings, Seventh Edition* book, we are proud to offer supplemental offerings that will help support classroom instruction and engage students in learning.

The **Instructor Resources** available on our Companion website contains *free* helpful tools for the instructor teaching a course on reading and interpreting construction drawings. Each component follows the chapters in the book and is intended to help instructors prepare classroom presentations and student evaluations. To access these helpful tools, please visit www.cengagebrain.com. At the home page, search for this Companion website by typing in the ISBN of the book in the search box at the top of the page. On the page illustrating this book, click on the “Access” button next to “Free Study Tools” and this will direct you to the following resources:

- An **Instructor’s Guide** provides answers to all the Assignment questions and test questions in the textbook, and explains how the answers were found or calculated. In addition, it contains more than

500 additional questions that can be used for tests, supplemental assignments, and review. The answer to each of these questions is given, along with an explanation of the answer.

- **PowerPoint Presentations** include an outline of each chapter along with photos and graphics to help illustrate important points and enhance classroom instruction. These presentations are editable, allowing instructors to include additional notes and photos/graphics from the Image Gallery included on our Companion website.
- **Cengage Learning Testing Powered by Cognero** is a flexible, online system that allows you to:
 - author, edit, and manage test bank content from multiple Cengage Learning solutions
 - create multiple test versions in an instant
 - deliver tests from your LMS, your classroom or wherever you want
- **Image Gallery** containing graphics and photos from all the chapters in the book provide an additional option for classroom presentations. Instructors may choose to add to the existing PowerPoint, or may wish to create their own presentations based on the book.

Acknowledgments

I am grateful to all who contributed to this textbook. Special thanks are due to Ralph Henderson, School of Science and Technology, Rogue Community College for contributing most of the content of Unit 36 on seismic considerations.

The instructors and their students who have used the previous five editions have given me valuable feedback that has played an instrumental role in shaping this edition. Several companies provided expertise and contributed illustrations—including many of the figures that illustrate this book.

I would especially like to thank the architects and engineers who supplied the drawings for the drawing packet, namely:

Robert Kurzon

Duplex and Lake House

Carl Griffith

Cataldo, Waters, and Griffith Architects, P.C., and HA2F Consultants in Engineering for the School Addition

Chelsea Richardson and Shawn Sidener

Jeffrey DeMure + Associates for architectural drawings of Urban Courts

Karl Freeman

O'Connor, Freeman, & Associates for structural drawings for Urban Courts

Lastly, I would also like to thank the instructors who reviewed the manuscript for the previous editions and for this new edition. They have provided guidance in making it the best print reading textbook it could be.

Ralph Henderson

Department Chair/Instructor for Construction Technology, Rogue Community College, Grants Pass, OR

Steven Peterson

Professor, Weber State University, Ogden, UT

Scott Bretthauer

Teacher, E.M.P.S., College of Lake County, Grayslake, IL.

Joe Dusek

Professor, Construction Management Department, Triton College, River Grove, IL.

Judy Guentzler-Collins

Building Technology Department, Cochise College, Sierra Vista, AZ.

Seongchan Kim

Department of Engineering Technology, Western Illinois University, Macomb, IL

About the Author

The author of this textbook, Mark W. Huth, brings many years of experience in the industry to his writing—first as a carpenter and then as a contractor, building construction teacher, and construction publisher—his career has allowed him to consult with hundreds of construction educators in high schools, colleges, and universities. He has also authored several other successful construction titles, including *Basic Blueprint Reading for Construction*, *Residential Construction Academy: Basic Principles for Construction*, and *Practical Problems in Mathematics for Carpenters*.

A Word about Math

Construction requires the use of mathematics. Whether you are a carpenter planning stairs, a plumber calculating pipe lengths and fitting allowances, or an estimator preparing for a contract bid, you need math to do your job. The math required in this textbook is basic, so you probably have learned enough math to do all of the work required. Most of the math required on a construction job can be done quite easily with a construction calculator, such as the one shown here. Today's construction calculators are preprogrammed to do everything from converting decimals to fractions, calculating the lengths of rafters, figuring cubic yards of concrete, and other standard industry computations.


If you are studying construction, you probably own a construction calculator now or will soon. However, as you progress in your learning and spend more time working on construction sites, you will soon find that you do not always have your trusty calculator handy. If you have learned to do the basic math required with a pencil and paper (or scrap of wood), you will not be hampered by not having your calculator. Also, it is easy to make big mistakes with a calculator—any kind of calculator. With one wrong press of a key, you can add when you meant to multiply or add an extra zero. If you

learn the math, you can check your work and ensure that it is close to what the calculator got, so there is less likely to be a catastrophic error.



A typical construction calculator.

For these reasons, you are urged to complete the assignments at the end of each textbook unit by doing the math *without a calculator*, at least until you feel confident in your ability. If you have trouble doing the math, check the Math Reviews in Appendix B at the back of the book. They give easy, step-by-step directions for doing all of the types of math needed in the book.



PART

DRAWINGS: TWO-UNIT APARTMENT

Part 1 helps you develop a foundation upon which to build skills and knowledge in reading the drawings used in the construction industry. The topics of the various units in this section are the basic concepts upon which all construction drawings are read and interpreted. The details of construction are explored in Parts 2, 3, and 4.

Many of the assignment questions in this part refer to the drawings of the Two-Unit Apartment Building (Duplex) included in the drawing packet that accompanies this textbook. The Duplex was designed as income property for a small investor. It was built on a corner lot in a small city in upstate New York. The Duplex is an easy-to-understand building. Its one-story, rectangular design requires only a minimum of views; you can quickly become familiar with the Duplex drawings.

UNIT 1

The Design-Construction Sequence and the Design Professions

Objectives

After completing this unit, you will be able to perform the following tasks:

- Name the professions included in the design and planning of a house or light commercial building.
- List the major functions of each of these professions in the design and planning process.
- Identify the profession or agency that should be contacted for specific information about a building under construction.

The construction industry employs about 15 percent of the working people in the United States and Canada. A large portion of construction workers are involved in constructing new buildings, roads, airports, and industrial facilities. The rest are involved in repairing, remodeling, and maintenance. As the needs of our society change, the demand for different kinds of construction increases. Homeowners and businesses demand more energy-efficient buildings. The shift toward automation in business and industry means that new offices are needed. Our national centers of commerce and industry are shifting. These are only a few of the reasons that new housing starts are considered important indicators of our economic health.

The construction industry is made up of light construction (small buildings) and heavy construction (large buildings, roadways, bridges, industrial installations, etc.). The industry can also be divided into the following four classifications: residential, commercial, industrial, and civil. *Residential construction* includes single-family homes, small apartment buildings, and condominiums (see **Figure 1–1(a)**). *Commercial construction* includes



Figure 1–1(a). Single- and multi-family homes are classified as residential construction.



Figure 1–1(b). Commercial construction.




Courtesy of Bechtel Corporation. Photographer: Terry Lowenthal. Used by permission.

Figure 1–1(c). Industrial construction. Delta Energy Center, water treatment tanks and buildings in the foreground.

office buildings, hotels, stores, shopping centers, and other large buildings (see **Figure 1–1(b)**). *Industrial construction* includes structures other than buildings, such as refineries and paper mills, that are built for industry (see **Figure 1–1(c)**). *Civil construction* (see **Figure 1–1(d)**) is more closely linked with the land and refers to highways, bridges, airports, dams, and the like.

The Design Process

The design process starts with the owner. The owner has definite ideas about what is needed, but may not be expert at describing that need or desire in terms the builder can understand. The owner contacts an architect to help plan the building.



Courtesy of Bechtel Corporation. Photographer: Ray Frayne. Used by permission.

Figure 1–1(d). Civil construction. At 726 feet, Hoover Dam is the highest dam in the United States.



GREEN NOTE

Green construction can be defined in many different ways, and sometimes the definitions sound complicated. In its simplest terms, green construction is the process of designing and constructing a building that minimizes its impact on the environment both during construction, over its useful life, and, ultimately, the recyclability of its materials—or their safe and proper disposal—when that life comes to an end.

A green home is built from environmentally sustainable materials using practices that reduce material use and waste. A durable, long-lasting home has lower maintenance requirements and less overall impact on the environment than a home that needs to be replaced sooner or requires frequent repairs. A green home is also designed to conserve resources such as heating and cooling energy and water.

The architect serves as the owner's agent throughout the design and construction process. Architects combine their knowledge of construction—of both the mechanics and the business—with artistic or aesthetic knowledge and ability. They design buildings for appearance and use.

The architect helps the owner determine how much space is needed, how many rooms are needed for now and

in the future, what type of building best suits the owner's lifestyle or business needs, and what the costs will be. As the owner's needs take shape, the architect makes rough sketches to describe the planned building. At first these may be balloon diagrams (see **Figure 1-2**) to show traffic flow and the number of rooms. Eventually, the design of the building begins to take shape (see **Figure 1-3**).




Figure 1-2. Balloon sketch of Duplex.




Figure 1-3. Straight line sketch of Duplex.

Before all the details of the design can be finalized, other construction professionals become involved. Building codes specify requirements to ensure that buildings are safe from fire hazards, earthquakes, termites, surface water, and other concerns of the community. Most building codes are based on a model code. For example, the International Code Council (ICC) publishes several model codes, one of which is the *International Building Code*[®]. It is commonly referred to as the IBC. Another is the *International Residential Code*[®] for One- and Two-Family Dwellings, the IRC, which includes all of the parts of the IBC that pertain to one- and two-family dwellings plus some additional content that applies to these dwellings (see **Figure 1–4**). The IRC is a model code, because it is a model that may be used by state and local building authorities as a basis for their own local code. A model code has no authority on its own. The government having jurisdiction in a locale must adopt its own building code. Very often the government body having jurisdiction (called the *Authority Having Jurisdiction*, or AHJ) adopts the model code. Sometimes the AHJ adds specific clauses to the model, and, in rare cases, it writes an all-new code. State building codes allow local governments to adopt a local



GREEN NOTE

The design and planning for a green home involves not only the owner and designer, but the general contractor and key trade contractors as well. The designer's preliminary house plans are reviewed by those who will build the home, each looking for ways to improve energy efficiency, incorporate durable construction details, and simplify utility systems installation. Group meetings are often conducted in which the designer, owner, contractor, and key trade contractors discuss the plans and examine the impact of each recommendation and how the work will be carried out. The general contractor and trade contractors can also recommend green building materials that best suit the project.


building code, but they require that the local code be at least as stringent as the state code.

The local building code is administered by a building department of the local government. The building department reviews the architect's plans before construction begins and inspects the construction throughout its progress to ensure that the code is followed.

Most communities also have zoning laws. A *zoning law* divides the community into zones where only certain types of buildings are permitted. Zoning laws prevent such problems as factories and shopping centers being built in the same neighborhood as homes.

Building departments usually require that very specific procedures are followed for each construction project. A building permit is required before construction begins. The building permit notifies the building department about planned construction. Then, the building department can make sure that the building complies with all the local zoning laws and building codes. When the building department approves the completed construction, it issues a *certificate of occupancy*. This certificate is not issued until the building department is satisfied that the construction has been completed according to the local code. The certificate of occupancy is usually issued after a final inspection by the building inspector. The owner is not permitted to move into the new building until the certificate of occupancy has been issued.

If the building is more complex than a home or simple frame building, engineers may be hired to help



Copyright © 2015 International Code Council, Inc., www.iccsafe.org. All rights reserved. Excerpts reprinted with permission.

Figure 1–4. 2015 *International Residential Code*[®] for One- and Two-Family Dwellings.

design the structural, mechanical, electrical, or other aspects of the building. Consulting engineers specialize in certain aspects of construction and are employed by architects to provide specific services. Finally, architects and their consultants prepare construction drawings that show all aspects of the building. These drawings tell the contractor specifically what to build.

Some homes are built from stock plans available from catalogs of house designs, building materials dealers, or magazines (see **Figure 1-5**). However, many states require a registered architect to approve the design and supervise the construction.




Figure 1-5. Stock plans can be ordered from catalogs.

Starting Construction

After the architect and the owner decide on a final design, the owner obtains financing. The most common way of financing a home is through a mortgage. A *mortgage* is a guarantee that the loan will be paid in installments. If the loan is not paid, the lender has the right to sell the building in order to recover the money owed. In return for the use of the lender's money, the borrower pays interest—a percentage of the outstanding balance of the loan.

When financing has been arranged (sometimes before it is finalized), a contractor is hired. Usually, a general contractor is hired with overall responsibility for completing the project. The general contractor in turn hires subcontractors to complete certain parts of the project. All stages of construction may be subcontracted. The parts of home construction most often subcontracted are excavation, plumbing and heating, electrical, drywall, painting and decorating, and landscaping. The relationships of all the members of the design and construction team are shown in **Figure 1-6**. Utility installers should carefully investigate all the drawings, especially the architectural drawings, in order to determine the installation locations of their equipment.




Figure 1-6. Design and construction team.



USING WHAT YOU LEARNED

Everyone involved in the design, construction, and ownership of a building needs to know who the major players are in the process. Only by understanding what role each agency, company, and individual plays in the process can a construction worker know where to go with questions and for information. For example, no work can begin on the site until a building permit has been issued. The owner, contractor, and superintendent all need to know who issues that permit. Building permits are issued by the building department of the city, town, or county where the building is to be constructed.

Assignment

1. Who acts as the owner's agent while the building is being constructed?
2. Who designs the structural aspects of a commercial building?
3. Who would normally hire an electrical engineer for the design of a store?
4. Who is generally responsible for obtaining financing for a small building?
5. To whom would the general contractor go if there were a problem with the foundation design for a home?
6. If local building codes require specific features for earthquake protection, who is responsible for seeing that they are included in a home design?
7. Whom would the owner inform about last-minute changes in the interior trim when the building is under construction?
8. What regulations specify what parts of the community are to be reserved for single-family homes only?
9. Who issues the building permit?
10. What regulations are intended to ensure that all new construction is safe?

UNIT 2

Views

Objectives

After completing this unit, you will be able to perform the following tasks:

- Recognize oblique, isometric, and orthographic drawings.
- Draw simple isometric sketches.
- Identify plan views, elevations, and sections.

Isometric Drawings

A useful type of pictorial drawing for construction purposes is the *isometric drawing*. In an isometric drawing, vertical lines are drawn vertically, and horizontal lines are drawn at an angle of 30° from horizontal, as shown in **Figure 2-1**. All lines on one of these isometric axes are drawn in proportion to their actual length. Isometric drawings tend to look out of proportion because we are used to seeing the object appear smaller as it gets farther away.

Isometric drawings are often used to show plumbing layout (see **Figure 2-2**). The ability to draw simple isometric sketches is a useful skill for communicating on the job site. Try sketching a brick in isometric as shown in **Figure 2-3**.

- Step 1. Sketch a Y with the top lines about 30° from horizontal.
- Step 2. Sketch the bottom edges parallel to the top edges.
- Step 3. Mark off the width on the left top and bottom edges. This will be about twice the height.
- Step 4. Mark off the length on the right top and bottom edges. The length will be about twice the width.
- Step 5. Sketch the two remaining vertical lines and the back edges.

Other isometric shapes can be sketched by adding to or subtracting from this basic isometric brick (see **Figure 2-4**). Angled surfaces are sketched by locating their edges and then connecting them.




Figure 2-1. Isometric of building.




Figure 2-2. Single-line plumbing isometric.



GREEN NOTE

Waste water is classified as either black water or gray water. Black water is that which is discharged from toilets and kitchens, where the water can be very contaminated and must be extensively treated before it can be released into the environment or reused. Gray water is from sinks, laundry areas, and storm water and is less dangerous to the environment. It is becoming increasingly common for green homes to treat gray water and reuse it for irrigation and toilets.




Figure 2-3. Sketching an isometric brick.

Oblique Drawings

When an irregular shape is to be shown in a pictorial drawing, an *oblique drawing* may be best. In oblique drawings, the most irregular surface is drawn in proportion as though it were flat against the drawing surface. Parallel lines are added to show the depth of the drawing as shown in **Figure 2-5**.

Orthographic Projection

To show all information accurately and to keep all lines and angles in proportion, most construction drawings




Figure 2-4. Variations on the isometric brick.




Figure 2-5. Oblique drawing.

are drawn by **orthographic projection**. Orthographic projection is most often explained by imagining the object to be drawn inside a glass box. The corners and the lines representing the edges of the object are then projected onto the sides of the box (see **Figure 2-6**). If the box is unfolded, the images projected onto its sides will be on a single plane, as on a sheet of paper (see **Figure 2-7**). In other words, in orthographic projection, each view of an object shows only one side (or top or bottom) of the object.

All surfaces that are parallel to the plane of projection (the surface of the box) are shown in proportion to their actual size and shape. However, surfaces




Figure 2-6. Duplex inside a glass box; method of orthographic projection of roof, front side, and end.




Figure 2-7. Orthographic projection unfolded on a flat sheet of paper.




Figure 2-8. Views of two shed roofs.





Figure 2-9. Plan view.

that are not parallel to the plane of projection are not shown in proportion. For example, both of the roofs in the top views of **Figure 2-8** appear to be the same size and shape, but they are quite different. To find the actual shape of the roof, you must look at the end view.

In construction drawings, the views are called plans and elevations. A *plan view* shows the layout of the object as viewed from above (see **Figure 2-9**). A set of drawings for a building usually includes plan views of the site (lot), the floor layout, and the foundation. **Elevations** are drawings that show height. For example, a drawing that shows what would be seen standing in front of a house is a building elevation (see **Figure 2-10**). Elevations are also used to show cabinets and interior features.






Figure 2-10. Building elevation.




(a)

(b) SECTION




Because not all features of construction can be seen in plan views and elevations from the outside of a building, many construction drawings are **section views**. A section view, usually referred to simply as a *section*, shows what would be exposed if a cut were made through the object (see **Figure 2–11**). Actually, a *floor plan* is a type of section view (see **Figure 2–12**). It is called a *plan* because it is in that position—viewed from above—but it is a type of *section* because it shows what would be exposed if a cut were made through the building. Most section views are called sections, but floor plans are customarily referred to as plans or floor plans.

Figure 2–11. Section of a window sash.



(a)



(b)


Figure 2–12. A floor plan is actually a section view of the building. (a) An imaginary cut is made at a level that passes through all windows and doors. (b) The floor plan shows what is left when the top is removed.



USING WHAT YOU LEARNED


As you look for specific information on a set of construction prints, it is helpful to know what type of drawing you are looking at. For example, if it is an orthographic projection, the lines you see will be drawn in true proportion to their actual sizes. However, if it is oblique or isometric, they may not be in proportion. The Assignment questions in this unit require you to identify various drawing types. Take a look at the door frame types on Sheet 2 of the Two-Unit Apartment in the drawing packet accompanying this textbook. It is a section view because it shows parts as though a cut were made through the door jamb, revealing the interior construction. It is a plan view because it shows what would be seen looking straight down from above. It is an orthographic projection drawing because what we see is what would have been projected onto the top of a glass box placed over the cut door jamb.

Assignment




(a)

1. Identify each of the drawings in **Figure 2-13** as oblique, isometric, or orthographic.
2. Identify each of the drawings in **Figure 2-14** as elevation, plan, or section.
3. In the view of the house shown in **Figure 2-15**, which lines are true length?
4. What type of pictorial drawing is easiest to draw on the job site?
5. What type of drawing is used for working drawings?



TOP VIEW
OF STAIR



(b)

Figure 2-13.






Figure 2-14.




Figure 2-15.

Scales

3 UNIT

Scale Drawings

Because construction projects are too large to be drawn full size on a sheet of paper, everything must be drawn proportionately smaller than it really is. For example, **floor plans** for a house are frequently drawn 1/48th of the actual size. This is called *drawing to scale*. At a scale of $\frac{1}{4}'' = 1'-0''$, $\frac{1}{4}$ inch on the drawing represents 1 foot on the actual building. When it is necessary to fit a large object on a drawing, a small scale is used. Smaller objects and drawings that must show more detail are drawn to a larger scale. The floor plan in **Figure 3-1** was drawn to a scale of $\frac{1}{4}'' = 1'-0''$. The detail drawing in **Figure 3-2** was drawn to a scale of $3'' = 1'-0''$ to show the construction of one of the walls on the floor plan.

The scale to which a drawing is made is noted on the drawing. The scale is usually indicated alongside or beneath the title of the view.

Reading an Architect's Scale

All necessary dimensions should be shown on the drawings. The instrument used to make drawings to scale is called an **architect's scale** (see **Figure 3-3**). Measuring a drawing with an architect's or engineer's scale is a poor practice. At small scales it is especially difficult to be precise. The following discussion of how to read an architect's scale is presented only to ensure an understanding of the scales used on drawings. The triangular architect's scale includes eleven scales frequently used on drawings.

Full Scale	
$\frac{3}{32}'' = 1'-0''$	$\frac{3}{16}'' = 1'-0''$
$\frac{1}{8}'' = 1'-0''$	$\frac{1}{4}'' = 1'-0''$
$\frac{3}{8}'' = 1'-0''$	$\frac{3}{4}'' = 1'-0''$
$\frac{1}{2}'' = 1'-0''$	$1'' = 1'-0''$
$\frac{1}{2}'' = 1'-0''$	$3'' = 1'-0''$

Two scales are combined on each face, except for the full-size scale, which is fully divided into sixteenths (see **Figure 3-4**). The combined scales work together because one is twice as large as the other, and their zero points and extra divided units **are on** opposite ends of the scale.

The fraction, or number, near the zero at each end of the scale indicates the unit length in inches that is used on the drawing to represent 1 foot of the actual building. The extra unit near the zero end of the scale is subdivided into twelfths of a foot (inches) as well as fractions of inches on the larger scales.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Identify the scale used on a construction drawing.
- Read an architect's scale.




Figure 3-1. Portion of a plan view with a firewall. ¼" = 1'-0".




Figure 3-2. Detail (plan at firewall). 3" = 1'-0".




Figure 3-3. Architect's scale.

To read the architect's scale, turn it to the $\frac{1}{4}$ -inch scale. The scale is divided on the left from the zero toward the $\frac{1}{4}$ mark so that each line represents 1 inch. Counting the marks from the zero toward the $\frac{1}{4}$ mark, there are 12 lines marked on the scale. Each one of these lines is 1 inch on the $\frac{1}{4}$ " = 1'-0" scale.

The fraction $\frac{1}{8}$ is on the opposite end of the same scale. This is the $\frac{1}{8}$ -inch scale and is read in the opposite direction. Notice that the divided unit is only half as large as the one on the $\frac{1}{4}$ -inch end of the scale. Counting the lines from zero toward the $\frac{1}{8}$ mark, there are only six lines. This means that each line represents 2 inches at the $\frac{1}{8}$ -inch scale.

Now look at the $\frac{1}{2}$ -inch scale. The divided unit is broken into twelfths of a foot (inches) and also fractional parts of an inch. Reading from the zero toward the number $\frac{1}{2}$, notice the figures 3, 6, and 9. These figures




Figure 3-4. Architect's triangular scales.

represent the measurements of 3 inches, 6 inches, and 9 inches at the $\frac{1}{2}$ " = 1'-0" scale. From the zero to the first long mark, that represents 1 inch (which is the same length as the mark shown at 3) and four lines. This means that each line on the scale is equal to $\frac{1}{4}$ of an inch. Reading from the zero to the 3, read each line as follows: $\frac{1}{4}$, $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$, $1\frac{3}{4}$, 2, $2\frac{1}{4}$, $2\frac{1}{2}$, $2\frac{3}{4}$, and 3 inches. Do not confuse the engineer's scale with the architect's scale. The engineer's scale uses feet and decimal parts of a foot.



GREEN NOTE

Many homes have green or sustainable features such as solar panels to provide energy or extra insulation to conserve energy, but what makes a home a green home? There are programs to certify homes as green. A green certification program is a set of standards for green building practices that are followed by the building team and verified by an independent third party. These programs usually have a system for awarding points meeting certification standards that, when added up, determine whether the home can be certified as a green home. The two best known national green certification programs are LEED (Leadership in Energy and Environmental Design) and the National Green Building Standard developed by Home Innovation Laboratories and the National Association of Home Builders (NAHB).



USING WHAT YOU LEARNED

Construction drawings are rarely drawn the actual size of what they depict. They are almost always smaller than the actual object. Drawings for buildings are drawn to one of the scales found on an architect's scale. For this reason it is important to understand how to read an architect's scale. If a drawing is made to a scale of $\frac{1}{4}'' = 1'$, what would be the dimension represented by a line $3\frac{3}{8}$ inches long? Each $\frac{1}{4}$ inch represents 1 foot, so 3 inches represents 12 feet. (There are four $\frac{1}{4}$ s in an inch and $3 \times 4 = 12$.) $\frac{3}{8}$ inch is actually 1 and $\frac{1}{2}$ quarters of an inch, so $\frac{3}{8}''$ represents $1\frac{1}{2}'$ or 1' foot 6". 12 feet plus 1 foot six inches is 13 feet 6 inches, normally written as 13'-6".

Assignment

1. What are the dimensions indicated on the scale in **Figure 3-5**?
2. What scales are used for the following views of the duplex? (Refer to the duplex drawings in your textbook packet.)
 - a. Floor plan
 - b. Site plan
 - c. Front elevation
 - d. Typical wall section




Figure 3-5.

Alphabet of Lines

4

That drawings are used in construction for the communication of information has already been discussed in Unit 2. Indeed, drawings serve as a language for the construction industry. The basis for any language is its alphabet. The English language uses an alphabet made up of twenty-six letters. Construction drawings use an *alphabet of lines* (see **Figure 4-1**).

The weight or thickness of lines is sometimes varied to show their relative importance. For example, in **Figure 4-2** notice that the basic outline of the building is heavier than the lines used for the smaller architectural details. This difference in line weight sometimes helps distinguish the basic shape of an object from surface details.

Object Lines

Object lines are used to show the shape of an object. All visible edges are represented by object lines. All the lines in **Figure 4-2** are object lines. Drawings usually include many solid lines that are not object lines, however. Some of these other solid lines are discussed here. Others are discussed later.








(a)		HEAVY SOLID (FOR OBJECT LINES)
(b)		LIGHT SOLID (FOR DIMENSIONS, LEADER, AND EXTENSION LINES)
(c)		DASHED (FOR HIDDEN AND PHANTOM LINES)
(d)		DOT DASH (FOR CENTERLINES)
(e)		DOT DOT DASH (FOR CUTTING PLANES)
(f)		BREAK LINES

Figure 4-1. Alphabet of lines.



Courtesy of Robert C. Kurzon

Figure 4-2. Elevation outlined.

Objectives

After completing this unit, you will be able to identify and understand the meaning of the listed lines:

- Object lines
- Dashed lines (hidden and phantom)
- Extension lines and dimension lines
- Centerlines
- Leaders
- Cutting-plane lines




Figure 4-3. The dashed lines on this foundation plan indicate the footing.

Dashed Lines

Dashed lines have more than one purpose in construction drawings. One type of dashed line, the *hidden line*, is used to show the edges of objects that would not otherwise be visible in the view shown. Hidden lines are drawn as a series of evenly sized short dashes (see **Figure 4-3**). If a construction drawing were to include hidden lines for all concealed edges, the drawing would be cluttered and hard to read. Therefore, only the most important features are shown by hidden lines.

Another type of dashed line is used to show important overhead construction (see **Figure 4-4**). These dashed lines are called *phantom lines*. The objects they show are not hidden in the view—they are simply not in the view. For example, the most practical way to show exposed beams on a living room ceiling may be to show them on the floor plan with phantom lines. Phantom lines are also used to show alternate positions of objects (see **Figure 4-5**). To avoid confusion, the dashed lines may be made up of different weights




Figure 4-4. The dashed lines on this floor plan indicate the edge of the roof overhang.

and different length dashes, depending on the purpose (see **Figure 4-6**).

Extension Lines and Dimension Lines

Extension lines are thin, solid lines that project from an object to show the extent or limits of a dimension. Extension lines do not quite touch the object they indicate (see **Figure 4-7**).

Dimension lines are solid lines of the same weight as extension lines. A dimension line is drawn from one extension line to the next. The dimension (distance between the extension lines) is lettered




Figure 4-5. The dashed lines here are phantom lines to show alternate positions of the double-acting door and the door of the dishwasher.

above the dimension line. On construction drawings, dimensions are expressed in feet and inches. The ends of dimension lines are drawn in one of three ways, as shown in **Figure 4-8**.

Dimensions that can be added together to come up with one overall dimension are called *chain dimensions*.




Figure 4-7. Dimension and extension lines.




Figure 4-6. Different types of dashed lines are used to show different features.




Figure 4-8. Dimension line ends.




Figure 4-9. This centerline indicates that the column is symmetrical, or the same, on both sides of the centerline.

The dimension lines for chain dimensions are kept in line as much as possible. This makes it easier to find the dimensions that must be added to find the overall dimension.

Centerlines

Centerlines are made up of long and short dashes. They are used to show the centers of round or cylindrical objects. Centerlines are also used to indicate that an object is *symmetrical*, or the same on both sides of the center (see **Figure 4-9**). To show the center of a round object, two centerlines are used so that the short dashes cross in the center (see **Figure 4-10**).

To lay out an arc or part of a circle, the radius must be known. The *radius* of an arc is the distance from the center to the edge of the arc. On construction drawings, the center of an arc is shown by crossing




Figure 4-10. When centerlines show the center of a round object, the short dashes of two centerlines cross.




Figure 4-11. Method of showing the radius of an arc.

centerlines. The radius is dimensioned on a thin line from the center to the edge of the arc (see **Figure 4-11**).

Rather than clutter the drawing with unnecessary lines, only the short, crossing dashes of the centerlines are shown. If the centerlines are needed to dimension the location of the center, only the needed centerlines are extended.

Leaders

Some construction details are too small to allow enough room for clear dimensioning by the methods described earlier. To overcome this problem, the




Figure 4-12. Leaders used for dimensioning.

dimension is shown in a clear area of the drawing. A thin line called a *leader* shows where the dimension belongs (see **Figure 4-12**).



GREEN NOTE

There are many ways to wire a house, plumb a bathroom, or frame a house that meet the minimum requirements of building codes. Green building goes beyond the building codes and raises the bar for construction practices to the highest level of quality. Materials that are installed just well enough to meet a building code might not perform efficiently or last as long as those that are installed perfectly. For example, fiberglass insulation that is overstuffed into a wall cavity and has air spaces along the top and bottom may only perform at half the expected insulating value due to the installation defects. Best practices require insulation to be properly installed so that it fits every space snugly without over packing it.




Figure 4-13. A cutting-plane line indicates where the imaginary cut is made and how it is viewed.

Cutting-Plane Lines

It was established earlier that section views are needed to show interior detail. In order to show where the imaginary cut was made, a *cutting-plane line* is drawn on the view through which the cut was made (see **Figure 4-13**). A cutting-plane line is usually a heavy line with long dashes and pairs of short dashes. Some drafters, however, use a solid, heavy line. In either case, cutting-plane lines always have some identification at their ends and arrowheads to indicate the direction from which the section is viewed. Cutting-plane-line identification symbols are discussed in the next unit.

Some section views may not be referenced by a cutting-plane line on any other view. These are *typical sections* that would be the same if drawn from an imaginary cut in any part of the building (see **Figure 4-14**).




Figure 4-14. Building section.



USING WHAT YOU LEARNED

On very simple drawings, it is usually easy to understand what each line represents, but on complex drawings, conveying a lot of information, there can be many types of lines, each with a different meaning. Look at the Site Plan for the Two-Unit Apartment. Why would some of the lines representing the building be much heavier than the lines across the middle of the building? What kinds of lines are these? The bold lines are object lines showing the basic shape and location of the building as viewed from above. The thinner lines are not part of the basic building outline. However, because this building is two dwelling units, the drafter has used these thinner lines to show how the building is divided. A better practice might have been to have used dashed hidden lines to show the division, because they cannot be seen from above the building.

Assignment

Refer to the drawings of the Two-Unit Apartment in your textbook packet. For each of the lines numbered A5.1 through A5.10, identify the kind of line and briefly describe its purpose on these drawings.

The broad arrows with A5 numbers are for use in this assignment.

Example: A5.E, object line, shows the end of the building.

Use of Symbols

5 UNIT

An alphabet of lines allows for clear communication through drawings; the use of standard symbols makes for even better communication. Many features of construction cannot be drawn exactly as they appear on the building. Therefore, standard symbols are used to show various materials, plumbing fixtures and fittings, electrical devices, windows, doors, and other common objects. Notes are added to drawings to give additional explanations.

It is not important to memorize all the symbols and abbreviations used in construction before you learn to read drawings. There are commonly accepted standards for architectural symbols, but many architects and drafters use their own variations of standard symbols. Even so, with very little practice, you can develop the ability to interpret the symbols that are commonly used on construction drawings, whether standard or a variation. Typically, an architectural symbol is a simplified picture of the material or item it represents. In many cases, the material represented by a symbol is also labeled with words or abbreviations. Some of the most common symbols are shown in this chapter and additional symbols are shown in the Appendix.

Door and Window Symbols

Door and window symbols show the type of door or window used and the direction the door or window opens. There are three basic ways for household doors to open—swing, slide, or fold (see **Figure 5-1**). Within each of these basic types




Figure 5-1. Types of doors and their plan symbols.

Objectives

After completing this unit, you will be able to identify and understand the meaning of the listed symbols:

- Door and window symbols
- Materials symbols
- Electrical and mechanical symbols
- Reference marks for coordinating drawings
- Abbreviations




Figure 5-2. Window symbols.

there are variations that can be readily understood from their symbols. The direction a swing-type door opens is shown by an arc representing the path of the door.

There are seven basic types of windows. They are named according to how they open (see **Figure 5-2**). The symbols for hinged windows—*awning*, *casement*, and *hopper*—indicate the direction they open. In elevation, the symbols include dashed lines that come to a point at the hinged side, as viewed from the exterior.

The sizes of windows and doors are usually shown on a special window schedule or door schedule, but they might also be indicated by notes on the plans near their symbols. Door and window schedules are explained later. The notations of size show width first and height second. Manufacturers' usually list several sets of dimensions for every window model (see **Figure 5-3**). The glass size indicates the area that will actually allow light to pass. The rough opening size is important for the carpenter, who will frame the wall into which the window will be installed. The masonry opening is important to masons. The notations on plans and schedules usually

indicate nominal dimensions. A *nominal dimension* is an approximate size and may not represent any of the actual dimensions of the unit. Nominal dimensions are usually rounded off to whole inches or feet and inches and are used only as a convenient way to refer to the window or door size. The actual dimensions should be obtained from the manufacturer before construction begins.

Material Symbols

The drawing of an object shows its shape and location. The outline of the drawing may be filled in with a material symbol to show what the object is made of (see **Figure 5-4**). Many materials are represented by one symbol in elevations and another symbol in sections. Examples of such symbols are concrete block and brick. Other materials look pretty much the same when viewed from any direction, so their symbols are drawn the same in sections and elevations.



GREEN NOTE

Life Cycle Assessment (LCA), also called cradle-to-grave assessment, is a technique to evaluate or assess all of the environmental impacts involved with the harvesting, mining, or manufacture; transportation; use; repair, and maintenance; and eventual disposal of a product. This analysis can be used to help determine which materials are most advantageous for a green home project.




Figure 5-3. Windows and doors can be measured in several ways.

When a large area is made up of one material, it is common to only draw the symbol in a part of the area (see **Figure 5-5**). Some drafters simplify this even further by using a note to indicate what material is used and omitting the symbol altogether.

Electrical and Mechanical Symbols

The electrical and mechanical systems in a building include wiring, electrical devices, piping, pipe fittings, plumbing fixtures, registers, and heating and air conditioning ducts. It is not practical to draw these items as they would actually appear, so standard symbols have been devised to indicate them.

The electrical system in a house includes wiring as well as devices such as switches, receptacles,




Figure 5-4. Material symbols.




Figure 5-5. Only part of the area is covered by the brick symbol, although the entire building will be brick.

light fixtures, and appliances. Wiring is indicated by lines that show how devices are connected. These lines are not shown in their actual position. They simply indicate which switches control which lights, for example. Outlets (receptacles) and switches are usually shown in their approximate positions. Major fixtures and appliances are shown in their actual positions. A few of the most common electrical symbols are shown in **Figure 5-6**.

Mechanical systems—plumbing and HVAC (heating, ventilating, and air conditioning)—are not usually shown in much detail on drawings for single-family homes. However, some of the most important features may be shown. Piping is shown by lines; different types of lines represent different kinds of piping. Symbols for pipe fittings are the same basic shape as the fittings they represent. A short line, or *hash mark*, represents the joint between the pipe and the fitting. Plumbing fixtures are






















	CONVENIENCE OUTLET WP INDICATES WEATHERPROOF	
	RANGE OUTLET	
S OR S ₃ (3-WAY)	WALL SWITCH	
 OR 	CEILING LIGHT FIXTURE	
	WALL LIGHT FIXTURE	
	FLUORESCENT LIGHT FIXTURE	
 OR  SD	SMOKE DETECTOR	
	THERMOSTAT	
	WATER HEATER	
	POWER PANEL	

Figure 5-6. Some common electrical symbols.


















drawn pretty much as the actual fixture appears. A few plumbing symbols are shown in **Figure 5-7**.

Reference Marks

A set of drawings for a complex building may include several sheets of section and detail drawings. These sections and details do not have much meaning without some way of knowing what part of the building they are meant to show. Callouts, called *reference marks*, on plans and elevations indicate where details or sections of important features have been drawn. To be able to

use these reference marks for coordinating drawings, you must first understand the numbering system used on the drawings. The simplest numbering system for drawings consists of numbering the drawing sheets and naming each of the views. For example, Sheet 1 might include a site plan and foundation plan; Sheet 2, floor plans; and Sheet 3, elevations.

On large, complex sets of drawings, the sheets are numbered according to the kind of drawings shown. Architectural drawing sheets are numbered A-1, A-2, and so on for all the sheets. Electrical drawings are

	VALVE	
	90° ELBOW	
	45° ELBOW	
	WYE	
	TEE	
	UNION	
	SOIL WASTE (BELOW GRADE)	
	SOIL WASTE (ABOVE GRADE)	
	COLD WATER	
	HOT WATER	
	GAS	

PIPING SYMBOLS

Figure 5-7. Some common plumbing symbols.

numbered E-1, E-2, and E-3. A view number identifies each separate drawing or view on the sheet. **Figure 5-8** shows drawing 5 on Sheet A-4.

Because most of the drawings for a single-family home are architectural, and the drawing set is fairly small, letters indicating the type of drawing may not be included. Instead, the views are numbered, and a second number shows on which sheet it appears. For example, the fourth drawing on the third sheet would be 4/3, 4.3, or 4-3.

Numbering each view and the sheet on which it appears makes it easy to reference a section or detail to another drawing. The identification of a section view

is given with the cutting-plane line showing where it is taken from. For example, the section view shown in **Figure 5-9** shows the fireplace at the cutting-plane line in **Figure 5-10**. Notice that the cutting-plane line in **Figure 5-10** indicates that the section is viewed from the top of the page toward the bottom, with the fireplace opening on the right. That is how the section view in **Figure 5-9** is drawn. This numbering system is also used for details that cannot be located by a cutting-plane line. The drawing in **Figure 5-11** is a *typical wall section*, meaning that it is typical of a section view of any outside wall. This typical wall section




Figure 5-8. This is drawing 5 on Sheet A-4.




Figure 5-9. This section view is drawing 2 on Sheet 5.

includes a callout referencing a detail drawing of the roof cornice or eave. The cornice detail is Drawing 4 on Sheet A-4 and is shown in **Figure 5-12**. Notice that the detail faces the opposite direction from the typical wall section. That is because, being a typical section, not a specific section, it represents all exterior walls regardless of the direction they face.

Abbreviations

Drawings for construction include many notes and labels of parts. These notes and labels are usually abbreviated as much as possible to avoid crowding the drawing. The abbreviations used on drawings are usually a shortened form of the word and are easily understood. For example, BLDG stands for building. The abbreviations used throughout this textbook and on the related drawings are defined in the Appendix.




Figure 5-10. Plan for fireplace detailed in Figure 5-9.




Figure 5-11. The detail of this cornice is shown in drawing 4 on Sheet A-4, Figure 5-12.




Figure 5-12. This is the detail of the cornice in Figure 5-11.



USING WHAT YOU LEARNED

Construction drawings use many symbols to represent various materials and devices. Usually, one of the first pages in the drawing set includes an index of the symbols used on the drawings, but sometimes the most common symbols are not included in the index. To be able to read all of the information on the drawings, you must be able to interpret these symbols. For example, what is the framing material shown in **Figure 5-8**? The two rectangles with Xs drawn from corner to corner are dimensional lumber. Based on the proportions of width and thickness, they are probably 2x4s. Between the 2x4s is a piece of plywood.


Assignment

1. What is represented by each of these symbols?

a.



b.



c.



d.




e.



f.



g.



h.

S₃

i.



j.



2. What is meant by each of these abbreviations?

a. GYP. BD.

b. FOUND.

c. FIN. FL.

d. O.C.

e. REINF.

f. EXT.

g. COL.

h. DIA.

i. ELEV.

j. CONC.

3. Where in a set of drawings would you find a detail numbered 6.4?

4. Where in a set of drawings would you find a detail numbered 5/M-3?

Plan Views

6 UNIT

You learned earlier in Unit 2 that plans are drawings that show an object as viewed from above. Many of the detail and section drawings in a set show parts of the building from above. Some of the plan views that show an entire building are discussed here. This brief explanation will help you feel more comfortable with plans, although it does not cover plans in depth. You will use plans frequently throughout your study of the remainder of this textbook. Each of the remaining units helps you understand plan views more thoroughly.

Site Plans

A *site plan* gives information about the site on which the building is to be constructed. The boundaries of the site (property lines) are shown. The property line is usually a heavy line with one or two short dashes between longer line segments. The lengths of the boundaries are noted next to the line symbol. Property descriptions are usually the result of a survey by a surveyor. Surveyors and engineers usually work with decimal parts of feet, rather than feet and inches. Therefore, site dimensions are usually stated in tenths or hundredths of feet (see **Figure 6-1**).




Figure 6-1. Minimum information shown on a site plan.

Objectives

After completing this unit, you will be able to describe the general kinds of information shown on the listed plans and how that information applies to a building project:

- Site plans
- Foundation plans
- Floor plans

A symbol or north arrow of some type indicates what compass direction the site faces. Unless this north arrow includes a correction for the difference between true north and magnetic north, it may be only an approximation. However, it is sufficient to show the general direction the site faces.

The site plan also indicates where the building is positioned on the site. At a minimum, the dimensions to the front and one side of the site are given. The overall dimensions of the building are also included. Anyone reading the site plan will have this basic information without having to refer to the other drawings. If the finished site is to include walks, drives, or patios, these are also described by their overall dimensions. Site plans often show other information, such as the slope or contour of the site and the locations of utilities. These are discussed in a later unit.

Foundation Plans

A foundation plan is like a floor plan, but instead of showing the living spaces, it shows the foundation walls and any other structural work to be done below the living spaces.

Two types of foundations are commonly used in homes and other small buildings. One type has a concrete base, called the **footing**, supporting foundation walls (see **Figure 6-2**). The other is the slab-on-grade type. A **slab-on-grade** foundation consists of a concrete slab placed directly on the soil with little or no other

support. Slabs-on-grade are usually thickened at their edges and wherever they must support a heavy load (see **Figure 6-3**).

When the footing-and-wall-type foundation is used, girders are used to provide intermediate support to the structure above (see **Figure 6-4**). The girder is




Figure 6-2. Footing and foundation wall.




Figure 6-3. Slab-on-grade foundation.




Figure 6-4. A girder provides intermediate support between the foundation walls.

shown on the foundation plan by phantom lines and a note describing it.

The foundation plan includes all the dimensions necessary to lay out the footings and foundation walls. The footings follow the walls and may be shown on the plan. If they are shown, it is usually by means of hidden lines to show their outline only. In addition to the layout of the foundation walls, dimensions are given for opening windows, doors, and ventilators. Notes on the plan indicate areas that are not to be excavated, concrete-slab floors, and other important information about the foundation (see **Figure 6-5**).

Floor Plans


A floor plan is similar to a foundation plan. It is a section view taken at a height that shows the placement of walls, windows, doors, cabinets, and other important

features. A separate floor plan is included for each floor of the building. The floor plans provide more information about the building than any of the other drawings.

Building Layout

The floor plans show the locations of all the walls, doors, and windows. Therefore, the floor plans show how the building is divided into rooms and how to get from one room to another. Before attempting to read any of the specific information on the floor plans, it is wise to familiarize yourself with the general layout of the building.

To quickly familiarize yourself with a floor plan, imagine that you are walking through the house. For example, imagine yourself standing in the front door of the left side of the Duplex—plans for which are included in the drawing packed with this text. You are



Courtesy of Home Planners, Inc.

Figure 6-5. Foundation plan.

looking across the living room. There is a closet on your right and a large window on your left. Straight ahead is the dining room with doors into a storage room and the kitchen. Looking in the kitchen doorway (notice there is no door in this doorway), you see cabinets, a sink, and a refrigerator on the opposite wall. More cabinets and a range are located on the left. Now, walk out of the kitchen and into the bedroom area. There are three doors: one leads into a large front bedroom with a long closet, another opens into a smaller bedroom, and the third opens into the bathroom. The bathroom includes a linen closet with bifold doors.

Dimensions

Dimensions are given for the sizes and locations of all walls, partitions, doors, windows, and other important features. On frame construction, exterior walls are usually dimensioned to the outside face of the wall framing. If the walls are to be covered with stucco or masonry veneer, this material is outside the dimensioned face of the wall frame. Interior partitions may be dimensioned to either face of the studs. (**Studs** are the vertical members in a wall frame.) Windows and doors may be dimensioned about their centerlines (see **Figure 6–6**) or to the edges of the openings.

Solid masonry construction is dimensioned entirely to the face of the masonry (see **Figure 6–7**). Masonry openings for doors and windows are dimensioned to the edge of the openings.



GREEN NOTE

It would be difficult to say exactly when green building began. Some practices, such as using local and renewable materials or passive solar design, date back millennia. The modern green building movement arose out of the need and desire for more energy efficient and environmentally friendly building practices, which began with the environmental movement of the 1960s. In the 1970s, drastically rising oil prices also spurred significant research and activity to improve energy efficiency and find renewable energy sources and, as a result, led to the earliest experiments with contemporary green building.

A few early milestones in the United States include:

- American Institute of Architects (AIA) formed the Committee on the Environment (1989).
- Environmental Resource Guide published by AIA, funded by U.S. Environmental Protection Agency (EPA) (1992).
- EPA and the U.S. Department of Energy launched the ENERGY STAR program (1992).
- First local green building program introduced in Austin, Texas (1992).
- U.S. Green Building Council (USGBC) founded (1993).




Figure 6–6. Frame construction dimensioning.




Figure 6-7. Masonry construction dimensioning.

Other Features of Floor Plans

The floor plan includes as much information as possible without making it cluttered and hard to read. Doors and windows are shown by their symbols, as explained in Unit 5. Cabinets are shown in their proper positions. The cabinets are explained further by cabinet elevations and details, which are discussed in Unit 8. If the

building includes stairs, these are shown on the floor plan. Important overhead construction is also indicated on the floor plans. If the ceiling is framed with joists, their size, direction, and spacing may be shown on the floor plan. Architectural features such as exposed beams, arches in doorways, or unusual roof lines are shown by phantom lines.



USING WHAT YOU LEARNED

A lot of information is shown on plan views. For example, carpenters use floor plans extensively to lay out walls, windows, and doors. This way, they can answer such questions as how far the edge of the 3'-6" opening is from the dining room into the kitchen from the inside face of the north wall of the building. Finding the answer involves a few steps.

First, find the north arrow on the site plan to determine that the north wall is the one at the top of the floor plan. Now look at the dimensions at either end of the floor plan to see that the kitchen side of the wall separating the living room and the kitchen is 11'-4 $\frac{1}{4}$ " from the inside face of the north wall. Now looking in the dining room we see that the north side of the opening is 2'-8" plus 3'-6" from the face of the living room–kitchen wall. Subtract 6'-2" from 11'-4 $\frac{1}{4}$ " to find that the dimension we are looking for is 5'-2 $\frac{1}{4}$ ".

Assignment

Refer to the drawings for the Two-Unit Apartment (which are included in your textbook packet) to complete this assignment.

1. In what direction does the apartment face?
2. What is the length and width of the apartment site?
3. How far is the front of the apartment from the front property line?
4. What is the overall length and width of the apartment?
5. What are the inside dimensions of the living room?
6. What is the thickness of the partitions between the two bedrooms?
7. What is the thickness of the interior wall between the two dining rooms?
8. With two exceptions, the units in the apartment are exactly reversed. What are the two exceptions?
9. What is the distance from the west end of the apartment to the centerline of the west front entrance?
10. What is indicated by the small rectangle on the floor plan outside each main entrance?
11. What is the distance from the ends of the apartment to the centerlines of the 6⁰/6⁸ sliding glass doors?
12. What is indicated by the dashed line just outside the front and back walls on the floor plan of the apartment?

Elevations

7

UNIT

Drawings that show the height of objects are called *elevations*. However, when builders and architects refer to building elevations, they mean the exterior elevation drawings of the building (see **Figure 7-1**). A set of working drawings usually includes an elevation of each of the four sides of the building. If the building is very complex, there may be more than four elevations. If the building is simple, there may be only two elevations—the front and one side.




Figure 7-1. Building elevations.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Orient building elevations to building plans.
- Describe the kinds of information shown on elevations.

Orienting Elevations

It is important to determine the relationship of one drawing to another. This is called *orienting* the drawings. For example, if you know which elevation is the front, you must be able to picture how it relates to the front of the floor plan.

Elevations are sometimes named according to compass directions (see **Figure 7-2**). The side of the house that faces north is the north elevation, and the side that faces south is the south elevation, for example. When the elevations are named according to compass direction, they can be oriented to the floor plan, foundation plan, and site plan by the north arrow on those plans. It might help to label the edge of the plans according to the north arrow (see **Figure 7-3**).

Labeling elevations according to compass direction is not always possible. When drawings are prepared to be sold through a catalog, or when they are for use on several sites, the compass directions cannot be included. In this case, the elevations are named according to their position as you face the building (see **Figure 7-4**). To orient these elevations to the plans, find the front on the plans. The front is usually at the bottom



GREEN NOTE

One of the earliest green practices designers and builders discovered was that by facing the building in the best direction, they could take advantage of natural heating and cooling. If the side with the most window area faces west, the afternoon sun will add considerable heat to the building. This can help heat the building in cold weather—but it can also add to the cooling load during the warm months. Designers have learned to both take advantage of these factors as well as adapt to them when planning buildings that use less energy.

of the floor plan, but it can be checked by the location of the main entrance.

Information on Building Elevations

Building elevations are normally quite simple. Although the elevations do not include a lot of detailed





Figure 7-2. Elevations are usually named according to their compass directions.



Courtesy of Robert C. Kurzon.

Figure 7-3. Plan labeled to help orientation to north arrow.




Figure 7-4. Elevations can be named according to their relative positions.




Figure 7-5. Underground portion of the building is shown with dashed lines.

dimensions and notes, they show the finished appearance of the building better than other views. Therefore, elevations are a great aid in understanding the rest of the drawing set.

The elevations show most of the building, as it will actually appear, with solid lines. However, the underground portion of the foundation is shown as hidden lines (see **Figure 7-5**). The footing is shown as a rectangle of dashed lines at the bottom of the foundation walls.

The surface of the ground is shown by a heavy solid line, called a grade line. The *grade line* might include one or more notes to indicate the elevation above sea level or another reference point (see **Figure 7-6**). Elevation used in this sense is altitude, or height—not a type of drawing. All references to the height of the ground or the level of key parts of the building are in terms of elevation. Methods for measuring site elevations are discussed in Unit 9.




Figure 7-6. The elevation of this site is 150 feet.

Some important dimensions are included on the building elevations. Most of them are given in a string at the end of one or more elevations (see **Figure 7-7**). The dimensions most often included are listed here:

- Thickness of footing
- Height of foundation walls
- Top of foundation to finished first floor
- Finished floor to ceiling or top of plate (The **plate** is the uppermost framing member in the wall.)
- Finished floor to bottom of window headers (The **headers** are the framing across the top of a window opening.)
- Roof overhang at eaves




Figure 7-7. Dimensions on an elevation.



USING WHAT YOU LEARNED

The building elevations are often the best drawings for a quick picture of what the finished building will look like. They also convey a lot of useful information in the construction of a building.

One requirement sometimes found in zoning ordinances is a limit on the overall height of a building. What is the height of the ridge of the two-unit apartment above the finished grade? This information is shown at the right end of each of the building elevations. The finished floor is 6 inches above the finished grade. The top of the wall plate is 7'-11 1/2" above the finished floor. The top of the roof (i.e., top of truss) is 4'-6" above the top of the plate. All of these added together, 12'-11 1/2" is the overall height of the building.

Assignment

Refer to the drawings of the Two-Unit Apartment in your textbook packet to complete this assignment.

1. Which elevation is the north elevation?
2. In what compass direction does the left end of the apartment face?
3. What is the dimension from the surface of the floor to the top of the wall framing?
4. What is the overall height of the building above the finished grade?
5. How far does the foundation project above the ground?
6. How far below the surface of the ground does the foundation wall extend?
7. What is the total height of the foundation walls?
8. What is the minimum depth of the bottom of the footings?

Sections and Detail

8

UNIT

It is not possible to show all the details of construction on foundation plans, floor plans, and building elevations. Those drawings are meant to show the relationships of the major building elements to one another. To show how individual pieces fit together, it is necessary to use larger-scale drawings and section views. These drawings are usually grouped together in the drawing set. They are referred to as **sections** and **details** (see **Figure 8–1**).



GREEN NOTE

The fill under the concrete slab in the Two-Unit Apartment in your textbook packet is run-of-bank (ROB) gravel. Many slabs are placed on crushed stone, but by using ROB gravel, the apartment reduces the impact on the environment. The gravel does not require running a stone crusher and grader, which consumes energy and emits stone dust into the atmosphere. The gravel may be available more locally than crushed stone, thereby reducing the need to transport it from any great distance.

Sections

Nearly all sets of drawings include, at least, a typical wall section. The typical section may be a section view of one wall, or it may be a full section of the building. Full sections are named by the direction in which the imaginary cut is made. **Figure 8–2** shows a transverse section. A *transverse section* is taken from an imaginary cut across the width of the building. Transverse sections are sometimes called *cross sections*. A full section taken from a lengthwise cut through the building is called a *longitudinal section* (see **Figure 8–3**).

Full sections and wall sections normally have only a few dimensions but have many notes with leaders to identify the parts of the wall. The following is a list of the kinds of information that are included on typical wall sections with most sets of drawings:

- Footing size and material (This is specified by building codes.)
- Foundation wall thickness, height, and material
- Insulation, waterproofing, and interior finish for foundation walls
- Fill and waterproofing under concrete floors
- Concrete floor thickness, material, and reinforcement

Objectives

After completing this unit, you will be able to perform the following tasks:

- Find information shown on section views.
- Find information shown on large-scale details.
- Orient sections and details to the other plans and elevations.







Figure 8-1. Typical sheet of sections and details for a small building.

Courtesy of Robert C. Kurzon.



Courtesy of Robert C. Kurzon.

Figure 8-2. Transverse section.




Figure 8-3. Longitudinal section.

- Sizes of floor framing materials
- Sizes of wall framing materials
- Wall covering (sheathing, siding, stucco, masonry, and interior wall finish) and insulation
- Cornice construction—materials and sizes (The **cornice** is the construction at the roof eaves.)
- Ceiling construction and insulation

Other section drawings are included as necessary to explain special features of construction. Wherever wall construction varies from the typical wall section, another wall section should be included. Section views are used to show any special construction that cannot be shown on normal plans and elevations. **Figure 8-4** is an example of a special section in elevation. This section view is said




Figure 8-4. Special section of ventilated ridge.




Figure 8-5. A section in plan.

to be in elevation because it shows the height of the ridge construction. **Figure 8-5** is in plan because it shows the interior of the fireplace as viewed from above.

Other Large-Scale Details

Sometimes necessary information can be conveyed without showing the interior construction. A large scale may be all that is needed to show the necessary details. The most common examples of this are on

cabinet installation drawings (see **Figure 8-6**). Cabinet elevations show how the cabinets are located, without showing the interior construction.

Many details are best shown by combining elevations and sections or by using isometric drawings. **Figure 8-7** shows an example of an elevation and a section used together to explain the construction of a fireplace. **Figure 8-8** shows an isometric detail drawing that includes sections to show interior construction.




Figure 8-6. Cabinet elevations.




Figure 8-7. Fireplace details.

Courtesy of W. D. Farmer.




Figure 8–8. Isometric section.



GREEN NOTE

When frame construction was first developed, horizontal or diagonal boards were applied as sheathing. After World War II, plywood replaced board sheathing. Today Oriented Strand Board (OSB) is the most commonly used sheathing material, but other engineered products are becoming increasingly popular. Gypsum-based structural sheathing and magnesium oxide structural sheathing are water resistant, decay resistant, and form a vapor barrier, eliminating the need for a separate moisture barrier.


Orienting Sections and Details

As explained earlier, some sections and details are labeled as typical. These drawings describe the construction that is used throughout most of the building.

Sections and details that refer to a specific location in the building include a reference that indicates


where the section or detail came from. That larger source drawing has a cutting-plane line to show exactly where the section cut or detail is taken from. The cutting-plane line has an arrowhead or some other indication of the direction from which the detail is viewed. The top drawing in **Figure 8–9** shows that there is a section view or detail of the construction at the skylight. The little flag at the top points to the right, so that is the direction from which the detail at the bottom of the figure is viewed. The label on the bottom drawing, the skylight detail, includes the number of the drawing, corresponding to the number indicated at the cutting-plane line in the top view. A reference mark near the arrow indicates where the detail drawing is shown. The reference marks that are used for orienting details may vary from one set of drawings to another. It is important, although not usually difficult, to study the drawings and learn how the architect references details. Usually a system of sheet numbers and view numbers is used. One such numbering system was explained earlier.

Some basic principles of details and sections have been discussed here. You will gain more practice later in reading details and sections.



NORTH ELEVATION

1/4" = 1' - 0"



SKYLIGHT DETAIL

3/8" = 1' - 0"



Courtesy of Robert C. Kurzon.

Figure 8-9. The elevation at the top indicates that the construction detail is drawing 2 on Sheet 7. The bottom drawing is that detail.



USING WHAT YOU LEARNED

A lot of information can be found on the various section views and detail drawings. Some of this is shown simply by drawing a symbol and adding a note or callout. Any material that is to be placed beneath a concrete slab or imbedded in the slab must be in place before the concrete is delivered. Beneath the concrete slab in the Two-Unit Apartment in your textbook packet there is rigid foam insulation. What is immediately beneath the insulation? The exterior wall section on Sheet 2 has a callout and a leader pointing to a line of long dashes. The callout identifies this as 6 mil poly vapor barrier.


Assignment

Refer to the drawings of the Two-Unit Apartment in your textbook packet to complete the assignment.

1. What is used to show the detail of a complex design, installation, or product?
2. What kind of section drawing is the Typical Section on Sheet 1?
3. What kind and size material is to be used for the foundation walls?
4. What material is immediately beneath the outer two feet of the concrete slab?
5. What kind and size of insulation is used around the foundation? Is this insulation used on the inside or outside of the foundation?
6. What kind and size of material is to be used on the inside face of the frame walls?
7. Sheet 2 includes a firewall detail. Where in the apartment is this firewall?
8. What is the distance between the centerlines of the studs in the firewall?
9. What is the total thickness of the firewall? (Remember that a 2×6 is actually $5\frac{1}{2}$ " wide.)
10. Were the cabinet elevations drawn of the kitchen on the east side or the west side of the Two-Unit Apartment?
11. How would the kitchen elevations be different if they were drawn from the other kitchen?
12. What is the distance from the kitchen counter top to the bottom of the wall cabinets?
13. How far does the roof overhang project beyond the exterior walls?
14. Where is the electrical panel located for the west apartment?

Test 2

A. Identify each of the dimensions indicated on the illustrated scale.



B. Which occupation or individual listed in Column II performs the task listed in Column I?

- | I | II |
|--|----------------------------------|
| 1. Obtains a building permit | a. Architect |
| 2. Issues the building permit | b. Building inspector |
| 3. Acts as the owner's representative | c. Owner |
| 4. Issues certificate of occupancy | d. Mechanical engineer |
| 5. Lays out rooms for efficient use | e. Municipal building department |
| 6. Designs plumbing in large buildings | f. General contractor |
| 7. Hires and supervises carpenters | |
| 8. Checks to see that codes are observed | |











C. Which of the lines shown in Column II is most likely to be used for each purpose in Column I?

- I
1. Outline of a window
 2. Alternate position of a fold-down countertop
 3. Centerline of a round post
 4. Extension line to show extent of a dimension
 5. Buried footing
 6. Point at which an imaginary cut is made for a section view

- II
- a. _____
 - b. _____
 - c. _____
 - d. _____
 - e. _____
 - f. _____

D. Which of the symbols shown in Column II is used for each of the objects or materials in Column I?

- I
1. Awning window in elevation
 2. Bifold door in plan
 3. Earth
 4. Dimension lumber
 5. Batt insulation
 6. Concrete
 7. Ceiling light fixture
 8. Finish wood
 9. Shutoff valve (plumbing)
 10. Hopper window in elevation


- II
- a. 
 - b. 
 - c. 
 - d. 
 - e. 
 - f. 
 - g. 
 - h. 
 - i. 
 - j. 

E. Select the one best answer for each question.

1. What kind of regulation controls the types of buildings allowed in each part of a community?
 - a. building code
 - b. zoning law
 - c. specification
 - d. certificate of occupancy
2. Which of the listed kinds of information can be clearly shown on construction drawings?
 - a. size of parts
 - b. location of parts
 - c. shape of parts
 - d. all of these


3. What type of drawing is the 2 × 4 shown in Illustration 3?

- a. isometric
- b. oblique
- c. perspective
- d. none of these




4. What type of drawing is the 2 × 4 shown in Illustration 4?

- a. isometric
- b. oblique
- c. perspective
- d. none of these




5. What type of drawing is the 2 × 4 shown in Illustration 5?

- a. isometric
- b. oblique
- c. perspective
- d. none of these




6. What kind of drawing is shown in Illustration 6?

- a. elevation
- b. detail
- c. rendering
- d. plan




7. What kind of drawing is shown in Illustration 7?

- a. elevation
- b. detail
- c. rendering
- d. plan



8. What kind of drawing is shown in Illustration 8?


- a. elevation
- b. detail
- c. rendering
- d. plan



9. If an object 12 feet long is drawn at a scale of $\frac{1}{4}'' = 1'-0''$, how long is the drawing?
 - a. 48 inches
 - b. 3 inches
 - c. 3 feet
 - d. none of these
10. If an object 1'-6" long is drawn at a scale of $1\frac{1}{2}'' = 1'-0''$, how long is the drawing?
 - a. $2\frac{1}{4}$ inches
 - b. 2 inches
 - c. 27 inches
 - d. none of these
11. Where in a set of drawings would you find detail number 9.6?
 - a. sheet 6
 - b. sheet 9
 - c. ninth sheet in the mechanical section
 - d. none of the above
12. In the drawing key 4/A-4, what does the letter A stand for?
 - a. architect's initial
 - b. first edition of the drawings
 - c. architectural
 - d. first detail on the sheet
13. On which drawing would you expect to find the height of the foundation wall?
 - a. site plan
 - b. building elevation
 - c. floor plan
 - d. foundation plan
14. On which drawing would you expect to find the setback of the building?
 - a. site plan
 - b. building elevation
 - c. floor plan
 - d. foundation plan
15. On which drawing would you expect to find the height of the window heads?
 - a. site plan
 - b. building elevation
 - c. floor plan
 - d. window detail

F. Refer to the Two-Unit Apartment drawings in your textbook packet to answer these questions.

1. How far is the building from the west boundary?
2. What is the dimension from the finished floor to the top of the wall plate?
3. What is the overall length of the building at window height?
4. What is the overall length of the building at the eaves?
5. What is the north-to-south dimension inside the front bedrooms?
6. What is the slope of the roof?
7. What types of windows are used in the bedrooms?
8. How thick is the concrete footing?
9. What material is the foundation wall?
10. What is under the floor at its center?



READING DRAWINGS: LAKE HOUSE

In Part 2, you will examine all the information necessary to build a moderately complex single-family home. The sequence of the units in Part 2 follows the sequence of actual construction. In some cases, all the information necessary for a particular stage of construction can be found on one sheet of drawings. Other stages require cross-referencing among several drawings. The relationships among the various drawings are discussed as the need to cross-reference them arises.

The assignments in this part refer to the Lake House drawings provided in your drawing packet. This Lake House was designed as a vacation home on a lake. The design is moderately complex, involving several floor levels and some interesting construction techniques.

UNIT 9

Clearing and Rough Grading the Site

Objectives

After completing this unit, you will be able to perform the following tasks:

- Identify work to be included in clearing a building site according to site plans.
- Interpret contour lines and grading indications on a site plan.
- Interpolate unspecified site elevations.

Property Boundary Lines

The boundary lines of the building site are shown on the site plan. The direction of a property line is usually expressed as a bearing angle. The *bearing* of a line is the angle between the line and north or south. Bearing angles are measured from north or south depending on which keeps the bearing under 90° (see **Figure 9-1**). Angles are expressed in degrees ($^\circ$), minutes ($'$), and seconds ($''$). There are 360 degrees in a complete circle, 60 minutes in a degree, and 60 seconds in a minute.

The *point of beginning* (POB) may or may not be shown on the site plan. If the point of beginning is not shown on the plan, start at a convenient corner. Corners are usually marked with an *iron pin* (IP) or some permanent feature. The approximate direction of the boundaries can be found with a handheld




Figure 9-1. Bearing angles are always less than 90° .

compass. This approximation should be accurate enough to aid in finding the marker (iron pin, manhole cover, concrete marker, or similar item) at the next corner. Proceed around the perimeter in this manner to find all corners. All construction activity and debris should be kept within the property boundaries unless permission is first obtained from neighboring landowners.

Clearing the Site

The first step in actual construction is to prepare the site. This means clearing any brush or trees that are not to be part of the finished landscape. The architect's choice of trees to remain is based on consideration of many factors. Trees and other natural features can be an important part of architecture—not only for their natural beauty but for energy conservation. For example, deciduous trees, which lose their leaves in the winter, can be used to effectively control the solar energy striking a house during warmer months as shown in **Figure 9-2**, where the trees shade the south side of the house. In the winter, the sun shines through the deciduous trees on the south side of a house, thus taking advantage of this source of heat as shown in **Figure 9-3**. The Lake House in your drawing package offers a good example of the importance of the selection of trees to remain on a site. This house gets a large part of its heat from its passive-solar features, which are described more fully later.

Trees that are to be saved are shown on the plot plan by a symbol and a note indicating their butt diameter and species (see **Figure 9-4**). Areas that are too densely wooded to show individual trees are outlined and marked "woods" (see **Figure 9-5**). Removal of unwanted trees may require felling and stump removal, or may be accomplished with a bulldozer and dump truck. In either case, care must be exercised not to damage the trees that are to be saved.

Grading

Grading refers to moving earth away from high areas and into low areas. Site grading is necessary to ensure that water drains away from the building properly and does not puddle or run into the building. In some cases, grading may be necessary for access to the site. For example, if the site has a steep grade, it may be necessary to provide a more gradual slope for a driveway.




Figure 9-2. The summer sun is shaded by deciduous trees.




Figure 9-3. The winter sun passes through deciduous trees.



Figure 9-4. Typical note and symbol for individual tree.




Figure 9-5. Typical note and symbol for wooded area.



GREEN NOTE

Surface water must be controlled in order to prevent erosion of the building site or neighboring property. Surface water should not be allowed to collect in puddles or overly damp areas of earth, as these can promote mosquito breeding and harm the growth of desirable vegetation. Proper grading of the site is the most effective way of controlling surface water. Some type of barrier should be placed prior to finished grading to prevent construction waste water from washing onto adjoining property. Hay bales are often used for this purpose.

Grade is measured in vertical feet from sea level or from a fixed object such as a manhole cover. This vertical distance is called **elevation**. The term *elevation* to denote a vertical position should not be confused with elevation drawings that show the height of objects. The elevations of specific points are given as *spot elevations*. Spot elevations are used to establish points in a driveway, a walk, or the slope of a terrace, as shown in **Figure 9-6**. Spot elevations are often given for trees that are to be saved.

The grade of a site is shown by **topographic contour lines**. These are lines following a particular elevation. The vertical difference between contour lines

is the **vertical contour interval**. For plot plans this is usually 1 or 2 feet. When the land slopes steeply, the contour lines are closely spaced. When the slope is gradual, the contour lines are more widely spaced.

The builder must be concerned with not only the grade or contour of the existing site but also that of the finished site. To show both contours, two sets of contour lines are included on the plot plan. Broken lines indicate natural grade (NG), and solid lines indicate finished grade (FG) (see **Figure 9-7**). **Figure 9-8** shows a cross section of the site in **Figure 9-7**.

When the natural-grade elevation is higher than the finished-grade elevation, earth must be removed. This is referred to as *cut*. When the natural grade is at a lower elevation than the finished grade, *fill* is required. To determine the amount of cut or fill required at a given point, find the difference between the natural grade and the finished grade (see **Figure 9-9**).

Interpolating Elevations

Sometimes it is necessary to find an elevation that falls between two contour lines. This can be done by interpolation. *Interpolation* is a method of finding an unknown value by comparing it with known values.

Example: To interpolate the elevation of the tree at point A in **Figure 9-10**, follow the listed steps of the procedure




Figure 9-6. Spot elevations for specific locations.




Figure 9-7. Two sets of contour lines show that this site will be graded to be more level in the area of the building.

using the information shown in the illustration and the numbers enclosed in parentheses.

Step 1. Scale the distance between the two adjacent contour lines (12 feet).




Figure 9-10. Interpolate the elevation of the tree.

Step 2. Scale the distance from the unknown point to the nearest contour line (4 feet).

Step 3. Multiply the contour interval by the fraction of the distance between the contour lines to the unknown point. (Contour interval = 2 feet; fraction of distance between contour lines = $\frac{4}{12} = \frac{1}{3}$. $2 \times \frac{1}{3} = \frac{2}{3}$.)




Figure 9-8. Cross section of the site showing natural grade and finished grade.




Figure 9-9. Cutting is required where NG is above FG. Fill is required where NG is below FG.

Step 4. If the nearest contour line is below the other one, add this to it. If the nearest contour line is above the other one, subtract this amount.

(Nearest contour = 48 feet. This is below the other contour line at 50 feet, so $\frac{2}{3}$ foot is added to 48 feet. $2/3' + 48' = 48.66'$.)



USING WHAT YOU LEARNED

One of the first activities on a building site, after laying out the building lines, is excavating for the foundation and any concrete slabs. This requires that you know elevations of the foundations and slabs are compared to the elevation of the natural grade of the site. Let's determine how far the northwest corner of the garage floor is above or below the natural grade at that point.

The garage elevation is clearly marked as 343.0'. The corner falls between the natural-grade contour lines for 342' and 344'. We will have to interpolate to find a close estimate of what that elevation is. Using the inch scale on an architectural scale, measure the distance between the two contour lines at the corner of the garage. The shortest distance between these two lines that crosses the corner of the garage is $1\frac{9}{16}$ ". The corner is $\frac{9}{16}$ " from the 344' contour line. These elevations are expressed in decimal parts of a foot, so we will find our elevation to the nearest 1/10th of a foot. Divide $\frac{9}{16}$ by $1\frac{9}{16}$ (or $\frac{25}{16}$) to find that the corner is 36 percent of the way from 344' to 342'. Thirty-six percent of 2 feet (the contour interval) is 0.72'. Subtract 0.72' from 344' to find that the elevation of the natural grade at the corner is 343.28'. To the nearest 1/10th of a foot this is 343.3 feet, so the garage floor is 0.3 feet above the natural grade at that point.

Assignment

Refer to the site drawings of the Lake House in your textbook packet to complete the assignment.

1. What are the lengths of the north, east, and west boundaries of the Lake House site?




Figure 9-11.

2. Which of the compass points shown in **Figure 9-11** corresponds with the north boundary of the Lake House? Which compass point corresponds with the east boundary?
3. How many trees are indicated for removal?
4. How many trees are to remain on the site? (Do not include wooded areas.)
5. What is the finished-grade elevation at the tree nearest the Lake House?
6. What is the natural-grade elevation of the most easterly tree to be saved?
7. What is the elevation of the tree to be saved nearest the lake?
8. What is the natural-grade elevation at the southwest corner of the Lake House? Do not include the deck as part of the house.
9. What is the finished-grade elevation at the southwest corner of the Lake House?
10. How much cut or fill is required at the entrance of the garage?
11. Is cut or fill required at the southwest corner of the Lake House? How much?
12. What is the elevation at the northeast corner of the site?

Locating the Building

10 MIN

Laying Out Building Lines

The position of the building is shown on the site plan. Dimensions show the distance from the street (or lake) to the building and from the side boundaries to the building. The location of one corner can easily be found by measuring with a long (100' or 200') steel tape. Refer to **Figure 10-1** as you read the following directions for finding the corners of a rectangular building. The lot boundaries are represented by A, B, C, and D. Along boundary line A-C measure the distance from the front edge of the property, usually a street. Mark this point with a stake (e). As you drive each stake, drive a nail in the top of the stake to accurately mark the location. Measure the same distance along the other side boundary (B-D) and mark that point with stake f. Stretch a string from stake e to stake f. The front of the building will fall on this string. The distance from the front boundary to the building line is called the front *setback*. Both the front and side setbacks are nearly always regulated by zoning ordinances. Next measure the side setback, which is the distance from the side of the property to the side of the building at stake e to side of the building (line e-G). Drive a stake where the side setback and front setback meet. This stake represents one front corner of the building (corner G). Find the other front corner by measuring the width of the building from the first corner (line G-H). Check the distance from the corners to the front boundary of the lot to make sure it agrees with the setback shown on the site plan.




Figure 10-1. Laying out building lines.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Lay out building lines according to a site plan.
- Use the 6-8-10 or equal-diagonals method to check the squareness of corners.
- Use a laser level to measure the depths of excavations.

Now measure the depth of the building from the front corners to the rear of the building (corner I). Use a framing square to make corner G as square as possible. Check the corner for square using the 6-8-10 method (see **Figure 10-2**). Measure 6 feet from the corner along line G-I to find point a. Measure 8 feet from the corner along line G-e to find point b. Line a-b should be exactly 10 feet. (See Math review 24.) Adjust the angle of the side building line as necessary to make a-b 10 feet. Drive a stake at corner I. Repeat the process to find the other rear corner J. Check to see that the rear building line (I-J) is the dimension shown on the plans. Make adjustments as necessary until all corners are square and all dimensions are correct.

Now check the final layout to ensure that rectangles have 90-degree corners by measuring the diagonals (see **Figure 10-3**). When the diagonals are equal, the corners of the rectangle are square.




Figure 10-2. The 6-8-10 method of checking a square corner.




Figure 10-3. When the diagonals of a rectangle are the same length, the corners are square




Figure 10-4. Batter boards.

The *building lines* can be saved, even after the corner stakes are removed for earthwork, by erecting batter boards (see **Figure 10-4**). *Batter boards* are sturdy horizontal boards fastened between 2 × 4 stakes, at least 4 feet outside the building lines. The building lines are extended and marked on the batter boards.

Excavating

Most buildings require some *excavation* (digging) to prepare the site for a foundation. The depth of the excavation is measured from a fixed benchmark. A benchmark can be any stationary object such as a surveyed point on a street or very large boulder that cannot be moved. All elevations (vertical distances) are measured from this benchmark. Only in the case of a real coincidence would the benchmark be at the same elevation as the surface of the ground where the excavation is to be done. The actual depth of the excavation is the difference between the elevation at the surface of the ground and the elevation at the bottom of the excavation (see **Figure 10-5**).

Concrete footings are placed in the bottom of the excavation to support the entire weight of the building (see **Figure 10-6**). These footings are placed on unexcavated earth to reduce the chance of the soil compacting under them. This means that the excavation contractor must measure the depth of the excavation accurately. The footings may be *stepped*, as in **Figure 10-7**, to accommodate a sloping site. This requires measuring the depth at each step of the footing. Information about




Figure 10-5. The top of this excavation is 2.3 feet above the benchmark. Its depth is 6.5 feet (101.3' – 94.8').




Figure 10-6. The footing spreads the weight of the building over a greater soil area.



GREEN NOTE

The different soil types found at varying depths during an excavation can be surprising. In some areas, there may only be a few inches of top soil to support healthy plant growth. Below that layer can be heavy clay, which contains few nutrients and does not drain well, or gravel that also has few nutrients and does not hold water at all. For this reason, the top soil should be stripped from the area to be excavated and stock piled in a safe place to be used later where landscaping and lawns are planted.




Figure 10-7. Footings can be stepped to accommodate a sloping site.




Figure 10-8. The foundation plan gives complete dimensions.




Figure 10-9. Spot elevations show key points on the footing and the foundation.

the footing design is found on the foundation plan and building elevations. The layout of the foundation walls and their footings is shown on the foundation plan. The foundation walls are shown by two solid lines with dimensions to indicate their sizes (see **Figure 10-8**). A dotted line on each side of the foundation indicates the concrete footing. The size of the footing may be omitted when the plan is developed for use in several locations. If the footing size is not indicated on the foundation plan, a consulting engineer will have to determine the size in accordance with the local building code and the conditions at the site.

The depth of the foundation, including its footing, is shown on the elevations. To simplify calculating excavation depths, many architects indicate the elevations as key points along the footings (see **Figure 10-9**). A section view through all or part of the building may show a typical depth, but it is wise to check all the elevations for steps in the footing. The footings may be shown on the elevation as a double or a single dotted line. In masonry foundations, steps in footings are usually in increments of 8 inches to conform to standard concrete block sizes.

Note: A laser level is often used to measure elevations and depths of excavations. Setting up a laser level is similar to setting up a builder's level. You should follow the manufacturer's instructions and obey the safety precautions provided for the use of the laser level.




Figure 10-10. This excavation is 4'-6" deep—the difference between the two readings on the target rod.

Use the following procedure to measure differences in elevation, such as the depth of an excavation:

- Step 1. Set the instrument up on a tripod, and level it in a convenient location.
- Step 2. Hold the target rod on a known elevation, such as a benchmark or ground of known elevation. Note the reading on the target rod where the target registers the laser beam.
- Step 3. Take a similar reading with the target rod at the bottom of the excavation. Subtract the target reading at the benchmark from the reading at the bottom of the excavation to find the difference in elevation at the benchmark and at the bottom of the excavation, **Figure 10-10**.



USING WHAT YOU LEARNED

In the old days, before people had much awareness of how site conditions affected the livability of a house, it was common for a builder to begin by removing all of the trees that were near the planned building. It was thought that those trees would just be in the way. Today we are much more conscious of how the site affects the performance of the building. What would be the result in how the house functions if all of the oak and maple trees near the front of the house were removed? Those trees, being on the south side of the house, provide cooling shade in the summer, when they have all of their leaves. They also help hold the soil in place on the steep slope down to the lake.

Assignment

Refer to the Lake House drawings (in the packet) to complete this assignment.

1. What is the distance from the Lake House to the nearest property boundary? (Do not treat the decks as part of the house for this question.)
2. What is the distance from the Lake House to the lake?
3. What is the distance from the north property line to the garage?
4. What is the area of the basement of the Lake House, including the foundation? Ignore slight irregularities in the shape of the foundation. For ease in calculating, divide the foundation into rectangles, **Figure 10–11**.
5. Find the highest and lowest natural grades meeting the house.
6. How much cut or fill is required for the basement at the northeast corner of the house?
7. Measuring from the natural grade, how deep is the excavation for the footing under the overhead garage door?
8. What is the elevation at the bottom of the deepest excavation for the Lake House? (Do not include the garage.)




Figure 10–11.

9. Why would a row of large evergreen trees between the Lake House and the lake decrease the energy efficiency of the house?
10. What aspect of the location of a building is most often regulated by local ordinances?

Site Utilities

11 UNIT

Sewer Drains

The *building sewer* carries the waste to the municipal sewer or septic system (see **Figure 11-1**). Because sewer lines usually rely on gravity flow, they are large in diameter (4 inches, minimum) and are pitched to provide flow. Because water supply lines and gas lines are pressurized, pitch is not important in their installation. Therefore, the sewer is installed first, and other piping is routed around it as necessary. The size, material, and pitch of drains are usually given in a note on the site plan (see **Figure 11-2**). The pitch of a pipe is given in fractions of an inch per foot. A pitch of $\frac{1}{4}$ inch per foot means that for every horizontal foot, the pipe rises or falls $\frac{1}{4}$ inch.

In some cases, sewers may have to flow uphill. This is the case with the Lake House. Uphill flow is accomplished by a *grinder pump* (see **Figure 11-3**). A grinder pump grinds solids into small enough particles to be pumped and pumps the sewage at low pressure.




Figure 11-1. The house sewer carries waste from the house to the municipal sewer or septic systems.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Interpret symbols and notes used to describe site utilities.
- Explain the septic system indicated on a site plan.
- Determine the pitch of drain lines.





Figure 11–2. This note indicates cast iron pipe sloped $\frac{1}{4}$ inch for every foot of run.

Building Sewer

Any plumbing that is to be concealed by concrete work must be installed without fixtures or *roughed in* before the concrete is placed. Because the plumbing contractor installs all plumbing inside the building lines, this phase of construction is discussed later with mechanical systems. The sewer, however, is usually installed *after* the building is erected to prevent damage due to machinery on the site during construction. The sewer, too, is generally considered a site utility, which is why it is discussed here.

The workers who install the sewer must be able to determine the elevation at which it passes through the foundation and the pitch of the line outside the building. The sewer line may be shown on plans as a solid or broken line. Although it is usually labeled, this is not always true. When the sewer is not labeled as such, it can still be recognized by its material, pitch, and ending place. In light construction, the sewer is usually the



Photograph Courtesy of Environment One.

Figure 11–3. A grinder is a pump that can move sewage uphill.

only 4-inch pipe to the building. Also, the sewer is the only line with the pitch indicated.

Municipal Sewers and Septic Systems

In most developed areas, the building sewer empties into a municipal sewer line near the street. The contractor for the new building is responsible for everything from the municipal sewer to the house.

In less developed areas, the sewer carries the sewage to a septic system. The most common type of *septic system* includes a septic tank and drain field (see **Figure 11-4**). The septic tank holds the solid waste while it is decomposed by bacterial action. The liquids pass through the baffles and flow out of the tank to the distribution box. The distribution box (DB) diverts the liquid into *leach lines*. These perforated plastic or loose-fitting tile lines allow the liquid to be absorbed by the surrounding soil. The liquid gradually evaporates from or drains through the soil. The *drain field*, where the leach lines are laid, is usually made of a layer of crushed stone.

The design of septic systems is closely regulated by most health and plumbing codes. These local codes should be checked before designing or installing any septic system. The building code or health department code often requires a *percolation test* before the system can be approved. In a *percolation test*, holes are dug. Then a measured amount of water is poured into each hole. The amount of time required for the water to drain into the soil is an indication of how well the soil



GREEN NOTE

There are several materials used to make pipes and fittings. Traditionally sewer pipes were cast iron and supply pipes were galvanized iron or steel. As polyvinyl chloride (PVC) became available, it became the most common material for drainage, waste, and vent piping and for sewer pipes. It requires less energy to manufacture than cast iron or steel, it lasts almost indefinitely, and it requires less time to install. The downside is that it does not withstand heat, so it can't be used for hot water.

Copper, with soldered fittings, has been widely used for supply piping, because it is noncorrosive and will last much longer than iron or steel pipe. Well water is sometimes slightly acidic and the acid does corrode copper pipe, but that is not usually a concern because municipal water is treated to control the acidity.

In recent years, copper has become very expensive and two kinds of plastic pipe have been developed for use where copper has been the standard. Chlorinated polyvinyl chloride (CPVC) is inexpensive, noncorrosive, and easy to install. Cross-linked polyethylene (PEX) is more flexible, so it requires fewer fittings and is quick to install. Both CPVC and PEX are widely used in home construction today.

Manufacture of all plastic piping requires petrochemicals, but as a percentage of the total materials in a home the amount of piping material is very small, plastic pipe is not considered to have much of an environmental impact. There is no one best material for piping in green home construction.




Figure 11-4. Septic system.

will accept water from the septic system. This ability to accept water is called *percolation*. The locations of key elements in the system are often shown on the site plan.

To ensure proper drainage for a septic system, the elevation of its drainage piping is critical. For this reason, it is necessary to know the *invert elevation* of a pipe, which is the elevation at the lowest point inside the pipe (see **Figure 11-5**).




Figure 11-5. Invert elevation is the elevation at the lowest point inside the pipe.

Other Piping

Other utility piping, such as that for water supply or gas, is shown on the site plan. If these lines will pass beneath the concrete footings or be concealed under a concrete slab, they must be roughed in before the concrete is placed. Water supply pipes follow the most direct route from the municipal water main or well to the main shut-off valve or pump. Gas lines run from the main to the gas meter. All supply lines on the plot plan should be labeled according to type and size of piping (see **Figure 11-6**).

Electrical Service

The electrical service is the wiring that brings electricity to the house. There are two types of electrical service: overhead and underground (or buried).




Figure 11-6. Partial site plan with utilities indicated.

Overhead service involves a cable from the utility company transformer or pole to a weather-tight fixture called a *service head* or *mast head* on the house (see **Figure 11-7**). The service head is mounted on the top of a pipe, which serves as a conduit to the meter receptacle. In an underground service, the cable is buried (see **Figure 11-8**). Although electrical service is a site utility, it is not usually installed until the building is enclosed.

The electrical service to residential and small commercial buildings is similar, as previously explained and as shown in **Figures 11-7** and **11-8**. This type of service

has only one distribution point, the main electrical panel. Heavy commercial and industrial electrical services require multiconductor feeders, and typically these are underground services from a utility transformer to a service entrance section in the designated electrical or utility room. Additional utility coordination will be required within the building, which is discussed in Unit 14. The placement of these underground electrical utility lines must be coordinated with the locations of other site and building utilities prior to starting installation.




Figure 11-7. Overhead electrical service.




Figure 11-8. Underground electrical service.



USING WHAT YOU LEARNED

All building trades workers need to have an understanding of where the utilities will be located on the site. It is obvious that plumbers need to know where the water supply and sewer enter the building, but masons and carpenters also need this information. For example, if the piping is to run through a sleeve in the concrete, that sleeve must be in place before the concrete is placed. Where does the water supply enter the Lake House? The site plan shows it entering through the north wall of the play room. This is a case where the architect should be consulted to determine if it would be better to run the water supply closer to the sewer pipe, so it enters the utility room.

Assignment

Refer to the Lake House drawings (in the packet) to complete the assignment.

1. What size is the sewer for the Lake House?
2. How many lineal feet are required from the foundation wall to the septic tank?
3. What is the rise of the sewer from the house to the septic tank?
4. Where does the sewer pass through the foundation?
5. How many lineal feet of perforated pipe are needed for the drain field?
6. How many cubic yards of crushed stone are needed for the drain field?
7. What is the invert elevation of the sewer pipe at the point it enters the house?

UNIT 12

Footings

Objectives

After completing this unit, you will be able to perform the following tasks:

- Find all information on a set of drawings pertaining to footing design.
- Interpret drawings for stepped footings used to accommodate changes in elevation.
- Discuss applicable building codes pertaining to footing design.

All soil changes shape under force. When the tremendous weight of a building is placed on soil, the soil tends to compress under the foundation walls and allow the building to settle. To prevent settling, concrete footings are used to spread the weight of the building over more area. The footings distribute the weight of the building, so that there is less force per square foot of area.

The simplest type of footing used in residential construction is referred to as *slab-on-grade*. In this system, the main floor of the building is a single concrete slab, reinforced with steel to prevent cracking. The walls are erected on this slab so that it supports the weight of the building (see **Figure 12-1**). Slab-on-grade foundations are common in warm climates. This type of construction is indicated on the floor plan by a note (see **Figure 12-2**) and on section views of the construction (see **Figure 12-3**). If excavation is involved in the construction where a slab-on-grade is to be placed, it is very important to thoroughly compact all loose fill before placing the concrete. Tamping the fill prevents the soil from compacting under the concrete later, causing the concrete to settle or crack.

A thickened slab, sometimes called a haunch, is used to further strengthen the slab where concentrated weight, such as a bearing wall, will be located. A *haunch* is an extra thick portion of the slab that is made by ditching the earth before the concrete is placed (see **Figure 12-4**).




Figure 12-1. Slab-on-grade foundation.




Figure 12-2. Note indicating slab-on-grade construction.




Figure 12-3. Typical wall section for slab-on-grade construction.




Figure 12-4. A haunch is a thickened part of a slab to reinforce it under a load-bearing wall.

Spread Footings

In most sections of the country, the foundation of the house rests on a footing separate from the concrete floor. This separate concrete footing is called a *spread footing* because it spreads the force of the foundation wall over a wider area (see **Figure 12-5**). Spread footings can be made by placing concrete inside wooden or metal forms (see **Figure 12-6**). The footing is shown on the foundation or basement plan by dotted lines outside the foundation wall lines (see **Figure 12-7**).

The dimensions of the footings can be determined from the dimensions shown for the foundation.




Figure 12-5. A spread footing is so named because it “spreads” the downward force of the foundation wall over a greater soil area.



Figure 12-6. Footing forms.




Figure 12-7. The footing lines are sometimes shown on the foundation plan by broken lines around the foundation.

The foundation rests on the center of the footing unless otherwise specified, but the dimensions must meet the minimum requirements shown in Table R403.1 of the *International Residential Code*[®]. Therefore, if an 8-inch foundation rests on a 16-inch footing, the footing projects 4 inches beyond the foundation on each side. To lay out these footing lines, measure 4 inches from the building lines marked on the batter

boards. Where footing lines cross to form a corner, suspend a plumb bob. Drive a stake under the plumb bob. Then, drive a nail in the stake to accurately mark the corner. When all corners are located in this manner, stretch a line between the nails to locate the inside of the footing forms.

A complete set of construction drawings also includes sections that show the spread footing in




greater detail. However, these drawings are often superseded by local building codes. Building codes for footings include such things as minimum permissible depth of footing, required strength of concrete for footings, the width of footings, and the use of keys or dowels made of reinforcing steel (see **Figure 12–8**). The drawings for the Lake House are drawn to satisfy the building codes that are enforced in the community where it is to be built. If the drawings were done for a plan catalog where the locality is not known in advance, the *International Residential Code*® might be used as a guide, but the builder would be referred to local building codes and many dimensions would be omitted. **Figure 12–9** shows an excerpt from the *International Residential Code*® section on footings.

When reading the foundation plan for footing dimensions, pay particular attention to special features like fireplaces and pilasters. (*Pilasters* are thickened sections of the foundation wall that add strength to the wall.) The footing in these areas will be wider and may be deeper than under straight sections of foundation wall. There are times when a footing or foundation wall must be crossed or penetrated by a utility line. Care must be taken when penetrating a footing or foundation wall. If the penetration is not shown on the drawings, prior approval by an engineer is most often required, and the building code



GREEN NOTE

All too often contractors, building with the “margin of safety” in mind, use concrete that is mixed to yield higher strength than is necessary. The extra strength is obtained by increasing the amount of Portland cement in the concrete. Using only what is required to achieve the necessary strength for the job is better for the environment and less expensive. The amount of Portland cement in concrete can also be reduced by replacing a portion of it with some other material. Fly ash, a by-product of burning coal, can be added to concrete to replace some of the cement. The slag from a blast furnace used to produce steel can also be added to concrete to replace some of the Portland cement.



MONOLITHIC (ONE PIECE)

Figure 12–8. Anchoring the foundation wall to the footing.

probably regulates how it can be done. Items of concern include expansion and contraction between the utility line and footing or foundation wall, reduction in structural strength, and breaking of the moisture barrier.

Column Pads

Where steel columns, masonry piers, and wooden posts are used in the construction, a special concrete pad is indicated on the foundation plan (see **Figure 12–10**). As with other footings, building codes for the area should be consulted for the design of these pads. These pads, as with all other footings, should rest on unexcavated or well-compacted earth.

TABLE R403.1(3)
MINIMUM WIDTH AND THICKNESS FOR CONCRETE FOOTINGS
WITH CAST-IN-PLACE CONCRETE OR FULLY GROUTED MASONRY WALL CONSTRUCTION (inches)^{a, b}

SNOW LOAD OR ROOF LIVE LOAD	STORY AND TYPE OF STRUCTURE WITH CMU	LOAD-BEARING VALUE OF SOIL (psf)					
		1500	2000	2500	3000	3500	4000
20 psf	1 story—slab-on-grade	14 × 6	12 × 6	12 × 6	12 × 6	12 × 6	12 × 6
	1 story—with crawl space	19 × 6	14 × 6	12 × 6	12 × 6	12 × 6	12 × 6
	1 story—plus basement	25 × 8	19 × 6	15 × 6	13 × 6	12 × 6	12 × 6
	2 story—slab-on-grade	23 × 7	18 × 6	14 × 6	12 × 6	12 × 6	12 × 6
	2 story—with crawl space	29 × 9	22 × 6	17 × 6	14 × 6	12 × 6	12 × 6
	2 story—plus basement	35 × 12	26 × 8	21 × 6	17 × 6	15 × 6	13 × 6
	3 story—slab-on-grade	32 × 11	24 × 7	19 × 6	16 × 6	14 × 6	12 × 6
	3 story—with crawl space	38 × 14	28 × 9	23 × 6	19 × 6	16 × 6	14 × 6
	3 story—plus basement	43 × 17	33 × 11	26 × 8	22 × 6	19 × 6	16 × 6
30 psf	1 story—slab-on-grade	15 × 6	12 × 6	12 × 6	12 × 6	12 × 6	12 × 6
	1 story—with crawl space	20 × 6	15 × 6	12 × 6	12 × 6	12 × 6	12 × 6
	1 story—plus basement	26 × 8	20 × 6	16 × 6	13 × 6	12 × 6	12 × 6
	2 story—slab-on-grade	24 × 7	18 × 6	15 × 6	12 × 6	12 × 6	12 × 6
	2 story—with crawl space	30 × 10	22 × 6	18 × 6	15 × 6	13 × 6	12 × 6
	2 story—plus basement	36 × 13	27 × 8	21 × 6	18 × 6	15 × 6	13 × 6
	3 story—slab-on-grade	33 × 12	25 × 7	20 × 6	17 × 6	14 × 6	12 × 6
	3 story—with crawl space	39 × 14	29 × 9	23 × 7	19 × 6	17 × 6	14 × 6
	3 story—plus basement	44 × 17	33 × 12	27 × 8	22 × 6	19 × 6	17 × 6
50 psf	1 story—slab-on-grade	17 × 6	13 × 6	12 × 6	12 × 6	12 × 6	12 × 6
	1 story—with crawl space	22 × 6	17 × 6	13 × 6	12 × 6	12 × 6	12 × 6
	1 story—plus basement	28 × 9	21 × 6	17 × 6	14 × 6	12 × 6	12 × 6
	2 story—slab-on-grade	27 × 8	20 × 6	16 × 6	13 × 6	12 × 6	12 × 6
	2 story—with crawl space	32 × 11	24 × 7	19 × 6	16 × 6	14 × 6	12 × 6
	2 story—plus basement	38 × 14	28 × 9	23 × 6	19 × 6	16 × 6	14 × 6
	3 story—slab-on-grade	35 × 13	27 × 8	21 × 6	18 × 6	15 × 6	13 × 6
	3 story—with crawl space	41 × 15	31 × 10	24 × 7	20 × 6	17 × 6	15 × 6
	3 story—plus basement	47 × 18	35 × 12	28 × 9	23 × 7	20 × 6	17 × 6
70 psf	1 story—slab-on-grade	19 × 6	14 × 6	12 × 6	12 × 6	12 × 6	12 × 6
	1 story—with crawl space	25 × 7	18 × 6	15 × 6	12 × 6	12 × 6	12 × 6
	1 story—plus basement	30 × 10	23 × 6	18 × 6	15 × 6	13 × 6	12 × 6
	2 story—slab-on-grade	29 × 9	22 × 6	17 × 6	14 × 6	12 × 6	12 × 6
	2 story—with crawl space	34 × 12	26 × 8	21 × 6	17 × 6	15 × 6	13 × 6
	2 story—plus basement	40 × 15	30 × 10	24 × 7	20 × 6	17 × 6	15 × 6
	3 story—slab-on-grade	38 × 14	28 × 9	23 × 6	19 × 6	16 × 6	14 × 6
	3 story—with crawl space	43 × 16	32 × 11	26 × 8	21 × 6	18 × 6	16 × 6
	3 story—plus basement	49 × 19	37 × 13	29 × 10	24 × 7	21 × 6	18 × 6

For SI: 1 inch = 25.4 mm, 1 plf = 14.6 N/m, 1 pound per square foot = 47.9 N/m².

a. Interpolation allowed. Extrapolation is not allowed.

b. Based on 32-foot-wide house with load-bearing center wall that carries half of the tributary attic, and floor framing. For every 2 feet of adjustment to the width of the house add or subtract 2 inches of footing width and 1 inch of footing thickness (but not less than 6 inches thick).




Figure 12–9. This is a table from the *International Residential Code*®. The Code also includes a table for light frame construction with brick veneer and those with hollow masonry foundations.




Figure 12-10. Column footings appear as a rectangle of broken lines on the plan.

Reinforcement

Footings, column pads, and other structural concrete frequently include steel reinforcement. Footing reinforcement is normally in the form of steel reinforcement bars, commonly called *rebars*. Reinforcement bars are designated by their diameters in eighths of an inch (see **Figure 12-11**).

Depth of Footings

In many sections of North America, the moisture in the surface of the earth freezes in the winter. As this frost forms, it causes the earth to expand. The force of this expansion is so great that if the earth under the footing of a building is allowed to freeze, it either cracks the footing or moves the building. To eliminate this problem, the footing is always placed below the depth of any possible freezing. This depth is called the *frostline* (see **Figure 12-12**).

The frost-depth map shown in **Figure 12-12** is only approximate and is not generally accurate enough for

REINFORCEMENT BARS	
Size Designation	Diameter in Inches
3	.375
4	.500
5	.625
6	.750
7	.875
8	1.000
9	1.128
10	1.270
11	1.410
14	1.693
18	2.257

Figure 12-11. Standard sizes of rebars.

foundation design. The local building department will have specific footing depth requirements for their area.

Two methods are commonly used to indicate the elevation, or depth, of the bottom of the footings. The easiest to interpret is for spot elevations to be given at key points on the elevation drawings. Where elevations are given in this manner, the tops of the footing forms are leveled with a leveling instrument, using a benchmark for reference.

Another commonly used method is to dimension the bottom of the footing from a point of known elevation. This may be the finished floor or the top of the masonry foundation, for example. These dimensions are given on the building elevations. Footings and other features marked with a reference symbol \ominus , called a *datum* symbol, are to be used as reference points for other dimensions.

For example, see the South Elevation 3/3 of the Lake House (included in the packet). The left end of this view shows a footing with its bottom at an elevation of 334.83 feet. This is a variation of the usual practice of showing the elevation of the top of the footing. The top of this footing is 10 inches higher, or 335.66 feet. (See Math Review 16 in Appendix B.) What room of the Lake House is this footing under?

At the right end of the South Elevation 3/3, the footing is shown to be 5'-40" below the finished floor and masonry. This is the basement floor, which the Site




Figure 12–12. Average frost depths in the United States.

Plan shows to be at 337.0 feet. Therefore, the top of this footing is at 331'–8" or 331.67'.

Stepped Footings

On sloping building sites, it is necessary to change the depth of the footings to accommodate the slope. This is done by stepping the footings. When concrete blocks are to be used for the foundation walls, these steps are normally in increments of 8 inches. This allows the concrete blocks to be laid so that the top of each footing step is even with a masonry course. Some buildings require several steps in the footing to accommodate steeply sloping sites. Steps in the footings are shown on the elevation drawings and on the foundation plan by a single line across the footing.

The Lake House has several steps in the footing. For example, see the east side of the garage. This is shown on the East Elevation 2/3. This step is also shown on the Foundation Plan. It is 8'–0" from the north end of the garage. Normally the two levels of the

footing should overlap each other (see **Figure 12–13**). The stepped footing shown on the East Elevation does not appear to overlap. This would be something to consult the engineer or architect about.




Figure 12–13. Stepped footing.



USING WHAT YOU LEARNED

Every component of a building must be installed or built in the exact location and with the exact dimensions intended by the designer. If a supporting column is only slightly too high or slightly too short, the structure that column supports will not align properly with the rest of the building. What should the elevation be at the top of the columns supporting the deck between the Lake House kitchen and the garage?

Refer to the upper level floor plan to find the elevation of the top surface of the deck. That elevation is 341.67'. Deck detail 3/6 on sheet 6 shows the sizes of materials used in the deck construction. Add all of the dimensions of the materials between the top of the column and the top of the deck: The first thing we encounter is a metal post base. Most post bases raise the wood 1 inch off the concrete, so let's assume that is the dimension in this case. In actual practice, the dimension should be confirmed by measuring the base or consulting the manufacturer's literature before the column is built. On top of that are three 2×10 s, which would have a depth of $9\frac{1}{4}$ inches. The joists are 2×8 s, which would have a depth of $7\frac{1}{4}$ inches. Finally, we have 1×6 composite decking, which is actually 1 inch thick. $1'' + 9\frac{1}{4}'' + 7\frac{1}{4}'' + 1'' = 18\frac{1}{2}''$. Subtract 18.5" from the elevation at the top of the deck, 341.67', to find that the top of the column should be at 340.13'.

Assignment

Refer to the Lake House drawings in your textbook packet to complete this assignment.

1. What is the typical width and depth of the concrete footings for the Lake House?
2. What is the total length and width (outside dimensions) of the concrete footings for the garage of the Lake House? (Remember to allow for the footings to project beyond the foundation wall.)
3. How many concrete pads are shown for footings under columns or piers in the Lake House?
4. What are the dimensions of these pads?
5. What reinforcement is indicated for these pads?
6. What reinforcement is indicated for the spread footings under the Lake House?
7. What is indicated by the 2-inch dimension between the 12-inch round concrete footings?
8. What is the elevation of the top of the footing under the garage door?
9. What are the elevations of the tops of each section of concrete footing shown on the East Elevation 2/3?
10. How far outside the foundation walls are the typical footings?
11. Refer to the building code in your community (or the model code section shown in **Figure 12-9**), and list the specific differences between the Lake House footings and the minimum code requirements. Use the part of the Lake House footing that is under the greatest load. Assume a soil load-bearing capacity of 3,000 pounds per square foot and a snow load of 50 psf.

UNIT 13

Foundation Walls

Objectives

After completing this unit, you will be able to perform the following tasks:

- Determine the locations and dimensions of foundation walls indicated on a set of drawings.
- Describe special features indicated for the foundation on a set of drawings.

Laying Out the Foundation

When the **concrete** for the footings has hardened and the forms are removed, carpenters can begin erecting forms for concrete foundations, or masons can begin laying blocks or bricks for masonry foundations. Although the material differs, the drawings and their interpretation for each type of foundation are similar.

You referred to the dimensions on the foundation plan to lay out the footings in Unit 12. The same dimensions are used to lay out the foundation walls. The layout process is also similar. The outside surface of the foundation wall is laid out using previously constructed batter boards. Then the forms are erected or the masonry units are laid to these lines. The foundation plan includes overall dimensions, dimensions to interior corners and special constructions, and dimensions of special smaller features. It is customary to place the smallest dimensions closest to the drawing. The overall dimensions are placed around the outside of the drawing (see **Figure 13-1**).





Figure 13-1. Dimensioning on a foundation plan.

All drawing sets include, at least, a wall section showing how the foundation is built, how it is secured to the footings, and any special construction at the top of the foundation wall (see **Figure 13-2**). Although a typical wall section may indicate the thickness of the foundation wall, you should carefully check around the entire wall on the foundation plan to find any notes that

indicate varying thicknesses of the foundation wall. For example, the wall may be 12 inches thick where it has to support brick veneer above, while it is only 8 inches thick on the back of the building where there is no brick veneer. A careful check of the foundation plan for the Lake House shows that the house foundation is 10-inch thick concrete, except the portion under the



Courtesy of Robert C. Kurzon.

Figure 13-2. Section through foundation.



GREEN NOTE

Concrete and concrete masonry units are the traditional materials for building foundations. These materials do not provide particularly good thermal insulation, and the processes for the manufacture of concrete and concrete products are not environmentally friendly. In recent years, many new developments in the construction of foundations are taking place. One such innovation that is gaining popularity is the use of insulated concrete forms (ICFs). ICFs are typically made of rigid foam, such as Styrofoam®, but they can also be made of other materials, such as mineralized wood chips.

ICFs are made in a variety of sizes that are small enough to be easy to handle. The individual ICF units lock together, so that the result is a wall form into which concrete can be placed, resulting in a wall that is insulated with several inches of foam yet has the structural properties of concrete.



fireplace, which is 12 inches thick. Some portions of the foundation wall have 6-inch concrete masonry units at the top to create a ledge for special construction and the garage foundation calls for 8-inch concrete.

Structural concrete is the most common foundation material because it is strong and concrete foundations can be built quickly. Some buildings have masonry (usually concrete block) foundations. There are some additional topics to be discussed for masonry (concrete block) foundations.

The details for a masonry foundation may call for horizontal reinforcement in every second or third course. This is usually prefabricated wire reinforcement to be embedded in the mortar joints. Prefabricated wire reinforcement is available in varying sizes for different sizes of concrete blocks.

The height of the foundation wall is dimensioned on the building elevations. These are the same dimensions as of those used to determine the depth of the footings in the preceding unit. Just as the footing was stepped to accommodate a sloping building site, the top of the foundation wall may be stepped to accommodate varying floor levels in the *superstructure* (construction above the foundation) as shown in **Figure 13-3**.

The top of a foundation may be built with smaller concrete blocks to form a ledge upon which later brickwork will be built. It is also common practice to use one course of 4-inch solid block as the top course of a masonry foundation wall.

In concrete foundations, **anchor bolts** are placed in the top of the foundation (see **Figure 13-4**). These bolts are left protruding out of the top of the foundation so that the wood superstructure can be fastened in place later. Anchor bolts are not normally shown on the foundation plan, but a note on the wall section indicates their spacing. On masonry walls, anchor bolts can be placed in the hollow cores of the concrete blocks. They are held in place by filling the core with mortar grout. **Grout** is a **Portland cement** mixture that has high strength.




Figure 13-3. The top of the foundation may be stepped to allow for a partial basement or varying floor levels.




Figure 13-4. Anchor bolt.

In areas where there is a threat of extremely high winds or earthquakes, additional hold-down straps may be called for (see **Figure 13-5**). These hold-downs are normally used only with concrete foundations. Hold-downs are discussed in more detail in Unit 36.




Figure 13-5. Hold-down straps are used in addition to anchor bolts in an earthquake zone.

Special Features

Many foundations include steel or wooden beams, which act as girders to support the floor framing over long spans (see **Figure 13-6**). When the girder is steel, it is indicated by a single line with a note specifying the size and type of structural steel. A wood girder is usually indicated by two or more lines and a note specifying the number of pieces of wood and their sizes in a built-up girder (see **Figure 13-7**).

If the top of the girder is to be flush with the top of the foundation beam, pockets must be provided in the foundation (see **Figure 13-8**). **Beam pockets** are shown on the details and sections of the construction drawings. The locations of these beam pockets are dimensioned on the foundation plans.

If windows are to be included in the foundation, the form carpenter or mason must provide openings of the proper size. The locations of windows should be dimensioned on the foundation plan. The sizes of the windows may be shown by a note or given on the window schedule. Window sizes and window schedules are discussed in Unit 25. It is important, however, to get the masonry opening size from the window manufacturer before forming the opening in the foundation wall. The *masonry opening* is the size of the opening required in the foundation wall to accommodate the window. This size may be different from the **nominal size** given in a note on the foundation plan.

The foundation may include pilasters for extra support. A *pilaster* is a thickened section of the foundation, which helps it resist the pressure exerted by the earth




Figure 13-6. The girder supports the floor framing.

COMMON SIZES OF STRUCTURAL STEEL GIRDERS			COMMON SIZES OF WOOD BUILT-UP GIRDERS		
SHAPE: S = STANDARD BEAM W = WIDE-FLANGE BEAM			NUMBER OF PIECES		
	NOMINAL DEPTH IN INCHES	WEIGHT PER FOOT IN POUNDS		THICKNESS EACH (NOMINAL) IN INCHES	WIDTH EACH (NOMINAL) IN INCHES
S	10	35	2	2	10
S	8	23	2	2	12
S	8	18.4	3	2	10
W	10	33	3	2	12
W	10	21			
W	10	11.5			
W	8	31			
W	8	28			
W	8	17			
W	8	13			

Figure 13-7. Typical specifications for structural steel and wood built-up girders—other types are described in the project specifications.




Figure 13-8. A beam pocket is a recess in the wall to hold the girder.

on the outside. The location and size of pilasters are shown on the foundation plan.

The Lake House drawing includes a special feature not commonly found on foundation plans for houses. There are four notes that read 3½" STD. WT. STL. COL. W/8 × 8 × ½ B.PL. These notes indicate a 3½-inch square, standard weight, steel column with 8-inch-by-8-inch-by-½-inch-thick base plates. This structural steelwork is explained in more detail later, but to completely understand the foundation plan, it is necessary to know that the steel will be erected.

Permanent Wood Foundation

Foundations are usually constructed of concrete or concrete block. However, a type of specially treated wood foundation is sometimes used (see **Figure 13-9**). These *permanent wood foundations* do not use concrete footings.

Instead, they are built on 2 × 8s or laid on gravel fill below the frostline. The foundation walls are framed with lumber that has been pressure treated to make it rot resistant and insect resistant. The framing is covered with a plywood skin, and the plywood is covered with



Figure 13–9. Permanent wood foundation.

polyethylene film for complete moisture proofing (see **Figure 13–10**). All the nails in a wood foundation are stainless steel to prevent rusting. The IRC includes separate provisions to cover wood foundations.




Figure 13–10. Section of wood foundation.



USING WHAT YOU LEARNED

Before any concrete form construction begins, it is necessary to have a good picture in your mind of what the finished product will be. The Lake House foundation has many variations from the typical wall shown in the Typical Wall Section on sheet 4. For example, near the southeast $3\frac{1}{2}$ " \square steel column, the Foundation Plan has a note that says "6" CONC. BLK. – TOP OF WALL TO BELOW STAIR." What does this note mean and why is that detail necessary? The floor plans show stairs from the living room down to the playroom at this point. The stairs are also shown by the hidden lines on the South Elevation 3/3 and that elevation includes a note that says "6" CMU FDN WALL (BELOW STAIR)." The typical foundation wall is 10 inches thick, so the 6-inch concrete masonry units create a 4-inch ledge to support the stairs.

Assignment

Refer to the Lake House drawings in your textbook packet to complete the assignment.

1. What is the thickness of the concrete foundation in the kitchen area of the Lake House?
2. Approximately how many lineal feet of concrete wall are included in the foundations of the Lake House?
3. How thick is the south foundation of the fireplace?
4. What is the elevation at the top of the north end of the east foundation wall of the garage?
5. What is the highest elevation in the entire foundation?
6. How high is the foundation wall at the highest elevation of the foundation?
7. What size anchor bolts are indicated at the top of the Lake House foundation?
8. What spacing is indicated for the anchor bolts?
9. What secures the foundation wall to the footing?
10. What is the elevation of the top of the concrete wall at the southwest $3\frac{1}{2}$ " steel column?

UNIT 14

Drainage, Insulation, and Concrete Slabs

Objectives

After completing this unit, you will be able to perform the following tasks:

- Locate and explain information for control of groundwater as shown on a set of drawings.
- Locate and describe subsurface insulation.
- Determine the dimensions of concrete slabs and the reinforcement to be used in concrete slabs.

Drainage

After the foundation walls are erected and before the excavation outside the walls is **backfilled** (filled with earth to the finished grade line), footing drains, if indicated, must be installed. **Footing drains** are usually perforated plastic pipe placed around the footings in a bed of crushed stone (see **Figure 14-1**). If the site has a natural slope, the footing drains can be run around the foundation wall to the lowest point, then away from the building to drain by gravity. In areas where there is no natural drainage, the drain is run to a dry well or municipal storm drain.

At one time, clay drain tile was the most common type of pipe for this purpose. However, perforated plastic pipe is used in most new construction. Plastic drain pipe is manufactured in 10-foot lengths of rigid pipe and in 250-foot rolls of flexible pipe (see **Figure 14-2**). An assortment of plastic fittings is available for joining rigid plastic pipe. When footing drains are to be included, they are shown on a wall section or footing detail (see **Figure 14-3**). A note on the drawing indicates the size and material of the pipe.

If the floor drains are to be included in concrete-slab floors, they are indicated by a symbol on the appropriate floor plan (see **Figure 14-4**). If these floor




Figure 14-1. Footing drain.




Figure 14-2. Plastic drain pipe.




Figure 14-4. The floor drain is shown by a symbol. (Notice that the floor is pitched toward the drain.)




Figure 14-3. Footing drains are shown outside the footing.

drains run under a concrete footing, the piping had to be installed before the footing was placed (see Unit 11). The **riser** (vertical part through the floor) and drain basin are usually set at the proper elevation just prior to placing the concrete floor.

The floor plan may include a spot elevation for the finished drain, or it may be necessary to calculate it from information given for the pitch of the concrete slab. Pitch of concrete slabs is discussed later in this unit.

Vapor Barriers

Another technique often used to prevent groundwater from seeping through the foundation is coating the foundation wall with asphalt foundation coating.

At this point, subsurface work outside the foundation wall is completed, but backfilling should not be done until the superstructure is framed. The weight and rigidity of the floor on the foundation wall help the wall to resist the pressure of the backfill. If the backfilling must be done before the framing, the foundation walls should be braced. To retard the flow of moisture from the earth through the concrete-slab floor, the drawings may call for a layer of gravel over the entire area before the concrete is placed. A polyethylene **vapor barrier** is laid over the gravel underfill. The thickness of polyethylene sheeting is measured in **mils**. One mil equals 1/1,000 of an inch. For vapor barriers, 6-mil polyethylene is generally used.



GREEN NOTE

One of the most basic principles of green home construction is the control of groundwater to keep it from penetrating the foundation and causing structural damage as well as interior finish damage and mold. Groundwater is kept away from the foundation by proper grading of the site, careful damp-proofing, and providing a path for groundwater to escape without penetrating the foundation. This path involves placing perforated drain pipes next to or below the footings and pitching it, so all water flows downhill to a daylight exit point. Poor workmanship on any of these aspects of groundwater control can result in devastating water damage and serious implications for the health of the occupants.

Insulation

In cold climates, it is desirable to insulate the foundation and concrete slab. This insulation is usually rigid plastic foam board placed against the foundation wall or laid over the gravel underfill (see **Figure 14-5**). Rigid insulation under the floor may only be specified for the outer 2 feet of the slab. The heat of the building keeps the frost from penetrating more than 2 feet into the perimeter of the floor slab.




Figure 14-5. Rigid plastic foam insulation may be laid under the perimeter of the floor or against the foundation wall.

Like all materials, concrete and masonry expand and contract slightly with changes in temperature. To allow for this slight expansion and contraction, the joint between the concrete slab and foundation wall should include a compressible expansion joint material. Expansion joints can be made from any compressible material such as neoprene or composition sheathing material. This expansion joint filler is as wide as the slab is thick and is simply placed against the foundation wall before the concrete is placed.




Figure 14-6. The callout for welded wire fabric explains the size and spacing of the wires.

Concrete Slabs

When the house has a basement, the floor is a concrete slab-on-grade. The areas to be covered with concrete are indicated on the foundation plan or basement floor plan. This is usually done by an area not giving the thickness of the concrete slab and any reinforcing steel to be used. To help the concrete resist minor stresses, it is usually reinforced with welded wire mesh. Welded wire mesh is sometimes abbreviated WWM and sometimes WWF for welded wire fabric. The specifications for welded wire mesh are explained in **Figure 14-6**. Where the slab must support bearing walls or masonry partitions, it may be haunched, as discussed in Unit 12.

When floor drains are included or where water must be allowed to run off, the slab is *pitched* (sloped slightly). A note on the drawings indicates the amount of pitch. One-quarter inch per foot is common. When there is any possibility of confusion about which way the slab is to be pitched, bold arrows are drawn to show the direction in which the water will run (see **Figure 14-7**).

When floor drains or forms are set for pitched floors, it is necessary to find the total pitch of the slab. This is done by multiplying the pitch per foot by the number of feet over which the slab is pitched. (See Math Review 8 in Appendix B.) For example, if the note on a concrete *apron* in front of a garage door indicates a pitch of $\frac{1}{2}$ inch per foot and the apron is 4 feet wide, the total pitch is 2 inches. The proper elevation for the form at the outer edge of the apron is 2 inches less than the finished floor elevation.




Figure 14-7. A bold arrow indicates the way that water will run off a pitched surface.

Slab-on-grade installations may require electrical raceways to be installed in or just below the concrete slab in the crushed or gravel fill. These installations must be made so that they do not reduce the structural integrity of the concrete slab. An oversized raceway in the concrete slab may cause the slab to crack and settle unevenly. An electrician should be present during concrete placement to observe and correct any damage to these electrical raceways.

All underground utility systems must be coordinated prior to starting installation, especially in commercial and industrial buildings, as discussed in Unit 11. The service entrance section may have up to six subdistribution sections or panels located throughout the building. Electrical feeders are required from the electrical service entrance section to these subdistribution sections or panels. This requires detailed coordination between the electrical installer and the other utility installers prior to starting the installation of the utility systems. The electrical installation must be laid out around the other utilities, with the other utility

layouts normally having priority. The other utilities to be coordinated may include plumbing, fire sprinkler, heating and air conditioning, and specialty systems. This coordination must be done for both the underground and above ground systems.

Some of the concrete work in the Lake House is of particular interest, because it is a part of the passive solar heating system the Lake House uses. Section 1/4 and the lower-level floor plan 1/2 indicate that the area under the living room and dining room floors is a heat sink. A *heat sink* is a mass of dense material that absorbs the energy of the sun during the day and radiates it at night. The living room and dining room are on the south side of the Lake House. In the winter, when the leaves are off the deciduous trees, the sun shines in the large areas of glass in these rooms and warms the heat sink. At night, this heat is radiated into the house to provide additional heat when it is needed most. The floor over the heat sink is a concrete slab similar to that used in the playroom. Detail 2/5 helps to explain this concrete slab.



USING WHAT YOU LEARNED

All of the reinforcement for the concrete slabs must be in place before the concrete is delivered to the site. In the Lake House how many rebar of what size are required for the haunch in the concrete slab between the two north 3½" square steel columns? The haunch is shown on Foundation Plan 4/1 and Detail 3/1 shows the reinforcement. The first callout on the detail is "2 -- #4 CONTINUOUS" with a leader pointing to the symbols for reinforcing bars.

Assignment

Refer to the Lake House drawings in your textbook packet to complete this assignment.

1. What is the thickness of the concrete slab over the heat sink in the Lake House?
2. Describe the reinforcement used in the concrete slab in the playroom of the Lake House.
3. How many square feet of 2-inch rigid insulation are needed for the Lake House heat sink?
4. What prevents moisture from seeping through the concrete slab floor in the Lake House?
5. What is the finished floor elevation of the Lake House garage?
6. What is the elevation of the floor drain in the utility room of the Lake House?
7. What is the purpose of the 8-inch-thick concrete haunch in the middle of the Lake House slab?
8. How many cubic yards of concrete are required for the garage floor? The basement floor including the crawl space?

Framing Systems

15 MIN

Platform Framing

Platform framing, also called **western framing**, is the type of framing used in most houses built in the last 70 years (see **Figure 15-1**). It is called platform framing because as the floor is built at each level, it forms a platform on which to work while erecting the next level (see **Figure 15-2**).

A characteristic of platform framing is that all wall *studs*, the main framing members in walls, extend only the height of one story. Interior walls, called *partitions*, are the same as exterior walls. The bottoms of the studs are held in position by a *bottom* (or *sole*) plate. The tops of the studs are held in position by a *top plate*. Usually, a *double top plate* is overlapped at the corners to tie intersecting walls and partitions together (see **Figure 15-3**). In some construction, the second top plate is not used. Instead, metal framing clips are used to tie

Objectives

After completing this unit, you will be able to identify each of the following types of framing on construction drawings:

- Platform
- Balloon
- Post-and-beam
- Energy-saving




Figure 15-1. Platform, or western, framing.




Figure 15-2. Platform, or western, framing provides a convenient work surface during construction.




Figure 15-3. The double top plate overlaps at the corners.

intersecting walls together. Upper floors rest on the top plate of the walls beneath. The framing members of the upper floors or roof are positioned over the studs of the wall that supports them.

Platform construction can be recognized on wall sections (see **Figure 15-4**). Notice that the studs extend only from one floor to the next.

Balloon Framing

In **balloon framing**, the exterior wall studs are continuous from the foundation to the top of the wall (see **Figure 15-5**). Floor framing at intermediate levels is supported by *let-in ribbon boards*. This is a board that fits into a notch in each joist and forms a support for the joists. Although balloon framing is not as widely used as it once was, some balloon-framing techniques are still used for special framing situations.

In both platform-frame and balloon-frame construction, the structural frame of the walls is covered with sheathing. **Sheathing** encloses the structure and, if a structural grade is used, prevents *wracking* of the wall. *Wracking* is the tendency of all the studs to move, as in a parallelogram, allowing the wall to collapse to the side (see **Figure 15-6**). There are two ways to prevent wracking. Plywood or other structural sheathing at the corners of the building prevents this movement. Also, diagonal braces can be attached to the wall framing at the corners to prevent wracking (see **Figure 15-7**).




Figure 15-4. This can be recognized as platform construction because the studs extend only from one floor to the next.




Figure 15-5. Balloon framing.




Figure 15-6. Wracking.




Figure 15-7. Let-in bracing prevents wracking.

Post-and-Beam Framing

Platform framing and *balloon framing* are characterized by closely spaced, lightweight framing members (see **Figure 15-8**). *Post-and-beam* framing uses heavier framing members spaced farther apart (see **Figure 15-9**). These heavy timbers are joined or fastened with special hardware (see **Figure 15-10**). Because post-and-beam framing uses fewer pieces of material, it can be erected more quickly. Also, although the framing members are large—they can range from 3 inches by 6 inches to 5 inches by 8 inches—their wider spacing results in a savings of material. However, to span this wider spacing, floor and roof decking must be heavier. Post-and-beam




Figure 15-8. Conventional framing. 16" OC.




Figure 15-9. Post-and-beam framing. 4' OC.

framing is sometimes left exposed to create special architectural effects (see **Figure 15-11**).

The structural core of the Lake House in your textbook packet uses posts and beams as shown in Detail 5/6. However, this is not purely post-and-beam construction. The posts are 3½-inch square steel tubing, and the beams are LVL beams. These are properly called **beams** because they carry a load without continuous support from below. These beams are supported only in the beam pockets on the steel posts (see **Figure 15-12**). In the Lake House, the post-and-beam construction does not include exterior walls. In pure post-and-beam construction, the exterior walls have widely spaced posts, and the space between is filled

in with nonload-bearing curtain walls. These curtain walls are merely panels that fill in the space between the structural elements—the posts and beams.

In areas where hurricanes and high tides are a threat, some houses are built as pole structures. Pole buildings are a variation of post-and-beam construction. Poles, which are treated to be insect and rot resistant, are set several feet in the ground and 8 to 12 feet apart. A *band joist*, or *header*, is then bolted to these poles (see **Figure 15-13**). The floors, walls, and roof are framed within the pole structure (see **Figure 15-14**). Pole buildings are strong; they resist severe winds. Pole construction allows buildings to be kept above damaging floodwaters.




Figure 15-10. Common timber fastenings.

Metal Framing

Light-gauge metal framing is used extensively in commercial construction in places where the strength of structural steel or reinforced concrete is not required. Metal framing is also very popular in home building where termites and water damage are known to be problems. Light-gauge steel framing uses studs and joists, the same as wood framing. Unlike wood framing, steel framing uses tracks and runners in place of bottom plates and top plates (see **Figure 15-15**). The lighter, less expensive grades of

metal framing are not as strong as wood, so they are used primarily for interior partitions or in conjunction with other structural materials. Metal framing can be preassembled just as you would preassemble wood framing. The runner is fastened to the floor with powder-actuated fasteners. The wallboard material is fastened to the metal studs using an electric screw gun with sheet metal screws. Subflooring material is fastened to the metal floor joists similarly with power-driven screws. The construction drawings and specifications will indicate the type of metal framing



Figure 15–11. The exposed timber framing in this house is an important part of its design.





Figure 15–12. Beam pocket for the lake house.



GREEN NOTE

Structural integrated panels (SIPs) are factory-built panels with an insulating core to which OSB is adhered to the exterior surface and usually gypsum board is adhered to the interior surface. Both the exterior and interior surfaces can be altered to suit the design of the building. Wiring and piping can be imbedded in the foam core as the panel is manufactured. SIPs are custom designed for each particular application. SIPs are joined together with screws, splines, and glue to create a weather-tight, well-insulated wall, roof, or floor. The advantages of SIPs are that they do not include the number of interior framing members that frame construction does, so they do a better job of thermal insulation; they result in a more weather-tight building envelope; there is virtually no waste created at the job site; and construction is faster.





EMBEDMENT AND ALIGNMENT OF POLES. DEPTH OF EMBEDMENT DEPENDS ON SPACING AND SIZE OF POLES, WIND LOADS, AND SO FORTH, AND MAY VARY FROM 5 TO 8 FEET.

Figure 15-13. Basic elements of a pole building.

to be used. The gauge must be taken into consideration before using certain tools (stud punches, powder-actuated tools, etc.) and special mounting devices (box hangers, conduit brackets, etc.).

Where electrical nonmetallic-sheathed cable is installed through metal framing, a bushing or grommet must be installed prior to installing the cable (see **Figure 15-16**).

Advanced Framing

Advanced framing is the name given by The APA—The Engineered Wood Association for what was previously called *Optimum Value Engineering* or *OVE*. It is a system of using 2×6 framing members spaced 24 inches on centers in place of 2×4 s spaced 16 inches on centers. Advance framing also uses aligned framing members to provide greater strength so that some members can be eliminated (see **Figure 15-17**). When the roof trusses are aligned directly over the studs, it is not necessary to use a double top plate. In this system, second floor framing is aligned with first floor framing.

When wall framing is done with 2×4 s spaced 16 inches on centers, 9.4 percent of the wall is solid wood. Wood conducts heat out of the building. Only the space between the solid wood framing can be filled with insulation. By using 2×6 studs spaced 24 inches on centers, the area of solid wood is reduced to 6¼ percent of the wall. The amount of framing material is the same. Not only does this reduce the amount of wood exposed to the surface of the wall, but it also allows for more insulation.

The area of exposed wood is further reduced by special corner construction. In conventional framing, three pieces are used to frame the corner of a wall (see **Figure 15-18**). To reduce heat loss through the wall, only two pieces are used (see **Figure 15-19**). The third piece, which normally provides a nailing surface for the interior *drywall*, is replaced by metal clips.

In advanced framing, many of the doubled framing members around door and window openings can be eliminated. Special hangers are used to support the header above an opening.




Figure 15–14. Framing in a pole building.




Figure 15–16. Nonmetallic-sheathed cable installed through metal framing.



Courtesy of Dietrich Metal Framing.

Figure 15–15. Metal framing.




Figure 15-17. Advanced framing includes some or all of the elements described here.




Figure 15-18. Conventional corner posts for 2 × 4 framing.




Figure 15-19. Energy-efficient corner construction.




Figure 15-20. Nonmetallic-sheathed cable installed in wood framing.

Many frame building are constructed using some of the elements of advanced framing, but not all of them. Notes on plans and details will describe these elements where they are to be used.

Examination of the first floor plan and the detail drawings of the Lake House shows that the walls are framed for maximum efficiency. Several details indicate that the studs are 2 × 6s @ 24 OC. This allows room for more insulation in the wall. Also notice that the house is sheathed with 3/4-inch insulation sheathing. Interior partitions do not need insulation, and so they are framed with 2 × 4s.

When installing nonmetallic-sheathed cable through wood wall studs and floor joists, the cable must be installed at least 1¼ inches from the nearest edge. Where this 1¼ inches cannot be met, a 1/16-inch-thick metal plate must be installed to protect the cable from nails and screws (see Figure 15-20).



USING WHAT YOU LEARNED

A good familiarity of the framing system for a house will be a big help in understanding all of the details necessary to frame the building. One aspect of the framing system is the method for framing corners. In a typical outside corner of the Lake House, what size and how many studs are used? This information is clearly shown in Detail 4/4 on Sheet 4 in your textbook packet, the first sheet showing framing details. There are three 2×6 studs in a typical corner.

Assignment

1. Identify a through h in **Figure 15–21**.
2. What kind of framing is shown in **Figure 15–21**?
3. Identify a through c in **Figure 15–22**.
4. Identify a through c in **Figure 15–23**.
5. Sketch a plan view of a conventional corner detail. Include drywall and sheathing.
6. Sketch a plan view of an energy-efficient corner detail. Include drywall and sheathing.
7. What two materials are most often used for framing homes?
8. What framing material requires bushings or grommets for nonmetallic-sheathed cable installations?
9. Which of the types of framing discussed in this topic is used for the exterior walls of the Lake House?
10. What supports the west ends of the floor joists in bedroom #1?
11. What supports the east ends of the kitchen rafters?
12. How are the LVL beams fastened to the $3\frac{1}{2}$ -inch square posts?
13. How are the steel posts anchored?
14. What does the northwest square steel post rest on?
15. What supports the north edge of the living room floor?
16. List the dimensions (thickness \times depth \times length) of all LVL beams.
17. List the length of each piece of $3\frac{1}{2} \times 3\frac{1}{2}$ steel.

Note: Refer to the Lake House drawings (in the packet) to complete the rest of the assignment.

Note: The length can be found by subtracting the outside dimension of the posts from the centerline spacing shown on the plan views.




Figure 15-21.




Figure 15-22.




Figure 15-23.

Columns, Piers, and Girders

16

UNIT

The most common system of floor framing in light construction involves the use of joists and girders. **Joists** are parallel beams used in the floor framing (see **Figure 16-1**). Usually buildings are too wide for continuous joists to span the full width. In this case, the joists are supported by one or more **girders** (beams) running the length of the building. The girder is supported at regular intervals by wood or metal posts or by masonry or concrete piers.

An exception to the above system of girders and columns might be when the floor is framed with floor trusses (**Figure 16-2**). Floor trusses can often span a much greater distance without a supporting girder than can solid wood joists or I-joists. Joists and trusses are covered in Unit 17.


Columns and Piers

Metal posts called *pipe columns* are the most common supports for girders. However, masonry or concrete piers may be specified. The locations of columns, posts, or piers are given by dimensions to their centerlines. When metal or wooden posts are indicated, the only description may be a note on the foundation plan (see **Figure 16-3**). This note may give the size and material of the posts only, or it may also specify the kind of bearing plates to be used at the top and bottom of the post (see **Figure 16-4**). A *bearing plate* is a steel plate

Objectives

After completing this unit, you will be able to perform the following tasks:

- Locate columns and piers, and describe each from drawings.
- Locate and describe the girders that support floor framing.
- Determine the lengths of columns and the heights of piers.



Courtesy of Richard T. Kreh, Sr.

Figure 16-1. Joist-and-girder floor framing.




Figure 16-2. Floor trusses are engineered to span a greater distance without a supporting girder.




Figure 16-3. Foundation plan with note for column and footing.




Figure 16-4. Bearing plate.

that provides a flat surface at the top or bottom of the column or post. If the girder is supported by masonry or concrete piers, a special detail may be included to give dimensions and reinforcement details.

Girders

Before the total length of the columns or height of the piers can be calculated, it is necessary to determine the size of the girder and its relationship to the floor joist. Three types of girders are commonly used in residential construction. Steel beams are often used where strength is a critical factor. Built-up wood girders are constructed on the site. These consist of three or more pieces of 2-inch lumber nailed together with staggered joints to form larger beams. *Laminated veneer lumber* (LVL) (see **Figure 16-5**) is also popular for use as girders. LVL is an engineered lumber product made by gluing layers of *veneer* together. These beams can be manufactured in almost any size. They are very strong, because lumber defects can be eliminated and all the grain runs in the best possible direction. The sizes and specifications for girders are specified by an engineer or architect using Tables R602.7(1), (2), and (3) of the *International Residential Code*[®]. The notes commonly



Courtesy of Trus Joist Macmillan, A limited Partnership, Boise, ID.

Figure 16-5. LVL (laminated veneer lumber) beams are popular, because they are strong and can be manufactured in any length and depth.

found on a foundation plan indicating the type and size of girder to be used are shown in **Figure 16-3**. The girder in **Figure 16-3** is to be built up of three 2×10 s.

Determining the Heights of Columns and Piers

The length of the columns or height of the piers depends on how the joists will be attached to the girder. The floor joists may rest directly on top of the girder or may be butted against the girder so that the top surface of the floor joist is flush with the top surface of the girder (see **Figure 16-6**).

To find the height of the columns or piers, first determine the dimension from the basement floor to the finished first floor. Then subtract from this dimension the



GREEN NOTE

Designers, especially those designing with an eye toward green homes, have to weigh the strengths and weaknesses of every material choice they make. In choosing material for a girder, the green designer may see some benefits in using laminated veneer lumber (LVL) instead of built-up lumber girders or steel girders. LVL can be produced in any length and a wide range of thicknesses and depths, yet even the longest LVL girder is made up of smaller pieces of material. This means that high strength can be achieved while using material that might otherwise have been destined for the scrap pile.




Figure 16-6. Several methods of attaching joists to girders.

depth of the first floor, including all of the framing and the girder. Then add the distance from the top of the basement floor to the bottom of the column. The result equals the height of the column or pier. (See Math Reviews 5 and 6 in Appendix B.) For example, the following shows the calculation of the height of the steel column in **Figure 16–7**:

- Dimension from finished basement floor to finished first floor = 8'-10½"
- Allowance for finished floor = 1"
- Nominal 2 × 8 joists = 7¼"
2 × 4 bearing surface on girder = 1½"
W8 × 31 = 8"
- Total floor framing = 17¾" or 1'-5¾"
- Subtract total floor framing
8'-10½" minus 1'-5¾" = 7'-4¾"
- Add thickness of concrete slab
7'-4¾" plus 4" = 7'-8¾"




Figure 16–7 Calculate the height of the steel column.



USING WHAT YOU LEARNED

Laminated veneer lumber (LVL) is a popular material for girders in light construction, because it is strong and available in any length desired. Describe three ways floor joists made of dimensional lumber might be supported by an LVL girder.

1. The joists can rest on top of the girder.
2. A ledger piece can be nailed along the bottom of the LVL to support the joists.
3. Metal joist hangers can be used.

If *I*-joists (often called TJIs, which are discussed in Unit 17) are used for the joists, they would most likely span the full width of the floor and rest on top of the girder, because I-joists are available in greater lengths than dimensional lumber.

Assignment

Questions 1 through 5 refer to **Figure 16–8**.

1. What is the length of the girder?
2. Describe the material used to build the girder, including the size of the material.
3. What supports the span of the girder? (Include material and cross-sectional size.)
4. How many posts, columns, or piers support the girder?
5. What is the height of the columns or piers supporting the girder, including bearing plates?

Questions 6 through 9 refer to **Figure 16–9**.

6. What is the length of the girder?
7. Describe the material used to build the girder, including the size of the material. What supports the span of the girder? (Include material and cross-sectional size.)
8. How many posts, columns, or piers support the girder?
9. What is the dimension from the top of the footing under the pier to the top of the steel beam?







Figure 16-8



Note: Nominal Size to Actual Size Lumber

Nominal	Actual
2 x 4	1 1/2 x 3 1/2
2 x 6	1 1/2 x 5 1/2
2 x 8	1 1/2 x 7 1/4
2 x 10	1 1/2 x 9 1/4
2 x 12	1 1/2 x 11 1/4

Figure 16-9

UNIT 17

Floor Framing

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe the sill construction shown on a set of drawings.
- Identify the size, direction, and spacing of floor joists according to a set of drawings.
- Describe the floor framing around openings in a floor.

Sill Construction

Where the framing rests on concrete or masonry foundation walls, the piece in contact with the foundation is called the *sill plate* (see **Figure 17-1**). The sill plate is the piece through which the anchor bolts pass to secure the floor to the foundation. To prevent the sill plate from coming in direct contact with the foundation, and to seal any small gaps, a *sill sealer* is included. This is a compressible, fibrous material that acts like a gasket in the sill construction. All lumber in contact with the foundation, including the sill plate, must be *pressure treated* (PT) with an approved chemical to prevent decay.

The entire construction of the floor frame at the top of the foundation is called *sill construction* or the *box sill*. The box sill is made up of the sill sealer, sill plate, joist, and joist header or rim board (see **Figure 17-2**). The sizes of materials are given on a wall section or sill detail. For areas where termites are present, a termite shield is included in the sill construction (see **Figure 17-3**). A *termite shield* is a continuous metal shield that prevents termites from getting to the wood superstructure.



Figure 17-1. Sill plate.



GREEN NOTE

As our sources of lumber have become more depleted and the world's desire to protect our planet has become greater, engineers have developed an increasing array of engineered wood products. These are usually building materials that use wood fibers, wood chips, veneer, and short pieces of wood as their basis, but the wood materials are bound together with synthetic resins. One such material is rim board, a specially engineered product designed for use as the joist header for I-joists. Rim board is made of bonded wood particles much like OSB.




Figure 17-2. Box sill.




Figure 17-3. Termite shield.

Floor Joists

Floor joists are the parallel framing members that make up most of the floor framing. Until recently, joists in residential construction were 2-inch framing lumber. However, recent advances in the use of materials have produced several types of engineered joists (see **Figure 17-4**). A common type of engineered wood joists is the I-joist, consisting of a top and bottom rib of solid wood and a thinner plywood web between the ribs. I-joists are often




Figure 17-4. Typical joist styles.



GREEN NOTE

I-joists are becoming increasingly popular for use as floor and ceiling joists because they are lighter than dimensional lumber, are available in greater lengths, and are dimensionally stable. They do not expand and contract or warp nearly as much as conventional lumber with changes in moisture content. They are lighter than dimensional lumber because they use far less material. Weighing less, they require less fuel to transport. Being more dimensionally stable, they are less apt to cause weaknesses in the structure or openings for air infiltration.

called TJIs because the first I-joists, introduced over 40 years ago, were named after the Trus Joist Institute, which developed the first I-joists. Although the materials in each type are different, their use is essentially the same. The joist header in each case is of similar material to the joist. When I-joists are used the header is typically an engineered rim board that is manufactured to have the same depth as the I-joists (see **Figure 17-5**).

Metal floor joists are often used in commercial and industrial construction. Where nonmetallic-sheathed cable is installed through metal studs or floor joists, a bushing or grommet must be installed prior to installing the cable (see **Figure 15-16**).



Courtesy of Weyerhaeuser NR Company

Figure 17-5. When I-joists are used for floor framing, the joist header is usually an engineered rim board.

Notes on the floor plans indicate the size, direction, and spacing of the joists in the floor above (see **Figure 17-6**). For example, notes on the foundation plan give the information for the first floor framing. When





Figure 17-6. Joist callouts for the first floor are shown on the foundation plan.



FLOOR FRAMING PLAN
SCALE: 3/16" = 1'-0"

Figure 17-7. A simple floor framing plan.

the arrangement of framing members is complicated, a framing plan may be included (see **Figure 17-7**). On most framing plans, each member is represented by a single line.

In the simplest building, all joists run in the same direction and are supported between the foundation walls by a single girder. However, irregularities in building shapes require that joists run in different directions (see **Figure 17-8**). As the building design becomes more complex, more variations in floor framing are necessary. In a building such as

the Lake House, which has floors at varying levels, the joists are supported by a combination of girders, beams, and load-bearing walls.

Lake House Floor Framing

The floor framing for the Lake House is shown on Framing Plan 1/6 in your textbook packet. Notice that the framing plan is made up of a simplified floor plan and single lines to represent floor joists, beams, and joist headers. A more elaborate type of framing plan uses double lines to represent the thickness of each




Figure 17-8. Floor framing plan for an irregular-shaped house.

member (see **Figure 17-9**). The framing plan shows the location and direction of framing members, but for more detail, it will be necessary to refer to Floor Plan 2/2 also.

The floor framing in the Lake House can be studied most easily if it is viewed as having four parts: the kitchen, bedroom #1, bedroom #2 and bathrooms, and the loft. There is no floor framing for the living room and dining room. These two areas form the heat sink for the passive-solar features discussed in earlier units. The floors in these rooms are concrete to absorb and radiate solar heat. As each area is framed, the carpenter must identify the following:

- Joist headers (locate the outer ends of joists)
- Bearing for inner ends of joists (beams, walls, etc.)
- Size and type of framing materials

- Length of joists
- Spacing
- Framing at openings

The joist headers are easily identified on the framing plan, but their exact position should be checked on the detail drawings. They may be set back to create a brick ledge, to accommodate wall finish, or to be flush with the foundation (see **Figure 17-10**).

The *bearing* (support) for the inner ends of some of the joists in the Lake House is the structural-steel-and-LVL-beam core, Detail 5/6. This core consists of four 3½-inch square steel posts with LVL beams and steel-channel beams. The positions of the posts are shown on all plan views of the house. The C8 × 11.5 steel acts as a beam to support the floor in bedroom #2. The doubled smaller LVLs support the loft. The LVL beams form part of the roof framing. All of the






Figure 17-9. Double-line framing plan.



Courtesy of W. D. Farmer

Figure 17-10. The joist headers are positioned according to the exterior finish to be used.

LVL beams rest in beam pockets that are welded to the posts. The structural steel channel (C8 × 11.5) is bolted directly to the posts.

The inner ends of the remaining floor joists in the Lake House are supported by bearing walls in the lower level. For example, some of the kitchen floor joists are supported by the west wall of the playroom, near the fireplace, and some by the LVL beam that spans the distance from the playroom wall to the foundation in the crawl space.

The size and spacing of material to be used are given on the framing plan by a note. They can also be found on the wall section. Lengths of framing members are usually not included on framing plans. However, these lengths can be found easily by referring to the floor plan that shows the location of the walls or beams on which the joists rest. For example, refer to **Figures 17–11** and **17–12** and find the length of the floor joists in bedroom #2 as follows:

1. The dimension from the outside of the north wall to the centerline of the 3½" □ steel post is 14'-1".
2. The dimension from the centerline of the 3½" □ post is 2", so the overall dimension of the bedroom floor is 14'-3".

3. According to Wall Section 3/4, the rim board is flush with the north foundation wall, so subtract 1¼" (the thickness of the rim board) from each end.
4. 14'-3" minus 2½" (1¼" at each end) equals 14'-1½" (the length of the joists).

Some floor framing is cantilevered to create a seemingly unsupported deck.

Cantilevered framing consists of joists that project beyond the bearing surface to create a wide overhang. This technique is used extensively for balconies, under bay windows, and for garrison-style houses (see **Figure 17–13**).

Framing at Openings

Where stairs and chimneys pass through the floor frame, some of the joists must be cut out to form an opening. The ends of these joists are supported by headers made of two or more members. The full joists at the sides of the opening have to carry the extra **load** of the shortened joists and headers, so they are also doubled or tripled (see **Figure 17–14**). The number of joists and headers required around openings of various sizes is spelled out in building codes and shown on framing plans.




Figure 17-11. Part of the Lake House Floor Plan.




Figure 17-12. Part of the Lake House wall section.






Figure 17-13. Typical uses of cantilevered framing.




Figure 17–14. Framing around an opening in the floor.



USING WHAT YOU LEARNED

Whether you are actually building the house or estimating the cost of building the house, you need to determine the exact length of all of the floor joists. Some times this requires using more than one of the many sheets of drawings. In this practice exercise, we will find the length of the floor joists in the Lake House kitchen floor.

The Floor Framing Plan, Drawing 1/6, on Sheet 6 tells us that the kitchen floor is framed with $1\frac{3}{4}'' \times 9\frac{1}{2}''$ TJs spaced 16" OC. If we look at the Upper Level Floor Plan, where the kitchen is shown, we see a symbol indicating a section view of the floor construction on Drawing 2/4. That is drawing number 2 on Sheet 4. Section 2/4 shows us where each end of the joist is supported. The west or left end rests on the foundation and ends at a $1\frac{1}{4}''$ engineered rim board, according to the typical Wall Section 3/4. That rim board is flush with the outside of the foundation wall. The east or right end rests on a frame wall beside the fire place in the play room, shown on the Lower Level Floor Plan. The east end has another $1\frac{1}{4}''$ engineered rim board, which is flush with the Playroom side of the frame wall. The face of the playroom wall is 2 inches east of the centerline of the steel posts. The Foundation Plan on Sheet 1 shows that the centerline of the steel posts is 14' -1" from the face of the foundation, so the face of the playroom wall is 14' -3" from the face of the foundation wall. Subtract $1\frac{1}{4}'$ from each end for the rim boards to find the length of the kitchen floor joists as 14' -0 $\frac{1}{2}''$

Assignment

Refer to the Lake House drawings in your textbook packet to complete this assignment.

1. What is used for the floor framing in bedroom #2?
2. What size lumber is used for the floor joists in the loft?
3. What size lumber is used for the joist headers in the loft?
4. How long are the joists in the loft?
5. How long are the floor joists in bedroom #1?
6. What supports the west end of the floor joists in bedroom #1?
7. What supports the south end of the floor joists in bedroom #2?
8. How long are the floor joists in bedroom #2?
9. How many floor joists are needed for bedroom #2 and the adjacent closets?
10. What size material is used for the sill?
11. What does the double $1\frac{3}{4}'' \times 9\frac{1}{2}''$ LVL in the structural core of the Lake House support?
12. How long are the headers that support the loft floor joists?
13. Is the box sill of the Lake House flush with the foundation wall or set back?
14. When an opening in a floor is framed, why are the joists at the sides of the opening doubled?

UNIT 18

Laying Out Walls and Partitions

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe the layout of a house from its floor plans.
- Find specific dimensions given on floor plans.

When the deck (framing and subfloor or concrete slab) is completed, the framing carpenter lays out the location of walls and partitions. The size and location of each wall are indicated on the floor plans. Drawings 1/2 and 2/2 are the floor plans for the Lake House.

Of all the sheets in a set of construction drawings, the floor plans often contain the most information. Before looking for specific details on floor plans, it may help to mentally walk through the house. Start at the main entrance to the main floor, and visualize each room as if you were walking through the house.

Visualizing the Layout of Walls and Partitions

The lowest floor with frame walls in the Lake House is the basement. Start at the $6^0 \times 6^8$ sliding glass doors (H) in the southeast corner of the playroom. This large L-shaped room covers most of the basement floor. Some plans list overall dimensions for each room. The plans for the Lake House give this information by conventional dimension lines only. Many of the dimensions of the Lake House framing are referenced to the columns of the structural steel core. The faces of some of the walls are an inch or two from the centerlines of the columns, but for the sake of visualizing the layout of the house, these centerline dimensions are close enough to develop a good mental picture of the layout.

The north–south dimension of the playroom is 28'-3". The east–west dimension of the north part of the playroom is 14'-1". The section of the playroom with the fireplace is 13'-10" by 13'-10". It may be helpful to notice the overall dimensions of each room as you visualize its shape and relationship to other rooms. It will be necessary to refer to these dimensions many more times. At the north end of the playroom is a small closet. South of the closet is a hall leading to the bathroom and utility room.

The bathroom has a shower, water closet (toilet), and lavatory. Notice that although most interior partitions are $3\frac{1}{2}$ inches thick, the wall behind the water closet and lavatory is $5\frac{1}{2}$ inches thick. This thicker wall is called a *plumbing wall*. Its extra thickness allows room for plumbing (see **Figure 18–1**).

The purpose of the utility room beyond the bathroom is to house mechanical equipment such as the water heater, furnace or boiler, and water pump. In the southwest corner of the utility room is a small opening into the crawl space on the west side of the house.




Figure 18-1. 6-inch plumbing wall.




Figure 18-2. Lake House playroom.

Walking back through the playroom to the stairs, you will see some interesting features (see **Figure 18-2**). A broken line in this area indicates the edge of a floor above. These floors can be seen more easily on the first floor plan. Also notice the location of the fireplace, which will extend up through the upper floor. The L-shaped stairs lead up to the first floor. It is obvious that this is not a full story higher because a callout indicates that there are only five risers. This can be seen more

clearly in the sections on Sheet 4 of the Lake House in your textbook packet. The L-shaped stairs lead up to the living room (see **Figure 18-3**). Against the west and south walls of the living room is a plywood platform or built-in bench.

Another set of stairs in the northwest corner of the living room leads to the kitchen and dining room. These rooms are separated only by a peninsula of kitchen cabinets. The kitchen is separated from a hall by a free-standing closet and enclosure for the refrigerator and oven (see **Figure 18-4**). This closet and enclosure cannot be recognized as free-standing (meaning they do not reach the ceiling) on the floor plan. However, this can be seen on Section 2/4. On the north side of the kitchen is a door to the deck outside. The east side




Figure 18-3. Lake House living room.




Figure 18-4. Lake House kitchen.

of the hall has a railing that continues up another set of stairs to the upper hall. Beyond this railing, the floor is open to the playroom below.

Above the open area of the playroom is a loft that provides storage or extra sleeping space (see **Figure 18-5**). Access to the loft is by a ladder in the upper hall. The loft is shown on a separate plan on Sheet 4. The loft is suspended on two beams of $1\frac{3}{4}'' \times 9\frac{1}{2}''$ LVL. The north and south sides of the loft are enclosed by a wall 2'-6'' high. The east and west ends have a railing.

A door at the end of the upper hall opens into bedroom #1. On the east side of this bedroom is a hall that leads past a large (7'-1'' \times 5'-1'') closet to toilet #1 in the northeast corner of the house. This toilet room has only a lavatory and water closet. A tub in the next room also serves toilet #2 to the east. Toilet #2 has a closet with shelves for linen storage. This toilet room can also be entered from the upper hall. The remaining room is bedroom #2.

The garage is attached to the house only by the wood deck and the roof. The garage is a rectangular building with 4-inch walls, an overhead door, and a walk-through door.

Finding Dimensions

When you understand the relationships of the rooms to one another, you are ready to look for more detailed information. Frame walls are dimensioned in one of two ways (see **Figure 18-6**). Exterior walls are usually dimensioned to the face of the studs. Interior walls may




Figure 18-5. Lake House loft.




Figure 18-6. Two types of dimensioning.





Figure 18-7. It is important to consider the true size of the framing material when working with OC dimensions.

be dimensioned either to the face of the studs or to their centerlines.

When walls are dimensioned to their centerlines, one-half of the wall thickness must be subtracted to find the face of the studs. For example, in **Figure 18-7**, the end walls are 12'-4'' on centers. However, the plates for the side walls are 12'-0 $\frac{1}{2}$ '' long (12'-4'' minus 3 $\frac{1}{2}$ '', the width of the studs, equals 12'-0 $\frac{1}{2}$ '').



Courtesy of Robert C. Kurzon.

Figure 18-8. Dimensions are placed in neat strings as much as possible.

Dimensions are usually given in a continuous string where practical (see **Figure 18-8**). Overall dimensions and major wall locations are given outside the view. Minor partitions and more detailed features are dimensioned either on or off the view, whichever is most practical.

The Lake House includes an angled wall. The length of such walls can be accurately found by trigonometry. However, the accuracy obtained by measuring with an architect's scale should be adequate for normal estimating.

As each wall is laid out, the plates are cut to length, and the positions of all openings and intersecting walls are marked. The wall frame is usually assembled flat on the deck. Its position is marked on the deck with a chalk line; then the assembly is tipped up and slid into place.

Commercial buildings may require a thicker wall, where the electrical service panel is flush mounted and the panel box is deeper than the standard 3½-inch wall. Many times this thicker wall requirement is not shown on the floor plan or drawing details.

The utilities that are to be stubbed up from a concrete floor slab into a wall are installed prior to floor slab-concrete placement and, therefore, prior to the wall locations being determined by the framing contractor. The utility installer must be able to accurately predetermine the specific wall locations.



USING WHAT YOU LEARNED

Each piece of framing material must be precisely positioned according to the construction drawings. What is the dimension from the inside of the framing of the west wall of the kitchen to the outside of the west end of the loft?

All of the information necessary to determine this dimension is shown on the Upper Level Floor Plan 2/2. Above the loft, in bedroom #2, there is a string of dimensions that show the edge of the loft to be 2'-2" from the inside face of the wall and another 2" to the centerline of the 3½" \square steel post. At the bottom of the Floor Plan is a dimension of 14'-1" from the centerline of the posts to the outside of the west wall and another dimension that shows the wall framing to be 5½" thick: $(2'-2") + 2" + (14'-1") - 5\frac{1}{2}" = 15'-11\frac{1}{2}"$.

Assignment

Refer to the Lake House drawings (in the packet) to complete the following assignment.

1. What is the inside dimension of each room? Use face-of-framing dimensions. Disregard slight irregularities in room shape, but remember to allow for wall thicknesses. Do not include the kitchen and dining room.


Room	N-S dimension	E-W dimension
<i>Utility</i>		X
<i>Basement Bath</i>		X
<i>Living Room</i>		X
<i>Bedroom #1</i>		X
<i>Bedroom #2</i>		X
<i>Toilet #1</i>		X
<i>Tub</i>		X
<i>Toilet #2</i>		X
<i>Loft</i>		X

2. How many lineal feet of 2×4 frame wall are there in the basement?
3. How many lineal feet of 2×6 frame wall are there in the basement?
4. What is between the dining room and the living room?
5. What is directly below the loft?
6. What is directly below the tub room?
7. How many lineal feet of 2×6 frame wall are there on the Upper Level Floor Plan?
8. What utilities must be roughed in prior to concrete slab placement?
9. Where would you find the utility concrete slab rough-in requirements?

Framing Openings in Walls

19

Two types of dimensions must be known before window and door openings can be framed: location and size. Opening locations are given by dimensioning to their centerlines in a string of dimensions outside the floor plan (see **Figure 19-1**). Such dimensions are usually given from the face of the studs. One-half the rough opening is then allowed on each side of the centerline.



Courtesy of Robert C. Kurzon.

Figure 19-1. The locations of openings in framed walls are usually given to their centerlines. The ± on the sliding door dimensions allows the builder to place the doors next to the corner post.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe typical rough openings.
- Locate and interpret specific information for framing openings.

Dimensions of Rough Openings

The size of the *rough opening* (RO), or opening in the framing, is listed on the door and window manufacturers' specifications. Door and window schedules are lists of all doors and windows in the house, usually with nominal dimensions (see **Figure 19–2**). Doors and windows are identified on the floor plan by a *mark*—a letter or number. All doors or windows of a certain size and type have the same mark. Each mark is listed on the schedule with the

information for the doors or windows of that type and size.

The rough opening dimensions are not usually given on the drawings. They should be obtained from the manufacturer. Window manufacturers do not list the same size information in their literature, but they do list the rough opening size. Other sizes they sometimes list are nominal size or unit dimensions (approximate overall size of the window) and glass size (size of the actual glass in the window) shown in **Figure 19–3**. If the

SCHEDULE OF WINDOWS				
⬡	SIZE	TYPE	GLASS	COMMENTS
A	3'-0" X 3'-0"	THERMAL BREAK ALUMINUM	5/8" INSULATED	
B	3'-0" X 5'-0"	O.O.	O.O.	
C	4'-0" X 4'-0"	O.O.	O.O.	
D	4'-0" X 5'-0"	O.O.	O.O.	
E	5'-0" X 5'-0"	O.O.	O.O.	
F	6'-0" X 4'-0"	O.O.	1" INSULATED	
G	6'-0" X 5'-0"	O.O.	1" INSULATED	
H	6'-0" X 6'-8"	O.O.	1" TEMP. INSUL.	SLIDING GLASS DOORS

SCHEDULE OF DOORS									
○	SIZE	THK	DOOR		FRAME		GLASS	LOCKSET	COMMENTS
			MAT'L	TYPE	MAT'L	TYPE			
001	2'-8" X 6'-8"	1 3/8	WD.	C	WD.	A		CLASSROOM	
002	2'-0" X 6'-8"	1 3/8	WD.	C	WD.	A		PRIVACY	
003	PR 2'-0" X 6'-8"	1 3/8	WD.	D	WD.	A		PASSAGE R.H. DUMMY TRIM L.H.	
101	3'-0" X 6'-8"	1 3/4	H.M.	A	WD.	A	1" INSUL.	ENTRY	1'-8" SIDE LIGHT
102	3'-0" X 6'-8"	1 3/4	H.M.	B	WD.	A		ENTRY	
103	PR 2'-4" X 6'-8"	1 3/8	WD.	D	WD.	B		NONE	BI-PASSING HDWARE
104	2'-6" X 6'-8"	1 3/8	WD.	C	WD.	B		PRIVACY	
105	PR 2'-6" X 6'-8"	1 3/8	WD.	D	WD.	B		PASSAGE R.H. DUMMY TRIM L.H.	
106	2'-0" X 6'-8"	1 3/8	WD.	C	WD.	B		PRIVACY	
107	(4) 1'-0" X 6'-8"	1 3/8	WD.	E	WD.	B		NONE	BI-FOLDING HDWARE
108	2'-0" X 6'-8"	1 3/8	WD.	C	WD.	B		PRIVACY	
109	2'-0" X 6'-8"	1 3/8	WD.	C	WD.	B		PRIVACY	
110	2'-6" X 6'-8"	1 3/8	WD.	C	WD.	B		PRIVACY	
III	2'-0" X 6'-8"	1 3/8	WD.	C	WD.	B		PASSAGE	
112	2'-6" X 6'-8"	1 3/8	WD.	C	WD.	B		PRIVACY	

Courtesy of Robert C. Kurzon.


Figure 19–2. Window and door schedules list all the windows and doors and their sizes.

Table of Basic Casement Unit Sizes Scale 1/8" = 1'-0" (1:96)

Unit Dimension	1'-5"	1'-8 1/2"	2'-0 1/8"	2'-4 3/8"	2'-7 1/2"	2'-11 15/16"	2'-9 3/4"	3'-4 3/4"	4'-0"	4'-8 1/2"					
Minimum Rough Opening	1'-5 1/2" (445)	1'-9" (533)	2'-0 5/8" (625)	2'-4 7/8" (733)	2'-8" (813)	3'-0 1/2" (927)	2'-10 1/4" (870)	3'-5 1/4" (1048)	4'-0 1/2" (1232)	4'-9" (1448)					
Unobstructed Glass*	12 5/8" (321)	16 1/8" (410)	19 3/4" (502)	24" (610)	27 1/8" (689)	31 9/16" (802)	12 5/8" (321)	16 1/8" (410)	19 3/4" (502)	24" (610)					
Unobstructed Glass Transom Units Only	12 3/16" (310)	15 11/16" (398)	19 5/16" (491)	23 9/16" (599)	26 11/16" (678)	31 1/8" (791)	28 15/16" (735)	35 15/16" (913)	43 3/16" (1097)	51 11/16" (1313)					
1'-0"	305	1'-0 1/2"	318	7 3/16"	183	CTR1510 †	CTR1810 †	CTR2010 †	CTR2410 †	CTR2810 †	CTR3010 †	CTR2910 †	CTR3410 †	CTR4010 †	CTR4810 †
2'-0 1/8"	613	2'-0 5/8"	625	19 5/16"	491	CR12	CN12	C12	CW12						
2'-4 3/8"	721	2'-4 7/8"	733	23 9/16"	598	CR125	CN125	C125	CW125	CX125					
2'-11 15/16"	913	3'-0 1/2"	927	31 1/8"	791	CR13	CN13	C13	CW13	CX13	CXW13	CR23	CN23	C23	CW23
3'-4 13/16"	1037	3'-5 3/8"	1051	36"	914	CR135	CN135	C135	CW135 †	CX135 **	CXW135 †	CR235	CN235	C235	CW235 †
4'-0"	1219	4'-0 1/2"	1232	43 3/16"	1087	CR14	CN14	C14	CW14 †	CX14 †	CXW14 †	CR24	CN24	C24	CW24 †
4'-4 13/16"	1341	4'-5 3/8"	1356	48"	1219	CR145	CN145	C145	CW145 †	CX145 †	CXW145 †	CR245	CN245	C245	CW245 †
4'-11 7/8"	1521	5'-0 3/8"	1534	55 1/16"	1399	CR15	CN15	C15	CW15 †	CX15 †	CXW15 **	CR25	CN25	C25	CW25 †
5'-4 13/16"	1646	5'-5 3/8"	1660	60"	1524	CR155	CN155	C155	CW155 †	CX155 †	CXW155 **	CR255	CN255	C255	CW255 †
5'-11 7/8"	1826	6'-0 3/8"	1838	67 1/16"	1703	CR16	CN16	C16	CW16 †	CX16 †	CXW16 **	CR26	CN26	C26	CW26 †

CTR units are non-venting.

- * "Unobstructed Glass" measurement is for single sash only.
- ** These units have straight arm operators, see opening specifications.
- † CW series units (except CW2, CW25 and CW3 height) open to 20" clear opening width using sill hinge control bracket. Bracket can be pivoted allowing for cleaning position. CW series units are also available with a 22" clear opening width.
- ‡ Andersen® art glass panels are available for these units by special order only. Contact your Andersen® supplier. Panels are available for all other units on this page through normal ordering process.
- These units meet or exceed the following dimensions: Clear Openable Area of 5.7 sq. ft., Clear Openable Width of 20" and Clear Openable Height of 24" when appropriate hardware (straight arm or split arm) is specified.
- Casement transom units (CTR) may be rotated to be used as a casement or awning side light.
- Rough opening dimensions may need to be increased to allow for use of building wraps, flashings, sill panning, brackets, fasteners or other items. See page 10 for more details.
- "Unit Dimension" always refers to outside frame to frame dimension.
- Dimensions in parentheses are in millimeters.
- When ordering, be sure to specify color desired: White, Sandtone, Terratone® or Forest Green.



Venting Configuration
 Hinging shown on size table is standard. Specify left, right or stationary, as viewed from the outside. For other hinging of multiple units, contact your local supplier.

Figure 19-3. Typical manufacturer's table of window sizes. The rough opening sizes are in the gray-shaded area of the table.

finished doorway, the *jamb*, is to be built on the site by a carpenter, the rough opening size will not be available. In this case, the rough opening for swing doors can be built 2 inches wider and 2 inches higher than the door. If the door is another type, you must first determine what the finished opening is to be. Manufacturers of hardware for sliding and bifold doors specify rough opening sizes for doors installed with their hardware. These manufacturer's specifications should be consulted as the opening is being framed.

Sizes of doors and windows are given with the width first and height second. To further simplify dimensioning, they are often listed as feet/inches. For example, a $2^6 \times 6^8$ door is 2 feet, 6 inches wide by 6 feet, 8 inches high.

The information in this unit is intended only to help you determine rough opening sizes. More information about windows and doors can be found in Unit 25.

Framing Openings

In stud-wall construction, it is usually necessary to cut off or completely eliminate one or more studs where windows and doors are installed. The load normally carried by these studs must be transferred to the sides of the opening. The construction over an opening that transfers this load to the sides of the opening is called the *header*. Additional studs are installed at the sides to carry this load (see **Figure 19-4**).

A set of construction drawings includes details showing the type of rough opening construction intended. It has been conventional to build headers in exterior walls with two 2×10 s or 2×12 s and plywood spacers between to form the header (see **Figure 19-5**). A flat 2×4 may be nailed to the bottom of the header to reduce the height of the top of the opening, but this flat 2×4 is filler and not a structural part of the header.

Following advanced framing techniques, the header may be a single $2 \times$ installed flush with the exterior surface of the wall framing. The decision to use a single-ply header must be made by an engineer, considering the loads that will be imposed on the header. The framing around the opening can sometimes be further simplified by replacing the jack studs with steel header hangers, as shown in **Figure 19-6**.




Figure 19-4. The jack studs support the header.




Figure 19-5. Built-up header.

To conserve lumber in nonbearing walls, the header may be two 2×4 s. The area over the header is framed with cripple studs. The area below a window also is framed with *cripple studs* (see **Figure 19-7**). These cripple studs are installed on the normal spacing for wall studs. This may require a cripple within a few inches of a side jack stud but is necessary to provide a nailing surface for the sheathing.




Figure 19-6. Advanced framing techniques around window or door opening.




Figure 19-7. The spaces above and below the window opening are framed with cripple studs.



Courtesy L. E. Johnson Products, Inc.

Figure 19-8. Pocket door frame.

Pocket doors are sliding doors that slide into an opening in the wall, thereby allowing the largest possible opening without swinging into the room. Most builders install pocket doors as a pre-assembled frame (see **Figure 19-8**). The wall framing to provide the opening into which a pocket door assembly can be installed is generally the same as the framing for any other type of door. Pocket door manufacturers provide rough opening dimensions for their products.

Several systems of metal framing are available for light construction. The basic elements of light-gauge metal framing are the same as for wood


framing (see **Figure 19–9**). These systems use top and bottom wall plates, studs, and floor joists. To make light-gauge framing compatible with wood, the metal members are made in common sizes for wood framing. The greatest difference is that metal framing is joined with screws instead of nails.

Headers over openings in light-gauge metal framing are usually very similar to those in wood framing. However, the system designed by the metal framing manufacturer should always be followed.



GREEN NOTE

The APA—The Engineered Wood Association publishes several Design and Construction Guides on a variety of topics suggesting ways to use wood products more efficiently and to make structures more durable. Most of these guides are fairly recent, so the techniques described in them have not been adopted by all designers and builders. Anyone in a position to make decisions about construction techniques would do well to become familiar with these and other modern construction developments.



Courtesy of Zinc Institute, Inc.

Figure 19–9. The parts of this steel frame are the same as those of a wood frame. Notice the window header and cripple studs.



USING WHAT YOU LEARNED

Carpenters must calculate the lengths of all of the headers over windows and doors. Assuming the rough opening is to be 2 inches greater than the width of the door, how long must the header be over the door into the bath on the lower level of the Lake House?

This is door #002. The Schedule of Doors on Sheet 6 tells us that it is a 2'-0" × 6'-8" door. (That is a narrow doorway, but there is not enough space for a larger door.) The header rests on a 2 × 4 at each end, so the header length will be 3 inches longer than the rough opening (1½ inches at each side of the opening). Add the dimensions to find the length of the header: 2'-0" + 2" + 3" = 2'-5".

Assignment

Refer to the Lake House drawings in your textbook packet to complete this assignment.

1. What type of header should be used over the door from the hall to bedroom #1?
2. What type of header should be used over the door from the deck to the kitchen?
3. Why should these two headers be made differently?
4. What is the length of the header over the garage overhead door? Allow for two trimmers at each side and 1 inch at each side for jambs.
5. What are the R.O. dimensions for the door from the deck into the garage?
6. Name the location and give the R.O. dimensions for each interior door on the Upper Level Floor Plan.
7. According to **Figure 19–3**, what are the R.O. dimensions for the windows in bedroom #2?
8. How long is the header over the window in bedroom #2?
9. How many cripple studs are needed beneath the windows in the south wall of the living room?
10. What is the length of the cripple studs beneath the window in bedroom #2? (Assume the bottom of the header is 6'–8½" from the top of the subfloor.)

UNIT 20

Roof Construction Terms

Objectives

After completing this unit, you will be able to perform the following tasks:

- Identify common roof types.
- Define the terms used to lay out and construct a roof.
- State roof pitches as a ratio of rise to run or as a fraction.

Types of Roofs

Several types of roofs are commonly used in residential construction (see **Figure 20–1**). Variations of these roof types may be used to create certain architectural styles.

The *gable roof* is one of the most common types used on houses. The gable roof consists of two sloping sides that meet at the ridge. The triangle formed at the ends of the house between the top plates of the wall and roof is called the *gable*.

The *gambrel roof* is similar to the gable roof. On this roof, the sides slope very steeply from the walls to a point about halfway up the roof. Above this point, they have a more gradual slope.

The *hip roof* slopes on all four sides. The hip roof has no exposed wall above the top plates. This means that all four sides of the house are equally protected from the weather.

The *mansard roof* is similar to the hip roof, except the lower half of the roof has a very steep slope and the top half is more gradual. It is also similar to a hip roof in that the roof slopes on all four sides.

The *shed roof* is a simple sloped roof with no ridge. A shed roof is much like one side of a gable roof. This type of roof is used in modern architecture and for additions to existing buildings.

Roof Construction Terms

The roof construction terms used with trussed roofs, the most common type of roof framing for light construction, are defined below and shown in **Figure 20–2**.

- *Top chord* is the top member in the truss.
- *Bottom chord* is the bottom member of the truss and acts as a ceiling joist for the space below.
- A *web* member is any of the interior bracing between the top chord and the bottom chord.
- A *gusset* is a reinforcing piece of metal or plywood fastened to the truss, where members are joined.
- *Span* is the distance between the outsides of the walls covered by a roof.
- *Rise* is the vertical distance or height of the roof.
- The *overhang* is the horizontal distance covered by the roof outside the walls.
- The *tail* is the portion of the top chord that is outside the walls.
- The *slope* of a roof is a way of indicating how steep the roof is. The slope of a roof is usually given as the number of inches of rise per foot of run.




Figure 20-1. Common roof types.

This is called *unit rise*. Another way of stating the steepness of a roof is *pitch*. Pitch is the rise of the roof divided by the span and is stated as a fraction.

In writing unit rise, the slope is given as the number of inches of rise for every 12 inches of run (see **Figure 20-3**). The rise per foot of run is given on drawings with the symbol ∇ . The horizontal leg of this symbol represents the run. The vertical leg represents the rise as shown in **Figure 20-4** and



GREEN NOTE

By planning the slope and overhang of the roof, the designer can minimize the amount of scrap material that is generated in its construction. The ideal dimensions for a roof section would be in 2-foot increments. Most roof framing is spaced either 16 inches on center or 2 feet on center. A roof that is multiples of 2 feet in length and width (ridge to eave) will not require extra framing if it is framed 2 feet on centers. Also, the roof decking that is usually sheets of 4-foot wide material will have only 2-foot wide scraps if the width of the roof is a multiple of 2 feet. The 2-foot scraps can usually be used on the next row of decking.

Steeper roofs have more roof area than do low-sloped roofs. The designer can make the roof width fit the 2-foot grid by adjusting the slope of the roof.




Figure 20-2. Parts of a roof truss.




Figure 20-3. Rise per foot of run. This roof has a 4 in 12 slope.




Figure 20-4. Roof slope is usually shown on building elevations.

When the dimensions are given for a run of other than 12 feet, the rise per foot of run can be calculated: Divide 12 by the actual run to find the proper ratio of rise. Multiply this result by the actual rise to find the rise per foot of run. For example, if the run is 14'-6" and the rise is 5'-0"; what is the rise per foot of run? $12 \div 14.5' = 0.83$. Multiply this rise per foot of run times the total rise of the roof. $0.83 \times 5 = 4.15$. The unit rise of this roof is approximately 4 1/8", close enough to 4 that rafter calculations can be based on 4 in 12.

notice that this figure illustrates two roof slopes. These slopes are written as 10 in 12 and 5 in 12.

Although most modern roof frames are built with **trusses**, it is valuable to know something about rafter-framed roofs, because some special situations call for **rafters** to be cut and installed on the site. The terms defined in the following list are illustrated in Figure 20-5.

- The **run** is the vertical distance covered by one rafter. Run does not include any part of the rafter that extends beyond the wall. On a common two-sided roof with both sides having the same pitch, the run is one-half the span.
- The **measuring line** is an imaginary line along which all roof dimensions are taken. The measuring line of a rafter is a line parallel to its edges and passing through the deepest part of the bird's mouth.
- A **bird's mouth** is a notch cut in the lower edge of the rafter to fit around the top of the wall.
- The **ridge board** is the horizontal member to which the upper ends of the rafters are connected.



GREEN NOTE

Roof color matters. Lighter color roofs generally reflect more of the sun's energy than do darker colored roofs. Also smooth metal reflects more than does the rough surface of composition shingles. By reducing the amount of the sun's heat that is absorbed by the roof covering, the air-conditioning load of the building can be reduced.




Figure 20-5. Common roof terms.



USING WHAT YOU LEARNED

Whether the roof is framed with trusses or with site-built rafters, the same convention is used to write the slope of the roof. How would the slope of the roof shown in **Figure 20-6** be written on a building elevation? The slope will be written with a symbol and numbers indicating the number of units (inches or feet) of rise for every 12 units of run. The total rise of this roof is 7'-0" in 14'-0" of run. The rise in 12 feet would be the $\frac{12}{14}$ ths of the total rise. $\frac{12}{14} \times 7 = 6$, so the slope is written as $\frac{12}{6}$.

Assignment

1. Give the following information for the roof shown in **Figure 20-6**:
 - a. Span
 - b. Run
 - c. Rise
 - d. Overhang
 - e. Length of the truss tails
 - f. Unit rise

Refer to the Lake House drawings in your textbook packet to complete the rest of the assignment.

2. What style roof is used for most of the Lake House?
3. What is the span of the rafters over the garage?
4. What is the rise per foot of run of the rafters over the garage?
5. What is the run of the rafters over bedroom #1?
6. What is the rise per foot of run of the rafters over bedroom #1?
7. What is the overhang of the rafters over bedroom #1?




Figure 20-6.

UNIT 21

Roof Trusses

Objectives

After completing this unit, you will be able to perform the following tasks:

- Find information about trusses on plans, elevations, and sections.
- Identify the appropriate truss engineering drawing for each truss in a roof frame.
- Find key information on a truss engineering drawing.

Truss Information on Drawings

The roof is designed to support weight, withstand weather, and give protection to the spaces below. In most roofs, the frame is made up primarily of trusses; however, some special framing situations call for rafters. Designing trusses to withstand all the stresses that can be placed on them by wind or snow, or both, requires the skills of an engineer. Generally, the architect or designer who designs the house has some idea of what size and type of trusses will be required. The plans and elevations for the building show a lot of information about the trusses. The pitch of the roof can be seen in the building elevations (see **Figure 21–1**). Section views through the building show trusses, but the truss shown in a section might not be the truss the engineer designs. Notice that a note in the truss area in **Figure 21–2** says “NYS P.E. Approved Roof Trusses @24” O.C.” and gives load information that the truss designer will need. This note indicates that the trusses will be designed by a professional engineer (P.E.) who is licensed in New York State (NYS) and that they will be spaced 24 inches from the centerline of one truss to the centerline of the next truss. The snow accumulation may weigh up to 40 pounds per square foot on level ground and the wind might be up to 115 miles per hour. The roof framing shown on the drawing is only an outline to give the truss designer the information that is needed to design the trusses.

Truss Engineering Drawings

To see what the engineered trusses are, refer to the *truss drawings* from the engineer. These usually include a *delivery sheet* showing all the types of trusses used in the building (see **Figure 21–3**). This sheet usually shows the following information:

Profile: A small drawing showing the basic shape of the truss.

Quantity: Number of each type of truss needed for the building.

Truss ID: The engineer’s letter/number designation for that truss type.


Span: The distance between the outside walls the truss will cover.

Truss type: Some trusses are referred to as *piggyback trusses*. Large trusses can be too large to transport to the construction site, so they are delivered in two parts. The top of the main truss is flat, so the piggyback truss can be applied to it after it is in place.

Slope or pitch: The example here shows slope or the unit rise of the roof.

LOH: Left overhang—the amount of the top chord that must extend beyond the building wall.

ROH: Right overhang—the amount of the top chord that must extend beyond the building wall.



Courtesy of Charlew Builders, Inc. and Danforth H. Chriss

Figure 21–1. Roof slope can be seen in building elevations.

The packet of engineering drawings usually includes a *truss layout plan* like the one shown in **Figure 21–4**. This plan shows the position of each truss on the building, with a label to indicate the truss ID. If you know from where in the building the section view in **Figure 21–2** is taken, you can find that truss on the truss layout. The section view is labeled as A/5, so look at the second floor plan in **Figure 21–5** to see where the

cut was made to take section A/5. The section was cut through the master bedroom and master bath, which are on the left side of the house.

Looking at the front building elevations in **Figure 21–6** you can see that this house has a small gable on the roof above the main entrance. Refer to the truss layout, **Figure 21–4**, to see how this gable is to be framed. There is a triangle with three

















Figure 21–2. Building section.

trusses: V2, V1, and T2GE. The main roof trusses, T1A run beneath the trusses for the small gable, so the small trusses are applied on the main trusses after the main trusses are secured in place. Refer to the

truss delivery sheet to see what the trusses look like and how big they are. V1 and V2 are the last two trusses on the delivery sheet and T2GE is the fourth truss from the bottom.

Bellevue Builders Supply 500 Duaneburg Road Schenectady, NY 12306 (518) 355-7190 Fax: (518) 355-1371			To: Charlew Constr. 130 Princetown Plaza Schenectady, NY 12306				Delivery			
Project: Charlew/83 Tamarack Block No: Model: Lot No:			Deliver To: 83 Tamarack Lane Niskayuna, NY				Job Number: J16-02632			
Contact:	Site:	Office:					Page: 1			
Name:							Account No: 000000003			
Phone:							Designer: VB / VB			
Fax:							Salesperson: Mike Scheidel			
							Quote Number: B16-02632			
							P.O. Number: 9010847			
Profile:	Qty:	Truss Id:	Span:	Truss Type:	Slope	LOH	ROH			Load By:
	7	T3	38-10-00	PIGGYBACK	8.00	00-10-08	00-10-08	Bundle: 02632-A		
	1	T3SGE	38-10-00	GABLE	8.00	00-10-08	00-10-08	Bundle: 02632-B		
	6	T1A	32-10-08	COMMON	8.00	00-10-08		Bundle: 02632-C		
	10	T1	33-00-00	COMMON	8.00	00-10-08	00-10-08	Bundle: 02632-D		
	2	T1GE	33-00-00	GABLE	8.00	00-10-08	00-10-08	Bundle: 02632-E		
	3	T4	26-06-00	COMMON	8.00	00-10-08	00-10-08	Bundle: 02632-F		
	1	T4GE	26-06-00	GABLE	8.00	00-10-08	00-10-08	Bundle: 02632-F		
	7	PB1	08-05-12	GABLE	8.00			Bundle: 02632-G		
	1	PB1GE	08-05-12	GABLE	8.00			Bundle: 02632-G		
	1	T2GE	10-00-00	COMMON	10.00			Bundle: 02632-H		
	1	M1	05-09-08	MONOPITCH	8.00	00-10-08		Bundle: 02632-H		
	1	V1	06-09-09	VALLEY	10.00			Bundle: 02632-I		
	1	V2	03-07-03	VALLEY	10.00			Bundle: 02632-I		

Above listed items have been received in good condition. (Exceptions listed to right)


Received by: _____

Date: _____

Thank you for your business.

Courtesy of Bellevue Builders Supply

Figure 21-3. Truss delivery list.



Courtesy of Bellevue Builders Supply



Bellevue Builders Supply
 500 Duaneburg Rd.
 Schenectady, NY 12306
 (518) 355-7190

Customer: Charlew Constr.
 Job Name: Charlew/83 Tamarack
 Date: 12/13/16
 Designer: VB

Figure 21-4. Truss plan.





Figure 21-5. Second Floor Plan.



Courtesy of Charlew Builders, Inc. and Danforth H. Chriss

FRONT ELEVATION
SCALE: 1/4" = 1'-0"

Figure 21-6. First Floor Plan.

The truss engineering drawings are detail drawings for each truss type. Truss T1A is shown in **Figure 21–7**. The *truss detail* includes a drawing of the truss and all the engineering data required to build the truss. Carpenters do not usually build trusses, but the same packet of engineering drawings that go to the site with the trusses is also used in the truss shop to build the trusses. It is very important for the carpenter to read all the information on the detail even though it might not all be needed to set the trusses on the building. For example, in some applications, the engineer will call for the trusses to be applied in 2-ply or 3-ply. If the trusses are plied, they are fastened together, face to face, so that all the truss members are joined in two or three layers. In this case

the ply is shown as “1” in the box at the top of the detail sheet. The last sheet in this packet of truss engineering drawings is an explanation of symbols, numbering, and general notes. (See **Figure 21–8**.)

Gable Ends


A roof *gable* is the triangle formed at the end of the roof by the two top chords of the truss and its bottom chord. The roof framing at a gable end must include studs, so there will be a place to attach whatever sheathing and siding are to be applied. A gable-end truss is used for this. When an overhang is needed on the gable end, it can be built as part of the gable-end truss (see **Figure 21–9**).

Job	Truss	Truss Type	Qty	Ply	Charlew/83 Tamarack	E10125961
J16-02632	T1A	COMMON	6	1		

Bellevue Builders Supply, Schenectady, NY 12306

Job Reference (optional)

7.640 s Apr 19 2016 MiTek Industries, Inc. Mon Dec 26 10:37:41 2016 Page 1
ID:drs3IR2?cVenVtad6N3ZGfy9fwv-fix9FIQO7yBtVwK?ZNYBZ41fP423fjKcJ76Jhy57hw



Scale = 1:71.8

Plate Offsets (X,Y)-- [2:0-4-14,0-0-1], [10:0-6-6,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 30.8	2-0-0	TC 0.52	in (loc) l/defl L/d	MT20	197/144
(Ground Snow=40.0)	Plate Grip DOL 1.15	BC 0.86	Vert(LL) -0.39 11-13 >999 360		
TCDL 10.0	Lumber DOL 1.15	WB 0.45	Vert(CT) -0.60 11-13 >657 240		
BCLL 0.0 *	Rep Stress Incr YES	(Matrix-M)	Horz(CT) 0.09 10 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014			Weight: 161 lb	FT = 20%

LUMBER-

TOP CHORD 2x6 SPF No.2
 BOT CHORD 2x4 SPF 1650F 1.5E
 WEBS 2x4 SPF No.2
 SLIDER Left 2x6 SPF No.2 2-0-0, Right 2x6 SPF No.2 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-10 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(lb/size) 2=1742/0-5-8, 10=1669/0-4-0
 Max Horz 2=220(LC 7)
 Max Uplift 2=-35(LC 10), 10=-22(LC 11)
 Max Grav 2=1757(LC 20), 10=1694(LC 21)

FORCES.

(lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/40, 2-3=-867/0, 3-4=-2278/72, 4-5=-2090/109, 5-22=-1955/128, 6-22=-1946/159, 6-23=-1931/159, 7-23=-1945/127, 7-8=-2074/109, 8-9=-2262/72, 9-10=-685/0
 BOT CHORD 2-24=-103/1927, 24-25=-103/1927, 13-25=-103/1927, 12-13=0/1319, 12-26=0/1319, 11-26=0/1319, 11-27=0/1752, 27-28=0/1752, 10-28=0/1752
 WEBS 6-11=-93/912, 8-11=-559/233, 6-13=-93/940, 4-13=-575/233

NOTES-

- Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
- TCLL: ASCE 7-10; Pg= 40.0 psf (ground snow); Pf=30.8 psf (flat roof snow); Category II; Exp B; Partially Exp.; Ct=1.1
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 30.8 psf on overhangs non-concurrent with other live loads.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 1-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 35 lb uplift at joint 2 and 22 lb uplift at joint 10.



December 27, 2016

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSIT/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



818 Soundside Road
 Edenton, NC 27932


Courtesy of Bellevue Builders Supply

Figure 21-7. T1A engineering detail.

Symbols

PLATE LOCATION AND ORIENTATION

Center plate on joint unless x, y offsets are indicated. Dimensions are in 1/16-in.-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0-1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.



* Plate location details available in MITek 20/20 software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3. These truss designs rely on lumber values established by others.

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
- Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor 1 bracing should be considered.
- Never exceed the design loading shown and never stack materials on inadequately braced trusses.
- Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
- Cut members to bear tightly against each other.
- Place plates on each face of truss at each joint and embed fully. Knots and warps at joint locations are regulated by ANSI/TPI 1.
- Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
- Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
- Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
- Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
- Top chords must be sheathed or purlins provided at spacing indicated on design.
- Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
- Connections not shown are the responsibility of others.
- Do not cut or alter truss member or plate without prior approval of an engineer.
- Install and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
- Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
- Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.

Figure 21-8. Guide to truss engineering symbols and numbering.




Figure 21–9. Gable-end truss with overhang.



USING WHAT YOU LEARNED

Unless a building is a simple square or rectangle, there are probably several types of trusses used in its roof. That is true of the house described in this unit. It is necessary to be able to identify where each type is to be used in order to place these trusses on the building frame. For example, what truss ID is to be placed over bedroom #3 of the house showing the figures of this unit?

Find bedroom #3 on the second floor plan in **Figure 21–5**. It is across from the top of the stairs. The stairs are directly ahead of the main entrance, which is below the small gable on the front of the house. Now find that area on the truss plan in **Figure 21–4**. A callout on that plan tells us that there are six trusses with ID number T1A.

Assignment

Refer to the figures in this unit to answer the following questions.

1. What is the slope of the garage roof?
2. What is the span of the trusses over the garage storage area?
3. What are the truss IDs for the six types of trusses in the roof over the garage and study?
4. What is the difference between the T1 and T1A trusses? What is the reason for that difference?
5. Where do the T1GE trusses go?
6. Where does the PB1GE truss go?
7. What is the on-center spacing from V1 to V2?
8. What is the slope of the roof over bedroom #2?

Common Rafters

22 UNIT

Roof Construction

In a common frame roof, the rafters, ridge board, and collar ties are the structural members. They are sized and spaced to support the weight of the roof itself plus any snow or wind that can be expected. The protection from weather is provided by sheathing (or roof decking) and roofing material (see **Figure 22-1**).

The size and spacing of the rafters vary depending on their length, pitch, and *load* (weight they must support) and are specified in Tables R802.5.1(1) through R802.5.1(8) of the *International Residential Code*[®]. If the rafters span a great distance or are spaced far apart, they must be deep to support their load. (The vertical dimension of rafters and joists is called *depth*). The size and spacing of the rafters are shown on a section view (see **Figure 22-2**). The ridge board is also usually shown on a section view. The ridge board should be made of stock 2 inches deeper than the rafters. The greater depth is needed because

Objectives

After completing this unit, you will be able to perform the following tasks:

- Find information about roof construction on drawings.
- Calculate the length of common rafters.
- Calculate the length of rafter tails when overhang is given.




Figure 22-1. Elements of a roof.




Figure 22-2. A section view of the roof shows the size and spacing of rafters.




Figure 22-3. The ridge board must be made of wider lumber than the rafters to allow for the angled plumb cut.

an angled cut across the rafters is longer than a square cut across the rafters (see **Figure 22-3**).

When the roof framing is complicated, a separate roof framing plan may be included (see **Figure 22-4**). Roof framing plans are used only to show the general arrangement of the framing. Therefore, unless specific dimensions are included, framing plans should not be relied upon for the lengths of the framing members.

The roof frame may also include **collar ties**. Collar ties are usually made of 1-inch (nominal thickness) lumber. They are normally included on every second or third pair of rafters. This information should be shown on the roof section if collar ties are planned.

The slope of the roof may be shown on any section view that shows the rafter size. Slope is usually also shown on the building elevations.

Roof Covering


The most common roof decking materials for houses are plywood and *oriented-strand board (OSB)*. However, in post-and-beam construction, where the extra strength is needed to span the distance between the rafters, dimensional lumber is used for the roof deck.

The material used to provide weather protection is often chosen for its architectural style (see **Figure 22-5**). Some of the most common materials are asphalt shingles, wood shingles, and terra-cotta or metal tiles. The material to be used is shown on the section view of the roof and usually on the building




GREEN NOTE

Raised heel rafters and trusses can be used to make more room for insulation and proper ventilation at the edge of the roof. In raised-heel-rafter construction, the ceiling joists rest on the top plate with a joist header capping their ends. A separate plate is nailed on top of the joists and header, so the bird's mouth of the rafters rests on this upper plate. In this way, the full depth of the joist is available for insulation right up to the edge of the roof.



elevations. The roofing should be applied over a layer of roofing underlayment. The underlayment is a membrane that prevents the chemicals in roofing materials from leaking onto the roof decking. Underlayment also provides an additional layer of waterproofing. There are three types of commonly used roofing underlayment: asphalt-saturated felt, rubberized underlayment, and nonbitumen synthetic underlayment (polypropylene or polyethylene.)

Asphalt roofing materials, including felt and shingles, are sold by their weight per hundred square feet of coverage. One hundred square feet of roof is called a **square**. If enough shingles to cover one square weigh 235 pounds, they are called 235-lb shingles. Asphalt-saturated felt underlayment is typically 15-lb or 30-lb weight.



Courtesy of Robert C. Kurzon.

ROOF FRAMING PLAN

1/8" = 1' - 0"

2/6

Figure 22-4. Roof framing plans show the arrangement of rafters.



Figure 22-5. Tile roofs are popular in some parts of the country.

Finding the Length of Common Rafters

Carpenters use a rafter table to find the length of rafters. These tables are available in handbooks and are printed on the face of a framing square (see **Figure 22-6**). To find the length of a **common rafter**, you must know the run of the rafter and its rise per foot of run.

The run can be found on the floor plan of the building. The rise per foot of run is shown on the building elevations. The length of the common rafter is then found by following these steps:

- Step 1. Find the number of inches of rise per foot of run at the top of the table. These numbers are the regular graduations on the square.
- Step 2. Under this number, find the length of the rafter per foot of run. A space between the numbers indicates a decimal point.
- Step 3. Multiply the length of the common rafter per foot of run (the number found in Step 2) by the number of feet of run.
- Step 4. Add the length of the tail, and subtract one-half the thickness of the ridge board. The result is the length of the common rafter as measured along the measuring line.

Note: If the overhang is given on the working drawings, it can be added to the run of the rafter instead of adding the length of the tail.

Shed Roof Framing

Most of the Lake House has shed roof construction. That is, the common rafters cover the full span of the area they cover in a single slope. To find the length of shed rafters, treat the entire span of the rafters as run. For example, the total width of the garage is 13'-9". There is no overhang on either side of the garage, so the span of the garage rafters is 13'-9". Use 13'-9",





Figure 22-6. Rafter table on the face of a square: The top line is the length of common rafters per foot of run.

or 13.75 feet, as the run in calculating the length of common rafters. (See Math Review 20 in Appendix B.)


Where shed rafters butt against a wall or other vertical surface, the drawings should include a detail to show how they are fastened. **Figure 22–7** shows three methods of fastening rafters to a vertical surface.

Roof Openings


It is often necessary to frame openings in the roof. Where chimneys, skylights, or other features require openings through the rafters; headers and double framing members are used. This method of framing openings is similar to that used in floor framing.



FACE NAIL



LEDGER



METAL HANGERS

Figure 22–7. Details of shed roof to wall.



USING WHAT YOU LEARNED

Although roof trusses have become the most widely used method for framing roofs of light frame buildings, such as homes, carpenters will very often be called on to layout and use common rafters. Although the length of a rafter can be found with a construction calculator, calculators are not always available on the job site. You are encouraged to learn to use the rafter tables on a framing square. Find the length of a common rafter for the roof in **Figure 22-8**.

1. Rise per foot of run = 4"
2. Length of common rafter per foot of run = 12.65"
3. Run of one rafter including overhang = 16'-0"
4. $16 \times 12.65'' = 202.40''$ (round off to $202\frac{3}{8}''$).
5. Subtract one-half the thickness of the ridge board: $202\frac{3}{8}'' - \frac{3}{4}'' = 201\frac{5}{8}''$.




Figure 22-8. Find the length of a common rafter.

Assignment

Give the following information for the rafters of the Lake House:

Rafter Location	Thickness × Depth	Run	Rise per Foot Run	Length	O.C. Spacing
1. Kitchen					
2. Bedroom #2 and Loft					
3. Living room					
4. Bedroom #1					
5. Garage					

UNIT 23

Hip and Valley Framing

Objectives

After completing this unit, you will be able to perform the following tasks:

- Calculate the length of hip rafters.
- Calculate the length of valley rafters.
- Calculate the length of hip and valley jack rafters.

Hip Rafters

Hip rafters run from the corner of the building to the ridge at a 45° angle (see **Figure 23–1**). The length of hip rafters can be found by using a table found on most framing squares (see **Figure 23–2**). The second line of this table is used to calculate the length of hip rafters. This table is based on the unit-run-and-rise method for finding the length of common rafters, explained in Unit 22.

To calculate the length of a hip rafter, you must know the run of the common rafters in the roof and the unit rise of the roof (see **Figure 23–3**). The length of the hip rafters is then found by using the table for length of hip and valley rafters in the same way the table for the length of common rafters is used in Unit 22.

- Step 1. Find the unit rise (number of inches of rise per foot of run) at the top of the table. These numbers are the regular graduations on the square.
- Step 2. Under this number, find the length of the hip rafter per foot of run of the common rafters.
- Step 3. Multiply the length of the hip rafter per foot of common-rafter run (the number found in Step 2) by the number of feet of run of the common rafters (one-half the width of the building).
- Step 4. Subtract the ridge allowance. Because the hip rafter meets the ridge board at a 45° angle, the ridge allowance is one-half the 45° *thickness* of the ridge board (see **Figure 23–4**). The 45° *thickness* is the length of a 45° line across the thickness of the ridge board. The 45° thickness of a $1\frac{1}{2}$ -inch (2-inch nominal) ridge board is $\frac{21}{8}$ inches. Therefore, the ridge allowance for a hip rafter on a $1\frac{1}{2}$ -inch ridge board is $\frac{1}{16}$ inch.

Note: If the hip rafter includes an overhang, add the overhang of the common rafters to the run of the common rafters.




Figure 23-1. Parts of a hip and valley roof frame.




Figure 23-2. Rafter table on the face of a square.

Example: Find the length of a hip rafter for the roof shown in Figure 23-5.

1. Rise per foot of run = 4".
2. Length of hip rafter per foot of common-rafter run = 17.44".

3. Common-rafter run including overhang = 16'-0".
4. $16 \times 17.44" = 279.04"$ (round off to $279\frac{1}{16}"$).
5. Subtract $1\frac{1}{16}"$ ridge allowance: $279\frac{1}{16}" - 1\frac{1}{16}" = 278"$




Figure 23-3. To use the table for the length of hip and valley rafters, use the run of the common rafters in the roof.




Figure 23-4. Use one-half of the 45° thickness of the ridge as a ridge allowance for hip rafters.




Figure 23-5. Find the length of a hip rafter.

The rafters that butt against the hip rafter are called hip **jack rafters**; they are cut at an angle (see **Figure 23-6**). This angled cut produces a surface that is longer than the width of the lumber from which the rafter is cut. Therefore, the hip rafters are sometimes made of wider lumber than the common rafters and jack rafters.

Valley Rafters

The line where two pitched roofs meet is called a **valley**. The rafter that follows the valley is a **valley rafter**. It is most common for both roofs to have the same pitch. This results in the valley rafter being at a 45° angle with both ridges—the same angle as a hip rafter. Because




Figure 23-6. Because the top of the hip jack is cut on an angle, the hip rafter must be wider.




Figure 23-7. On some roofs the common rafter tails are close enough so no tail is needed on the valley rafters.




Figure 23-8. When both spans are the same distance and the same pitch, the valley goes all the way to the ridge.

the angles of the hip and valley rafters are the same and the pitch is the same, the same table can be used to compute their lengths.

All steps of the procedure given earlier for hip rafters can be followed to find the length of valley rafters. However, the valley rafters often have no tail even though the roof has an overhang (see **Figure 23-7**).

In this case, the total length of the valley rafters is computed on the basis of the run of the common rafters excluding the overhang.

When both roofs have the same span and rise, the valley extends from the eave to the ridge (see **Figure 23-8**). When one roof has a greater span than the other, the valley does not reach the ridge




Figure 23-9. When the spans are not equal, the valley does not reach the ridge.




Figure 23-10. Framing valleys with long and short valley rafters.




Figure 23-11. A valley framed against a common rafter.

(see **Figure 23-9**). In this case, the valley is framed in one of two ways. One valley rafter can extend to the ridge, and the other can butt against the first (see **Figure 23-10**). The other method is to install a common rafter on the wider roof in line with the ridge of the narrower roof. Both valley rafters can then butt against this common rafter (see **Figure 23-11**).

The length of the valley rafters is based on the run of the common rafters that have their upper (ridge) ends at the same level as the valley rafter. In other words, when the long and short valley rafters are used, the length of the long valley rafter is based on the run of the common rafters in the wider roof. The length of the short valley rafter is based on the run of the common

rafters in the narrower roof. When both valley rafters butt against a common rafter of a higher roof, their lengths are based on the run of the common rafters in the narrower roof.



GREEN NOTE

The most important function of a roof is to prevent water from entering the structure. One area where leaks sometimes occur is in valleys. If the valley flashing is not wide enough for the pitch of the roof wind-blown water may be forced under the roof covering and run beneath the flashing. Most roofers also apply a self-adhering ice and water barrier to the valley area before installing the flashing. The ice and water barrier provides excellent additional protection against leaks in the valley.

Jack Rafters

Rafters that extend from the wall plate to a hip rafter are called *hip jack rafters*, as shown in **Figure 23-1**. Those that extend from a valley rafter to the ridge board are called *valley jack rafters*, also shown in **Figure 23-1**.

The third and fourth lines of the rafter table on most framing squares, shown in **Figure 23-2**, are used to calculate the length of jack rafters. The length of each jack rafter in a roof varies from the length of the one next to it by the same amount (see **Figure 23-12**). The amount of this variance depends on the spacing of the rafters and the pitch of the roof. The third line of the rafter table is used when the rafters are spaced 16 inches O.C.; the fourth line is used when they are spaced 24 inches O.C. As with the other lines of the rafter table, the inch numerals at the top of the square are used to indicate the unit rise of the roof. For example, if a roof has a 6 in 12 slope and the roof framing is 16 inches O.C., the difference in the length of jack rafters is $17\frac{7}{8}$ inches.




Figure 23-12. Each jack rafter in a string varies from the next by the same amount.

The first jack rafter should be a full space (16 inches or 24 inches) from the bottom of the hip or the top of the valley. Therefore, the first jack rafter should be the length shown on the rafter table.

The length of the tail must be added to the theoretical length from the table. The length of the tail on hip jacks is the same as the length of the tail on common rafters. Therefore, the length of the tail can be found by using the table for the length of common rafters. Simply treat the tail as a very short common rafter. If the overhang is is not in even feet, divide the length of common rafter per foot of run on the table by 12. This gives you the length of the common rafter (or jack rafter tail) per inch of run.

Example: Find the length of the tails of the jack rafters in **Figure 23–13**.

1. Unit rise (rise per foot of run) = 4"
2. Length of common rafter per foot of run = 12.65"
3. Length of common rafter per inch of run = $12.65''/12 = 1.05''$.
4. Run of rafter tail (overhang) = 8"

5. Length of rafter tail = $8 \times 1.05'' = 8.4''$, approximately $8\frac{7}{16}''$.

Hip jack rafters are also shortened at the top to allow for the thickness of the hip rafter they butt against. This allowance is one-half the 45° thickness of the hip rafter. Valley jack rafters are shortened at the bottom to allow for the thickness of the valley rafter. This allowance is one-half the 45° thickness of the valley rafter. The valley jack rafters are also shortened at the top to allow for the thickness of the ridge board. The ridge board allowance for valley jacks is the same as the ridge board allowance for common rafters—one-half the actual thickness of the ridge board.

Example: Find the length of the hip jack rafters (A, B, and C) and the valley jack rafters (D, E, and F) in **Figure 23–13**.

Hip Jack Rafters

1. Rise per foot of run = 4"
2. Spacing of rafters = 24" O.C.
3. Difference in the length of jacks = $25\frac{5}{16}''$.




Figure 23–13. Find the length of the tails of jack rafters, hip jack rafters, and valley jack rafters.

- Theoretical length of hip jack rafter A = $0 + 25\frac{5}{16}'' = 25\frac{5}{16}''$.
- Add tail as found in earlier example: $25\frac{5}{16}'' + 8\frac{7}{16}'' = 33\frac{3}{4}''$.
- Subtract one-half the 45° thickness of the hip rafter: $33\frac{3}{4}'' - 1\frac{1}{16}'' = 32\frac{11}{16}''$ (actual length of A).
- Actual length of hip jack B = $32\frac{11}{16}''$ (length of A) + $25\frac{5}{16}''$ (from rafter table) = 58".
- Actual length of hip jack C = 58" (length of B) + $25\frac{5}{16}'' = 83\frac{5}{16}''$.

Valley Jack Rafter

- Theoretical length of valley jack rafter D = $0 + 25\frac{5}{16}'' = 25\frac{5}{16}''$.
- Subtract one-half the 45° thickness of the valley rafter: $25\frac{5}{16}'' - 1\frac{1}{16}'' = 24\frac{1}{4}''$.
- Subtract one-half the actual thickness of the ridge board: $24\frac{1}{4}'' - \frac{3}{4}'' = 23\frac{1}{2}''$ (actual length of D).
- Actual length of valley jack E = $23\frac{1}{2}''$ (length of D) + $25\frac{5}{16}''$ (from rafter table) = $48\frac{13}{16}''$.
- Actual length of valley jack F = $48\frac{13}{16}''$ (length of E) + $25\frac{5}{16}'' = 74\frac{1}{8}''$.



USING WHAT YOU LEARNED

Hip roofs are quite common and as is true with common rafters, it is sometimes necessary for a carpenter to be able to layout the rafters for a hip roof. In this practice exercise, we find the length of the long valley rafter in **Figure 23–14** using the rafter tables on a framing square.

A valley rafter is the same length as a hip rafter on the same roof.

- The rise per foot of run is 6".
- The length of a hip (or valley) rafter per foot of run at this slope is 18".
- The common-rafter run of this roof is 12'-0".
- $12 \times 18'' = 216''$.
- Subtract half the 45° thickness of the ridge board or $1\frac{1}{16}''$. $216'' - 1\frac{1}{16}'' = 214\frac{15}{16}''$ or $17'-10\frac{15}{16}''$.




Figure 23–14.

Assignment

- A. Refer to Figure 23–14 to complete questions 1–11.
1. What is the run of the common rafters at A?
Note: Do not include the overhang.
 2. How much overhang does the roof have?
 3. What is the actual length of the common rafters at A?
 4. What is the actual length of the hip rafter at B?
 5. What is the run of the common rafters at C?
 6. What is the actual length of the common rafters at C?
 7. What is the length of the short valley rafter?
 8. What is the actual length of the shortest hip jack rafter?
 9. What is the actual length of the second shortest hip jack rafter?
 10. What is the actual length of the shortest valley jack rafter?

11. What is the actual length of the second shortest valley jack rafter?
- B. Refer to the Lake House drawings (in the packet) to complete this part of the assignment.
12. What is the length of the structural steel hip rafter over the dining room?
Note:
 - This hip rafter is a steel channel shown on Roof Framing Plan 2/6 and Details 4/6 and 5/6, and marked as MC8 × 8.7
 - Remember to allow for the distance from the column centerline to the end of the rafter as dimensioned on the detail drawing.
 - This roof has an unusual pitch of 2.96 in 12. This is close enough to use 3 in 12 for calculating rafter lengths.

Cornices

24

Types of Cornices

The *cornice* is the construction at the place where the edge of the roof joins the sidewall of the building. On hip roofs, the cornice is similar on all four sides of the building. On gable and shed roofs, the cornice follows the pitch of the end (*rake*) rafters. The cornice on the ends of a gable or shed roof is sometimes called simply the *rake* (see **Figure 24–1**). The three main types of cornice are the *box cornice*, the *open cornice*, and the *close cornice*.

Box Cornice

The box cornice boxes the rafter tails. This type of cornice includes a fascia and soffit (see **Figure 24–2**). The *fascia* covers the ends of the rafter tails. The *soffit* covers the underside of the rafter tails. There are three types of box cornices. These types vary in the way the soffit is applied.

Sloping Box Cornice. In the sloping box cornice, the soffit is nailed directly to the bottom edge of the rafter tails. This causes the soffit to have the same slope or pitch as the rafter, (see **Figure 24–3**).

Narrow Box Cornice. In the narrow box cornice, the rafter tails are cut level. The soffit is nailed to this level-cut surface (see **Figure 24–4**).

Wide Box Cornice. In a wide box cornice, the overhang is too wide for a level cut on the rafter tails to hold the full width of the soffit. In conventional wood framing, *lookouts* are installed between the rafter ends and the sidewall. The lookouts provide a nailing surface for the soffit (see **Figure 24–5**). For a metal soffit, special metal channels fastened to the sidewall and the back of the fascia hold the soffit (see **Figure 24–6**).

Open Cornice

In an open cornice, the underside of the rafters is left exposed (see **Figure 24–7**). Blocking is installed between the rafters and above the wall plate to seal the cornice from the weather. An open cornice may or may not include a fascia.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe the cornice construction shown on a set of drawings.
- List the sizes of the individual parts of the cornice shown on a set of drawings.
- Describe the provisions for attic or roof ventilation as shown on a set of drawings.




Figure 24-1. The cornice is the construction at the place where the roof and the sidewall meet.




Figure 24-2. Parts of a box cornice.




Figure 24-3. Sloping box cornice.




Figure 24-4. Narrow box cornice.




Figure 24-5. Wide box cornice with horizontal lookouts.




Figure 24-6. Metal and vinyl soffit systems include ventilated soffits and channels.

Close Cornice

In a close cornice, the rafters do not overhang beyond the sidewall (see **Figure 24-8**). The interior may be sealed by the sheathing and siding or by a fascia. In either case, there must be some provision for ventilation.

Cornice Returns

Any type of construction described for cornices can be used for the rake. When a sloping cornice is used, the fascia and soffit follow the line of the roof up the rake. When a level box cornice is used, a *cornice return* is necessary. This is the construction that joins the level soffit and fascia of the eave with the sloping rake (see **Figure 24-9**).

The style of cornice return is shown on the building elevations (see **Figure 24-10**). Although good architectural drafting practice requires details of all special construction, many architects do not include details of cornice returns. The carpenter is expected to know how to achieve the desired results. **Figures 24-11** and **24-12** show the construction of two popular types of cornice returns.




Figure 24-7. Open cornice.




Figure 24-8. Close cornice.



Courtesy of Richard T. Kreh, Sr.

Figure 24-9. Cornice return.




Figure 24-10. The cornice returns can be seen on the building elevations.




Figure 24-11. Section through cornice return shown in Figure 24-10.

Ventilation



GREEN NOTE

In some areas, especially where houses do not have basements, it is common to locate furnaces and water heaters in the attic. Combustion equipment, such as gas-fired furnaces and water heaters should not be located in a conditioned attic unless it is in a separate space that is sealed off from the rest of the conditioned spaces of the house. A conditioned attic would be one in which the insulation is placed against the roof instead of the floor. If backdrafting occurs, carbon monoxide can escape into the surrounding space. In addition to the danger posed by carbon monoxide, backdrafting can cause water vapor from burning fuel to remain in the attic and increase the chances of condensation forming in the attic.

The cornice must allow for ventilation of the attic or roof. Attic or roof ventilation is necessary in both hot and cold weather. Without ventilation, the air in the attic becomes stagnant because it is trapped and unable to circulate.

In hot weather, this stagnant air builds up heat and makes the house warmer. Hot, stagnant air can hold a




Figure 24-12. Framing for cornice return shown in Figure 24-9.

large amount of moisture. When this moisture-laden air comes in contact with the cooler roof, the moisture condenses. The condensation can reduce the effectiveness of the insulation. Condensation can also cause the wood in the attic to rot.

Attic or roof ventilation also helps prevent ice buildup in cold climates. Without ventilation, the heat from the building melts the snow that falls on the roof. As the melted snow reaches the overhang of the roof, it refreezes. Eventually an ice dam may build up. The ice dam can back up newly melted snow, causing it to seep under the shingles (see **Figure 24-13**).




Figure 24–13. Ice dam.

Ventilation is created by allowing cool air to enter through the cornice and exit at the ridge or through special ventilators (see **Figure 24–14**). A section view of the sidewalls or a special roof and cornice detail shows the construction of the cornice including any ventilators. Notice that each of the soffits in **Figures 24–2**, **24–4**, and **24–5** includes a ventilator.

Using I-joists for rafters allows for greater rafter lengths and conserves natural lumber resources, but such framing requires construction details that are not normally required with solid lumber. **Figure 24–15** shows the necessary provisions for roof framing with




Figure 24–14. Airflow through the attic.

TJIs. Notice that many of these details include a V-cut to allow air flow.

The heated air can be allowed to exit in one of three ways. Some buildings have a ventilated, metal ridge cap. This may be shown on the building elevations or on a separate detail. When a ventilated ridge is used, an opening is left in the roof decking at the ridge. Metal roof ventilators can be installed in the roof. Ventilators can be installed in the gables. Metal roof ventilators and gable ventilators are usually shown on the building elevations only.

ROOF DETAILS

Shear blocking—
1 1/4" TimberStrand® LSL rim board,
1 1/2" TJ® Rim Board, or TJ® joist

Web stiffeners
required on
both sides at
R1W

Beveled bearing plate
required when slope
exceeds 1/4:12

1/2 adjacent span maximum

R1 R1 W

V-cut shear blocking—
1 1/4" TimberStrand® LSL
rim board

Web stiffeners
required on
both sides at
R3W

Variable slope
seat connector

1/2 adjacent span maximum

R3 R3 W

Birdsmouth Cut

Allowed at low end of joist only

Beveled web stiffeners
required on both sides.
Cut to match roof slope.

TJ® joist
flange must
bear fully on
plate

Birdsmouth
cut must not
overhang
inside face of
plate

2x4 block for
soffit support

2'-0"
maximum

R5

Intermediate Bearing

Blocking panels or shear blocking may be specified for joist stability at intermediate supports

Web stiffeners
required on both sides
at R7W

Twist strap and backer block required
at R7S with slopes greater than 3:12.
See nailing requirements on page 13.

Beveled bearing plate
required when slope
exceeds 1/4:12

R7 R7 W R7 S

Birdsmouth Cut

Allowed at low end of joist only

Two rows 8d
(0.113" x 2 1/2") nails
at 8" on-center

2x4 one side. Use 2x4 both
sides if joist spacing is
greater than 24" on-center.

Beveled 2x4 block with
beveled web stiffener on
opposite side of web

2'-0"
maximum

4'-0"
minimum

1 1/2"

R8

Birdsmouth Cut

Allowed at low end of joist only

2x4 one side. Use 2x6 if joist spacing
is greater than 24" on-center.

10d (0.128" x 3") nails
at 8" on-center

Beveled 2x4 block

Beveled web stiffeners on both sides

2'-0"
maximum

4'-0"
minimum

R9

Birdsmouth Cut

Allowed at low end of joist only

Two rows 8d
(0.113" x 2 1/2") nails
at 8" on-center

2x4 one side. Use 2x4 both
sides if joist spacing is
greater than 24" on-center.

Beveled 2x4 block. Second
beveled web stiffener
required on opposite side at
R10W

Beveled bearing plate required
when slope exceeds 1/4:12

2'-0"
maximum

4'-0"
minimum

1 1/2"

Filler

R10 R10 W

These Conditions Are NOT Permitted

DO NOT cut holes too close to support.

Refer to Allowable Holes on page 9 for minimum distance from support.

DO NOT bevel cut joist beyond inside face of wall.

DO NOT overhang birdsmouth cut from inside face of plate.

TJ® joist flange must bear fully on the plate. See detail BC on page 15.

Figure 24–15. Roof details for framing with TJs.



USING WHAT YOU LEARNED

It is important to allow ventilating air to flow along the bottom of the roof from the cornice to the upper ends of the rafters. In the Lake House, what prevents birds and rodents from entering with the air?

The typical cornice construction is shown in Roof Detail 1/7. That drawing shows a continuous vent above the OSB sheathing and outside the web stiffeners. This continuous vent has either screening or small enough openings so that only air can enter.

Assignment

Refer to the Two-unit Apartment and the Lake House drawings in your textbook packet to complete the assignment.

1. Which type of cornice does the Apartment have?
2. What material is used for the Apartment cornice?
3. How wide is the Apartment soffit?
4. The Apartment fascia is made of two parts. What are they?
5. What provision does the Apartment cornice have for ventilation?
6. How does attic air exit from the Apartment?
7. Sketch the Lake House cornice and show where air enters for ventilation.
8. There are two ways that air can escape from the Lake House roof. Describe one.

UNIT 25 Windows and Doors

Objectives

After completing this unit, you will be able to perform the following tasks:

- Interpret information shown on window and door details.
- Find information in window and door manufacturers' catalogs and online listings.

Window Construction

Most windows are supplied by manufacturers as a completely assembled unit. However, the carpenters who install windows often have to refer to window details for information. Some special installations require knowledge of the construction of the window unit. Also, when a special window is required, the carpenter may build parts of it on the construction site.

Wood Windows

The major types of windows are briefly discussed in Unit 19. All these windows include a frame and sash. The *sash* is the glass and the wood (or metal) that holds the glass. The sash is made of *rails* (horizontal parts) and *stiles* (vertical parts) (see **Figure 25-1**). The sash may also include muntins. *Muntins* are small strips that divide the glass into smaller panes. The glass is sometimes called the *lite*.




Figure 25-1. Parts of a double-hung window.

The window frame is made of the *side jambs*, the *head jamb*, and the *sill*. Stop molding is applied to the inside of the jambs to hold the sash in place. Factory-built windows also come with the exterior casing installed. The *casing* is the molding that goes against the wall around the frame. The interior casing and the apron, if one is included, are applied after the window is installed.

Metal Windows

Many buildings have vinyl or metal windows. Improvements in the design of metal windows have made them competitive with wood windows in both cost and energy efficiency. The most important of these design improvements has been the development of thermal-break windows. *Thermal-break windows* use a combination of air spaces and materials that do not conduct heat easily to separate the exterior from the interior.

The basic parts of a metal or vinyl window are similar to those of a wood window. The sash consists of a

stile, rails, and glazing. The frame is made up of side jambs, a head jamb, and a sill. However, the trim (casing) is not included as part of the window. Often the window frame itself is the only trim used on the exterior. The frame includes a nailing fin for attaching the window to the building framing.

Window Details

All windows include the parts discussed so far. However, to show the smaller parts, which vary from one window style to another, architects and manufacturers use detail drawings. The most common type of window detail is a section (see **Figure 25-2**). All the parts can be shown in section views of the head, sill, and one side jamb. These sections also usually show the wall framing around the window.

Some of the parts that can be found on window sections are defined here. Find each of the parts on the sections and illustrations in **Figures 25-3, 25-4, and 25-5**.





Figure 25-2. Typical casement window detail drawing.



GREEN NOTE


Fenestration is all of the openings in the building that are intended to allow air, daylight, people, animals, and vehicles to enter and exit the building. This is primarily windows, doors, and skylights. Even the best windows and doors tend to have poorer thermal insulating qualities than the surrounding wall. By eliminating all windows and doors, the heating and cooling load for the building could be greatly reduced, however, it would not be a pleasant home in which to live. Green home designers pay particular attention to the sizes and locations of all fenestration.

The thermal quality of a window is also greatly affected by its glazing. By using glass with low energy transmission properties (low-E glass) and filling the space between the layers of glass with inert gas, its heat transmission and solar properties can be improved.



Courtesy of Andersen Corporation, Bayport, MN 55003.

Figure 25-3. Window parts.



Courtesy of Andersen Corporation, Bayport, MN 55003.

Figure 25-4. Section views of an awning window.




Figure 25-5. Section view of a double-hung window.

- Weather stripping is used on windows that open and close. It forms a weather-tight seal around the sash.
- The transom bar is the horizontal part of a window frame that separates the upper and lower sash when one is a fixed sash.
- Meetings rails or check rails are the rails that meet in the middle of a double-hung window.

- Insulating glass is a double or triple layer of glass, creating a space between the layers. The space is filled with inert gas such as argon and acts as an insulator.
- Extension jambs are fastened to standard jambs when the window is installed in a thicker than normal wall.
- A mullion is a vertical section of the frame that separates side-by-side sash. If the mullion is formed by butting two windows together, it is called a narrow mullion. If the mullion is built around a stud or other structural support, it is called a support mullion.

Door Construction

Doors include many of the same basic parts as windows (see Figure 25-6). A door frame consists of side jambs and a head jamb with stop and casing. Exterior door frames also include a sill. Many doors are made of a framework with panels (see Figure 25-7). The parts of panel doors are named similarly to the parts of a window. The vertical parts are stiles, and the horizontal parts are rails. Doors with glass or louvers are variations of panel doors. The framework is made of rails and stiles, and the glass or louvers replace the




Figure 25-6. Parts of a door frame.




Figure 25-7. Construction of a panel door.

panels. Several manufacturers make molded doors. The most common type of molded door is made of hardboard for interior doors or steel for exterior doors which is manufactured in folds that contour the surface to look like panel doors (see Figure 25-8). *Hollow core doors* consist of an internal frame with “skin” applied to each side (see Figure 25-9). Exterior doors have insulation between the two outer steel skins. These insulated doors result in considerable heating and cooling savings.




Figure 25-8. Molded hardboard door.





Figure 25-9. Flush doors.

Door Details

Door details are usually less complex than window details. Where security, fire alarm, electronic lock, or special systems must be run in door and window metal frames, the corresponding installers must familiarize themselves with the actual manufacturer details and coordinate their installation with the door and window installation schedule. Carpenters rarely make doors, so all that is needed are simple details of the door frame and its trim (see **Figure 25–10**).




Figure 25–10. Typical jamb detail for an exterior door.



GREEN NOTE

Doors must insulate the conditioned space inside the home from the hot or cold weather outside and seal the opening against infiltration of air and water, sometimes in strong winds. If the door is glazed, that part of the door can be treated like a window and insulated with low-E glass and inert gas between the layers of glass. The rest of the door can be insulated by filling it with insulating material. To properly seal the opening requires a good weather seal on a good fitting door. If the weather seal is pinched or has gaps, air and water will enter at that point. If the door does not close evenly against the weather seal, that will cause leaks. The same principles apply to windows and skylights.

Many doors are sold as prehung units. In these units, the frame is assembled, including the trim, and the door is hung in the frame. A section view of the jambs shows how the door is installed. For example, the door detailed in **Figure 25–10** is made with two-piece jambs. These split jambs are pulled apart; each side is then slid into the opening for installation. The stop can be either applied or integral. *Applied stop* is molding that is applied to the jambs with finish nails. *Integral stop* is milled as a part of the jamb when the jamb is manufactured.

Reading Catalogs

It is often necessary to find specific information about windows or doors in the manufacturer's catalog or on its web site. Usually the catalog has a table of contents and web sites have a home page that lists the types of windows and doors available and illustrated. For each type of window or door, you will find some or all of the information listed below:

- A brief description of the window type and some of the features the manufacturer wants to highlight—a little advertising.
- Installation detail drawings.
- Sizes available—This information usually consists of drawings of the various sizes and arrangements, with dimensions for glass size, stud or rough opening, and unit dimensions. **Figure 25–11** shows typical window size information reprinted from a manufacturer's catalog.
- Additional information, such as optional equipment available.

Each manufacturer uses its own design to show the information. It sometimes takes a minute of study to familiarize yourself with how the manufacturer's pages are designed. Also, each manufacturer may make slightly different sizes of stock windows. If the windows used in constructing a building are from a different manufacturer than the one the architect used to make the drawings, it may be necessary to find windows that are as close as possible to the sizes shown on the drawings. Of course, if the construction specifications call for a particular manufacturer, that specification must be followed unless a change is authorized by the architect or owner.


Table of Basic Unit Sizes Scale 1/8" = 1'-0" (1:96)

Unit Dimension	2'-11 1/4" (895)	3'-11 1/4" (1200)	4'-11 1/4" (1505)	5'-11 1/4" (1810)
Minimum Rough Opening	3'-0" (914)	4'-0" (1219)	5'-0" (1524)	6'-0" (1829)
Unobstructed Glass*	12 9/16" (319)	18 9/16" (472)	24 9/16" (624)	30 9/16" (776)

1'-10 1/4" (565)	1'-11" (584)			
2'-11 1/4" (895)	3'-0" (914)			
3'-5 1/4" (1048)	3'-6" (1067)			
3'-11 1/4" (1200)	4'-0" (1219)			
4'-11 1/4" (1505)	5'-0" (1524)			

	14 1/8" (359)						
		27 1/8" (689)					
			33 1/8" (841)				
				39 1/8" (994)			
					51 1/8" (1299)		

	G32	G42		
	G33	G43	G53	G63 ♦
	G336	G436	G536 ♦	G636 ♦
	G34	G44 ♦	G54 ♦	G64 ♦
	G35	G45 ♦	G55 ♦	G65 ♦



Venting Configuration
As viewed from the exterior. Passive sash will open after active sash has been opened.

* "Unobstructed Glass" measurement is for single sash only.
 ♦ These units meet or exceed the following dimensions: Clear Openable Area of 5.7 sq. ft., Clear Openable Width of 20" and Clear Openable Height of 24".
Rough opening dimensions may need to be increased to allow for use of building wraps, flashing, sill panning, brackets, fasteners or other items.
 "Unit Dimension" always refers to outside frame to frame dimension.
 Dimensions in parentheses are in millimeters.
 When ordering, be sure to specify color desired: White, Sandtone or Terratone.†

Handle Locations — Operational Force = 8 lbs.




Figure 25–11. A typical manufacturer's catalog page showing window sizes.



USING WHAT YOU LEARNED


Sometimes drawings specify window sizes that are very close to but slightly different from the sizes that a particular manufacturer stocks. Custom-made windows can usually be ordered in any size requested, but when the stock sizes are very close, it is much less expensive to use a stock window that is close to the size shown on the drawings. For example, what size window shown in **Figure 25–11** might be used in the west wall of the dining room?

Refer to the Lake House example in your textbook packet. According to both the Upper Level Floor Plan and the West Elevation of the building, this is a “B” window on the Window Schedule. The Window Schedule on Sheet 5 tells us that a “B” window is 3’-0” × 3’-0”. On the schedule of sizes in Figure 25–11, the unit dimensions are the top row and the far left column, so the closest size would be 2’-11¼” × 2’-11¼”. Coincidentally, the rough opening for that window is 3’-0” × 3’-0”, shown in the second row of dimensions across the top and the second column of dimensions down the left side.

Assignment

Refer to the Lake House drawings when necessary to complete the assignment.

1. Name the lettered parts (a through f) in **Figure 25–12**.
2. What is the nominal size of the window in the south end of the Lake House dining room?
3. In the catalog sample shown in **Figure 25–11**, what is the width and height of the rough opening for a 3’-11¼” × 2’-11¼” window?
4. In the catalog sample, what are the rough opening dimensions for a window with a 24⁹/₁₆” by 39¹/₈” glass size?
5. In the catalog sample in **Figure 25–11**, what is the glass size of the window in bedroom #2 of the Lake House?
6. In the catalog sample, what is the RO for the window in bedroom #2 of the Lake House?
7. Is the exterior door in the Lake House kitchen to be prehung or site hung?
8. What type and size are the doors in the Lake House playroom closet?



Courtesy of Andersen Corporation, Bayport, MN 55003.

Figure 25–12.

UNIT 26

Exterior Wall Coverings

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe the exterior wall covering planned for all parts of a building.
- Explain how flashing, drip caps, and other devices are used to shed water.
- Describe the treatment to be used at corners and edges of the exterior wall covering.

Wood Siding

Wood is a popular siding material because it is available in a variety of patterns, it is easy to work with, and it is durable. Wood siding includes horizontal boards, vertical boards, shingles, and plywood.

Boards can be cut into a variety of shapes for use as horizontal siding (see **Figure 26–1**). These boards are nailed to the wall surface starting at the bottom and working toward the top. With lapped boards and beveled siding, a starting strip of wood furring is nailed to the bottom of the wall. This starting strip holds the bottom edge of the first piece of siding away from the wall. Each board covers the top edge of the one below. The amount of each board left exposed to the weather is called the *exposure* of the siding (see **Figure 26–2**).

Vertical siding patterns can be created by boards or plywood (see **Figure 26–3**). These materials are applied directly to the wall with no special starting strips. However, where horizontal joints are necessary Z-flashing should be applied (see **Figure 26–4**).

Shingles take longer to apply but make an excellent siding material. In place of a starting strip, the bottom *course* (row) of shingles is doubled.




Figure 26–1. Horizontal siding.




Figure 26–2. The exposure is the amount of the siding exposed to the weather.




Figure 26–3. Three popular vertical siding patterns.




Figure 26–4. Horizontal joints in plywood siding must be protected from water penetration with Z flashing.

Fiber Cement Siding

Fiber cement siding is made of Portland cement, ground sand, cellulose fiber, and additives mixed with water and formed into siding. Fiber cement siding will not rot, and it is termite proof.

Fiber cement siding looks like wood siding (see **Figure 26–5**). It comes in a smooth finish, a wood grain texture, and even a rough-sawn look, and it is available in widths of 6, 7½, 9½, and 12 inches. Fiber cement siding is sometimes referred to as Hardiplank®, a popular brand of fiber cement siding. Hardiplank® comes in standard 12-foot lengths, while other siding materials come in 16-foot lengths. The 4-foot difference is because fiber cement siding is much heavier than wood siding, and anything over




Figure 26–5. Fiber cement siding is made to look like wood siding but is more durable.


12 feet would be difficult for one person to handle. Although fiber cement siding looks like wood and it is installed in much the same way as wood, it is important to follow the manufacturer's installation instructions to maintain the warranty on the siding.

Drip Caps and Flashing

It is important to prevent water from getting behind the siding, where it can cause dry rot and attract insects. Where a horizontal surface meets the siding, water is apt to collect. **Flashing** is used to prevent this water from

running behind the siding. Aluminum, galvanized steel, and copper are the most common flashing materials. The flashing is nailed to the wall before the siding is applied. The lower edge of the flashing extends over the horizontal surface far enough to prevent the water from running behind the siding. Areas to be flashed are usually noted on building elevations, but the carpenter should be familiar with flashing practices and install flashing wherever water penetration might be a problem. The flashing is also usually shown on the detail drawings (see **Figure 26-6**).

The heads of windows and doors may form a small horizontal surface. Wood **drip cap** molding can be used



LEFT SIDE ELEVATION




Figure 26-6. Flashing is shown on elevations and details.



GREEN NOTE

Together with the roofing, the exterior wall finish is the home's first line of defense against water. There are many exterior finish materials available to the homebuilder and most of them are capable of doing an excellent job of shedding water. None of them, however, will do a good job if not installed properly. Most water enters the home through the force of gravity. As it either drips off the roof or strikes the wall near the top it flows downward, always seeking the path of least resistance. Sometimes that path of least resistance is through a gap in a drip cap over a door or window, or through a poorly fitted piece of flashing. The key to success is to install all wall covering materials, house wrap, flashing, siding, masonry veneer, paint or whatever is called for with care and according to the manufacturer's instructions.




Figure 26-7. Drip cap.

in these places to shed water (see **Figure 26-7**). Drip caps are shown on details and elevations.

Corner and Edge Treatment

Regardless of the kind of siding used, the edges must be covered to prevent water from soaking into the end grain or running behind the siding. Around windows,




Figure 26-8. Corner boards can be used with most types of siding.




Figure 26-9. Shingles are trimmed to form their own corners.

vents, doors, and other wall openings, the trim around the opening usually covers the end grain of the siding. In an inside corner, a strip of wood can be used to form a corner bead for the siding. Outside corners in plywood, hardboard sheets, or vertical boards are usually built with corner boards (see **Figure 26-8**). Horizontal siding is butted against the corner boards. Shingles are trimmed to form their own outside corner (see **Figure 26-9**), or they are butted against corner boards.




Figure 26–10. Accessories for metal and vinyl siding.

The corner treatment to be used can usually be seen on the building elevations. If no corner treatment is shown on the elevations, look for a special detail of a typical corner.

Metal and Plastic Siding

Several manufacturers produce aluminum, steel, and vinyl siding and trim. The most common type is made to look like horizontal beveled wood siding. A variety of trim pieces are available for any type of application (see **Figure 26–10**).

Stucco

Stucco is a plaster made with Portland cement. The wall sheathing is covered with waterproof building paper. Next the *lath* (usually wire netting) is stapled to the wall (see **Figure 26–11**). Finally, the stucco is troweled on—a rough *scratch coat* first—as shown




Figure 26–11. Wall prepared for stucco.



Figure 26–12. Scratch coat applied.

in **Figure 26–12**, then a *brown coat* to build up to the approximate thickness, and finally a finish coat. Outside corners and edges are formed with galvanized metal beads nailed to the wall before the scratch coat is applied.

Masonry Veneer

Masonry veneer is usually either brick or natural stone. It is called “veneer” because it is a thin layer of masonry over some kind of structural wall. The structure may be wood framing, metal framing, or concrete blocks. The masonry has to rest on a solid foundation. Normally, the building foundation is built with a 4-inch ledge to support the masonry veneer. This ledge can be seen in a typical wall section (see **Figure 26–13**).






Figure 26–13. Typical foundation section with ledge for masonry veneer.

Interesting patterns can be created by using half bricks and bricks in different positions. Some of the most common *bond patterns*, as they are called, are shown in **Figure 26–14**. If no pattern is indicated, the bricks are normally laid in running bond.


Above and below windows, above doors, and in other special areas, bricks may be laid in varying positions (see **Figure 26–15**). If bricks are to be laid in any but the stretcher position, they will be shown on the detail drawings (see **Figure 26–16**). The details for openings in masonry walls will also indicate a lintel at the top of the opening. The *lintel* is usually angle iron. It carries the weight of the masonry above the opening.




RUNNING BOND



STACKED BOND




ENGLISH CROSS



FLEMISH BOND

Figure 26–14. Frequently used bond patterns.



STRETCHER

HEADER

SOLDIER

ROWLOCK

Figure 26–15. Brick positions.




Figure 26-16. Notice the rowlock and soldier bricks on the window detail.



USING WHAT YOU LEARNED

Before the siding is applied, the carpenters should examine the drawings to know exactly how all of the edges are to be treated. Questions to consider include:

- Where is caulk to be used?
- Where are siding edges covered with trim?
- Exactly where do the edges fall? For example, where is the bottom edge of the siding relative to the top of the foundation? This is shown on the Lake House Wall Section 3/4. The bottom of the siding aligns with the top of the foundation wall.

Assignment

Refer to the Lake House drawings in your textbook packet to complete the assignment.

1. What material is used for the Lake House siding?
2. How are the outside corners of the Lake House siding finished?
3. Where is the bottom edge of the siding relative to the wall construction?
4. What prevents water from running under the siding at the heads of the Lake House windows?
5. Detail 1/7 of the Lake House shows aluminum screen nailed behind the top edge of the siding. What is the purpose of the opening covered by this screen?
6. Describe one use of aluminum flashing under the siding on the Lake House.

Decks

27 UNIT

Wood decks are used to extend the living area of a house to the outdoors. A deck may be a single-level platform, or it may be a complex structure with several levels and shapes. However, nearly all wood decks are made of wood planks or synthetic planks made to simulate wood laid over joists or beams (see **Figure 27-1**). The planks are laid with a small space between them, so rainwater does not collect on the deck.

The same construction methods are used for decks and porches as for other parts of the house. The parts of deck construction that require special attention or that were not covered earlier in the text are discussed here.

Support

The deck must be supported by stable earth. The support must also extend below the frost line in cold climates. The most common method of support is by concrete columns with metal post anchors (see **Figure 27-2**). A typical metal post anchor is shown in **Figure 27-3**. Such anchors fasten posts to the concrete pier while keeping them from contacting the concrete in order to prevent decay. Indeed, all wood used in the construction of a deck should be pressure treated with a chemical to prevent such decay. Note that deck detail 3/6 for the Lake House includes a note that all wood is to be pressure treated.




Figure 27-1. Typical deck construction.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Explain how a deck is to be supported.
- Describe how a deck is to be anchored to the house.
- Locate the necessary information to build handrails on decks.

There are a number of products made from combinations of wood fibers and synthetic materials (plastics) that may be used for decks and other outdoor structures. These products, called *composites*, are not affected by weather, moisture, or termites. They can generally be worked with ordinary carpentry tools and




Figure 27-2. Foundation for a typical wood deck.

fasteners. Of course, as with all products, you should read and follow the manufacturer's instructions for installation.

Decks are usually included on the floor plans for the house. The floor plans show the overall dimensions of the decks and the locations of posts, piers, or other support (see **Figure 27-4**). If the decks are complex, they may be shown on a separate plan or detail. On the Lake House, the decks are shown on the floor framing plan.



Figure 27-3. Metal post anchor.




Figure 27-4. Deck shown on floor plan.

Typically the posts or piers support a beam or girder, which in turn supports joists. The beam may be solid wood or built-up wood. The joists can be butted against or rested on top of the beam in any of the ways discussed for floor framing.

Anchoring the Deck

The most common ways of anchoring the deck to the building are shown in **Figure 27-5**. If the deck is at the same level as the house floor, the deck joists can be cantilevered from the floor joists. In this case, blocking

is required between the joists. If the deck is secured with anchor bolts in a concrete foundation, the anchor bolts must be positioned when the foundation is poured. If the deck is to be added to an existing concrete wall, anchors made for this purpose can be inserted into drilled holes. There are many different types of anchors available, but only those rated for this use should be used to fasten the deck to the house.

The anchor bolts or through bolts hold a joist header. The deck joists either rest on top of the header or butt against it. If the joists butt against the header, they are supported by joist hangers or a ledger strip.




Figure 27-5. Three methods of anchoring the deck to the house.



GREEN NOTE

Decks and outdoor structures are parts of the home. In the spirit of designing and building a green home, the same principles that apply to the house should be applied to decks. Design on a 2-foot module; avoid unnecessary corners, angles, and curves; select materials that require a minimum of maintenance and do not involve unnecessary embodied energy (the energy required to manufacture and transport a product); and always observe best practices—use quality workmanship.

Although all deck framing should be built of pressure-treated lumber, it is still important to prevent water from collecting on top of the header. This can be done by cementing flashing into a kerf (i.e., saw cut) in the concrete wall or with caulking.

Railings

Most decks have a railing because they are several feet from the ground. Although metal railings are available in ready-to-install form, the architectural style of most wood decks calls for a carpenter-built wood




Figure 27-6. Railing detail.

or composite railing. The simplest type of railing is made of uprights and two or three horizontal rails. The uprights are bolted to the deck frame, and the rails are bolted, screwed, or nailed to the uprights. The style of the railing and the hardware involved are usually indicated on a detail drawing (see **Figure 27-6**).



USING WHAT YOU LEARNED

To build a deck, it is necessary to know the sizes of all of the parts. The joists that support the deck planks must be of the correct material and cut to the correct length. On the Lake House, what are the dimensions of the joists that support the deck between the kitchen and the garage?

The basic arrangement of these joists is shown in the floor framing plan 1/6. The joists are 2×8 s, which span from the three 2×8 s at the west end of the house to the east end. The upper level floor plan 2/2 shows the dimension from the west edge of the deck (and the side of the garage) to the west wall of bedroom #2 to be $13'-9''$. Subtract $3 \times 1\frac{1}{2}'$ for the header at the west side end of the joists to find the length of the joists. Thus, $13'-9'' - 4\frac{1}{2}'' = 13'-4\frac{1}{2}''$. The joists are 2×8 ($1\frac{1}{2}'' \times 7\frac{1}{4}''$) by $13'-4\frac{1}{2}''$ long.

Assignment

Refer to the Lake House drawings in your textbook packet to complete the assignment.

1. What supports the south edge of the decks located outside the Lake House living and dining rooms?
2. How far from the outside of the house foundation is the centerline of these supports?
3. How far apart are these supports?
4. How many anchor bolts are required to fasten both of these decks to the Lake House foundation?
5. What is the purpose of the aluminum flashing shown on deck detail 3/6?
6. What material is used for the railings on the Lake House south decks?
7. How many lineal feet of horizontal rails are there on these decks? (Do not include the cap rail.)
8. What is the total rise from the lower deck to the higher deck? Which deck is higher?
9. What supports the west edge of the deck between the Lake House kitchen and the garage?

UNIT 28

Finishing Site Work

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe retaining walls, planters, and other constructed landscape features shown on a set of drawings.
- Find the dimensions of paved areas.
- Identify new plantings and other finished landscaping shown on a site plan or landscape plan.

As the exterior of the building is being finished or soon after it is finished, the masons, carpenters, and landscapers begin the finished landscape work. Any constructed features (called *site appurtenances*) are completed first. Then trees and shrubs are planted. Finally, lawns are planted.

Retaining Walls

Retaining walls are used where sudden changes in elevation are required (see **Figure 28–1**). The retaining wall retains, or holds back, the earth. Where the height of the retaining wall is several feet, the earth may put considerable stress on the wall. Therefore, it is important to build the wall according to the plans of the designer. A section through the wall usually is included to show the thickness of the wall, its foundation, and any reinforcing steel




Figure 28–1. Retaining wall on site plan.

(see **Figure 28-2**). For low retaining walls, the site plan may be the only drawing included.

A low retaining wall is sometimes built around the base of a tree when the finished grade is higher than the natural grade. This retaining wall forms a well around the tree, allowing the roots of the tree to “breathe.” An example of a tree that will require a well can be seen in **Figure 28-3**, taken from the Lake House site plan. The 24-inch oak is at an elevation of approximately 333 feet, but the finished grade at this point is 336 feet. Therefore, a well 3-feet deep is required.

Planters

Planters are sometimes included in the construction of retaining walls or attached to the building. In these cases, the information needed to build the planter is included with the information for the building or retaining wall (see **Figure 28-4**). The planter is built right along with the house or retaining wall. If a planter that is separate from other construction is included, it is usually shown with dimensions on the site plan. A special section may be included with the details and sections to show how the planter is constructed (see **Figure 28-5**).

The planter should be lined with a waterproof membrane, such as polyethylene (common plastic sheeting). This keeps the acids and salts in the soil from seeping through the planter and staining it. The planter should also include some way for water to escape. This can be through the bottom or through weep holes. **Weep holes** are openings just above ground level. In cold climates, the planter may be lined with compressible plastic foam. This allows the earth in the planter to expand as it freezes, without cracking the planter. If the planter is to have landscape lighting, automatic watering, and so on, additional waterproofing may be required where these utilities penetrate the waterproof membrane.

Paved Areas

Paved areas on housing sites are drives, walks, and patios. Drives and walks are usually described most fully in the specifications for the project. However, the site plan includes dimensions and necessary grading information for paved areas, as shown in **Figure 28-3**. These dimensions are usually quite straightforward and easy to understand.




Figure 28-2. Typical retaining wall construction detail.



GREEN NOTE

Paved areas can be either impervious (water will not pass through) or pervious (water passes through to the earth below). For small areas such as walkways, the choice of pervious or impervious is not significant, but for large areas this can be an important design question. If ½ inch of rain falls on a paved area that is 100 feet by 20 feet, that is over 83 cubic feet or 617 gallons of water. If that much water drains at one point, it can do considerable damage to the landscape in that area. If impervious pavement, such as asphalt or concrete is to be used, provisions should be made for groundwater runoff.

Patios are similar to drives and walks in that they are flat areas of paving with easy-to-follow dimensions. They may differ from drives and walks by having different paving materials, such as slate, brick, and flagstone, for example. Patios may also be made of a concrete slab with different surface material.




Figure 28-3. Typical site plan. The 24-inch oak tree near the SW corner of the house requires a well.

Plantings

Plantings include three types: grass or lawns, shrubs, and trees. On some projects, such items are planted by the owner. When the builder/contractor does the landscaping, the trees and shrubs are planted first; then, the lawns are planted. Some or all of the trees

included in the landscape design may have been left when the site was cleared. Any new trees to be planted are shown with a symbol and an identifying note, as shown in **Figure 28-3**. There is no widely accepted standard for the symbols used to represent trees and shrubs. Most architects and drafters use symbols






Figure 28-4. Because the planter is a part of the foundation, it is included on the normal drawings for the house.

Courtesy of Home Planners, Inc.




Figure 28-5. Section through planter and patio.





Figure 28-6. Typical symbols for plantings.

that represent deciduous (leaf shedding) trees, coniferous (evergreen) trees, palms, and low shrubs (see **Figure 28-6**). The trees and shrubs may also be listed in a schedule of plantings (see **Figure 28-7**).

Grass is planted by seeding or sodding. Although a note on the site plan may indicate seeded or sodded areas, more detailed information is usually given on the schedule of plantings or in the specification.



**LANDSCAPE PLANTING PLAN FOR:
MR. & MRS. C. BURTON
KENNEDY ROAD
COBLESKILL, N. Y.**

LANDSCAPE DESIGN BY DAN PIERRO

PLANT LIST

BOTANICAL NAME	COMMON NAME	NUMBER USED	BOTANICAL NAME	COMMON NAME	NUMBER USED
~ TREES ~					
ACER PALMATUM	JAPANESE RED MAPLE	1	JUNIPERUS CHINENSIS TORULOSA	TORULOSA JUNIPER	1
ACER SACCHARUM	SUGAR MAPLE	1	JUNIPERUS CHINENSIS WILTONI	WILTONI JUNIPER	7
BETULA Papyrifera	CLUMP WHITE BIRCH	1	KALMIA LATIFOLIA	MOUNTAIN LAUREL	3
GLEDITSIA TRIACANTHOSINERMIS	SHADEMASTER HONEY LOCUST	1	PICEA ABIES NIDIFORMIS	BIRDS NEST SPRUCE	3
~ SHRUBS ~					
AZALEA MOLLIS	CHINESE AZALEA	5	PICEA GLAUCA ALBERTIANA	ALBERTA SPRUCE	1
COTONEASTER HORIZONTALIS	ROCK SPRAY COTONEASTER	5	PIERIS JAPONICA	ANDROMEDA	1
FORSYTHIA INTERMEDIA	FORSYTHIA LYNWOOD GOLD	31	PINUS MUGO MUGHUS	MUGO PINE	1
ILEX CRENATA	JAPANESE HOLLY	2	PINUS THUNBERGI	JAPANESE BLACK PINE	2
ILEX CRENATA CONVEXA BULLATA	CONVEX LEAF HOLLY	11	RHODODENDRON CAROLINA	RHODODENDRON CAROLINA	11
JUNIPERUS CHINENSIS ESPALIER	ESPALIER JUNIPER	1	TAXUS CUSPIDATA DENSIFORMIS	DENSIFORMIS JAPANESE YEW	5
JUNIPERUS CHINENSIS PARSONI	PARSONI JUNIPER	18	TSUGA CANADENSIS	AMERICAN HEMLOCK	8
JUNIPERUS CHINENSIS PFITZERIANA	PFITZER JUNIPER	13	~ GROUND COVERS ~		
			VINCA MINOR	MYRTLE	1200

Figure 28-7. A landscape plan complete with plant list.



GREEN NOTE

The landscaping should be planned at the beginning, along with the rest of the home. Grading should be done to ensure that storm runoff does not damage the plantings. The area should be surveyed for invasive species. If they exist, they should be removed before any landscaping begins and certainly none should be introduced with the landscaping. Grading and planting should not harm the roots of any trees intended to remain on the site. In arid regions, design landscaping that requires little or no watering.



USING WHAT YOU LEARNED

A masonry planter can be used to add plantings in a confined, easy-to-maintain area. If the planter is attached to the house, the foundation will probably be constructed at the same time as the house foundation, but the masonry finish is normally left until the house is well underway. To order the materials for the planter, the builder must know how much of each item to order. The stone coping of the planter in **Figures 28–8** and **28–9** is expensive, so it is important to be accurate in determining the quantity. How many lineal feet of coping are required for this planter?

The dimensions of the planter are shown in **Figure 28–9**. Add all of the dimensions together and subtract the 12-inch width once for each corner. (The coping does not overlap at the corners.) That is, $16'-0" + 2'-4" + 4'-0" + 2'-8" + 12'-0" + 5'-0" - 6'-0" (\text{corners}) = 36'-0"$.




Figure 28–8. Section view for assignment questions.




Figure 28-9. Plan view for assignment questions.

Assignment

Refer to **Figures 28–8** and **28–9** to complete the assignment.

1. What is the height of the retaining wall above the patio surface at A?
2. How long is the retaining wall?
3. Of what material is the retaining wall constructed?
4. What is the width and the length of the patio?
5. What materials are used in the construction of the patio?
6. Describe the weep holes in the planter.
7. How is the planter treated to prevent acids and salts from staining its surface?
8. How many deciduous trees are to be planted?
9. What is the area of the driveway?
10. Assuming that the driveway is 4 inches thick, how many cubic yards of asphalt does it require? (See Math Review 22 in Appendix B.)

Fireplaces

29 UNIT

Basic Construction and Theory of Operation of Wood-Burning Fireplaces

A fireplace can be divided into four major parts or zones: foundation, firebox, throat area, and chimney (see **Figure 29-1**). Each of these zones has a definite function. To understand the construction details, it is necessary to know how these zones work.




Figure 29-1. Four zones of a fireplace.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe the foundation, firebox, throat, and chimney of a wood-burning fireplace using information from a set of construction drawings.
- Explain the finish of the exposed parts of the fireplace, using information from a set of construction drawings.
- Explain the methods used to vent a gas-burning fireplace.

Foundation

The fireplace foundation serves the same purpose as the foundation of the house—it supports the upper parts and spreads the weight over an area of stable earth. The foundation consists of a footing and walls capable of supporting the necessary





Figure 29-2. Section view of a masonry fireplace.

weight (see **Figure 29-2**). The fireplace foundation sometimes houses an ash pit. The *ash pit* is a reservoir to hold ashes that are dropped through an *ash dump* (a small door) in the floor of the fireplace (see **Figure 29-3**). When the foundation includes an ash pit, a *cleanout door* is installed near the bottom of the ash pit (see **Figure 29-4**).


Firebox

The firebox is the area where the fire is built. In all wood-burning masonry fireplaces, the firebox is constructed of two layers of masonry, as shown in **Figure 29-2**. Each layer is called a *wythe*. The floor of the firebox consists of firebricks laid over a concrete base. The concrete base may extend beyond the face of the



Courtesy of Majestic Company.

Figure 29-3. Ash dump.



Courtesy of Majestic Company.

Figure 29-4. Cleanout door.

firebox to support the hearth. The **hearth**, which may be tile, stone, brick, or slate, forms a noncombustible floor area in front of the fireplace. The outer walls of the firebox are most often common brick. The inner walls are of firebrick to withstand the heat of the fire. The back wall of the firebox slopes in to direct the smoke and gas into the throat area. The masonry over the fireplace opening is supported by a steel lintel. The lintel is long enough so that 4 inches of it can rest on the masonry at each end.

Throat


The throat of the fireplace is the area where the firebox narrows into the chimney. Modern wood-burning fireplaces are built with a metal damper in the throat (see **Figure 29-5**). The **damper** is a door that can be closed to prevent heat from escaping up the chimney when the fireplace is not in use. The damper is placed on top of the firebox with 1-inch clearance on all four sides. This clearance allows the metal damper to expand as it gets hot.

The flat area behind the damper (above the sloped back of the firebox) is called the **smoke shelf**. The smoke shelf is especially important for the proper operation of the fireplace. The cold air coming down the chimney hits the smoke shelf and turns back up with the rising hot gas and smoke from the firebox. This helps carry the smoke and gas up the chimney (see **Figure 29-6**). If the smoke shelf is not built properly and kept clean, the falling cold air can force the smoke and gas back into the firebox.

Chimney

The chimney carries the smoke and hot gas from the throat to above the house. The top of the chimney must be high enough above the roof, trees, and other nearby obstructions to ensure that the air flows evenly across its top. According to the *International Residential Code*[®], the chimney must extend at least 2 feet through the roof and 2 feet above anything within 10 feet. However, the dimensions on the drawings should always be followed.

To ensure fire safety and a smooth inner surface, masonry chimneys are lined with a clay **flue**. This flue is installed in 2-foot sections as the chimney is built. A 1-inch air space is allowed between the flue lining and the chimney masonry (see **Figure 29-7**).



Courtesy of Majestic Company.

Figure 29-5. Damper.




Figure 29-6. The smoke shelf turns the incoming air back up the chimney.




Figure 29-7. Plan view of a two-flue chimney.



GREEN NOTE

Wood-burning fireplaces are not very efficient in heating a structure. They are primarily decorative. Their efficiency can be improved somewhat by the use of a prefabricated metal fireplace liner. There is a design of fireplaces that uses massive amounts of masonry and a flue that winds the smoke in an indirect route up the chimney. The fire and hot flue gases heat the masonry which slowly radiates its heat to the surrounding spaces. This type of fireplace can be up to 90 percent efficient, but it requires large amounts of masonry materials and is expensive to build.

Gas-burning fireplaces are more efficient, but still not as efficient as a good furnace or boiler. Some gas-burning fireplaces have an electronic ignition, eliminating the need for a pilot flame that is always burning, consuming fuel, and emitting greenhouse gases.

In recent years insulated, metal chimneys have become quite popular. These chimneys are lightweight; they do not require massive foundation for their support. It also takes less time to install them. Because the outer wall of a metal chimney remains cool, it can be enclosed in wood (see **Figure 29–8**). The chimney sections are slipped together and fastened with sheet metal screws; then, the chimney is framed with wood and covered with the specified siding and trim. A chimney enclosure of this type is called a *chase*.

Prefabricated Metal Fireplaces

Constructing masonry fireplaces is time consuming. Their great weight requires massive foundations. Engineered, metal fireboxes have been developed that can be installed in very little time and require only modest foundations (see **Figure 29–9**). The prefabricated units are available from several manufacturers and in a variety of styles. However, they are all similar in that they have double walls and a complete throat with the damper in place. Most also have a firebrick floor.

The double wall improves the heating ability of the metal fireplace. Cool air enters the space between the walls through openings near the bottom. The air absorbs heat from the fire, and because warm air naturally rises,





Figure 29–8. The framed enclosure for a metal chimney is called a chase.



Courtesy of Majestic Company.

Figure 29–9. Prefabricated metal fireplace.

it exits through openings near the top of the unit (see **Figure 29–10**). The outside surfaces of the prefabricated unit are cooled by the circulating air; the unit can be enclosed in wood if recommended by the manufacturer. For a more traditional appearance, the exposed face of the fireplace can be covered with masonry veneer.

Gas-Burning Fireplaces

Gas-burning fireplaces are a feature of many new homes and are becoming more common than their wood-burning ancestors. A gas fireplace is an appliance that is installed as a unit. The prefabricated unit is installed in a wood-frame enclosure. Because the outer housing does not get as hot as that of a wood-burning fireplace, it can be installed closer to combustible wood framing. The unit is vented to the outside and the gas line is connected to complete the installation. Any style of architectural trim can be applied to the front of the chase after the unit is installed.

Gas fireplaces are efficient, but some heat is lost through the metal surfaces. It is very important that the manufacturer's specifications and instructions be followed to ensure safe venting and to keep combustible materials a safe distance from hot surfaces. Gas-burning fireplaces can be vented straight through the building wall (see **Figure 29-11**), or vertically through a chase (see **Figure 29-12**). Clearances and framing details are provided in the manufacturer's instructions.




Figure 29-10. In a heat-circulating fireplace, cold air enters the double wall at the bottom, and warm air exits at the top.





Figure 29-11. Venting through the wall.

Courtesy of Hearth & Home Technologies.




Figure 29-12. Venting through a vertical chase.

Fireplace Drawings

Where a gas fireplace is to be installed, most of the information about the fireplace is found in the manufacturer's installation instructions. Gas appliances are fairly lightweight, so there are no special foundation requirements. Wood-burning fireplaces, however, are constructed on site from masonry materials, so the building plans and elevations must supply all the construction information.

The foundation is normally included on the foundation plan for the building. The dimensions and notes show the location of the fireplace foundation, its size, and the size and type of material to be used. The floor plan of the house shows where the fireplace is located and its overall dimensions. The building elevations show the chimney.

More detailed information about the fireplace is shown on the fireplace details, which usually include a cross section (see **Figure 29-13**). The following

information is often included on a section view of the fireplace:

- Dimensions of the firebox
- Materials used inside the firebox (firebrick)
- Materials used for the outside of the firebox and chimney
- Ash dump, if any is included
- Lintel over the opening
- Dimensions of the hearth
- Mantel, if any is included
- Dimension from the smoke shelf to the flue
- Size of the flue
- Materials for the chimney

An elevation of the fireplace shows the exterior finish of the fireplace (see **Figure 29-14**). Only those features that could not be adequately described on the section view are called out on the elevation. However, this view shows the exterior finish—the mantel and the trim—better than the section view does.




Figure 29-13. A section view shows the construction of the firebox and throat area.




Figure 29–14. An elevation view is a good guide to the finished appearance of the fireplace.



USING WHAT YOU LEARNED

Natural stone products are usually ordered well in advance of the time they are needed on the site and cut to finished size by the supplier or a company that specializes in working with these materials. This means that the precise size of each cut piece must be specified when the piece is ordered. What is the width and length of the granite piece on top of the Lake House fireplace? Allow 4 inches for the width of the soldier-course bricks, including mortar. There are three fireplace details on sheet 7. Section 4/7 shows that the granite is to fit inside a soldier course of bricks (bricks laid in a vertical position.) The overall size of the fireplace, without the hearth, is shown in Fireplace Plan 5/7 as 3'-4" by 7'-0". Subtract 4 inches from each side (8 inches from the width and 8 inches from the length) for the soldier course bricks and the size of the granite is 2'-8" by 6'-4".

Assignment

Refer to the Lake House drawings in your textbook packet to complete the assignment.

1. What type of fireplace does the Lake House have?
2. How wide is the opening of the firebox?
3. How high is the opening of the firebox?
4. What is the opening next to the firebox?
5. Determine the overall width and length of the fireplace, including the hearth.
6. Of what material is the hearth constructed?
7. What is used for a lintel over the firebox opening? (Include dimensions.)
8. Briefly describe the foundation of the fireplace.
9. How far above the highest point on the roof is the top of the chimney?
10. What is the total height from the playroom floor to the top of the chimney?
11. What is the overall height of the brickwork involved in the fireplace construction?
12. The top of the fireplace is covered with granite on 3/4-inch plywood. How much clearance is there between that plywood and the chimney?
13. Where would you look for the minimum clearance around a gas fireplace vent where it passes through a wall?
14. Where would dimensions be found for the foundation of a wood-burning fireplace?

Stairs

30 UNIT

Stair Parts

In order to discuss the layout and construction of stairs, you need to know the parts of stairs described below and shown in **Figure 30-1**:

- *Stringers* are the main support members. The assembly made up of the stringers and vertical supports is called a **stair carriage**.
- **Treads** are supported by the stringers. The treads are the surfaces one steps on.
- *Risers* are the vertical boards between the treads.
- A *landing* is a platform in the middle of the stairs. Landings are used in stairs that change directions or in very long flights of stairs.
- The *run* of the stairs is the horizontal distance covered by the stairs.
- The *rise* of the stairs is the total vertical dimension of the stairs.
- The **nosing** is the portion of the tread that projects beyond the riser.

Objectives

After completing this unit, you will be able to perform the following tasks:

- Identify the parts of stairs.
- Calculate tread size and riser size.




Figure 30-1. Basic stair parts.




Figure 30-2. Stair trim and balustrade.

- The underside of the nosing may be trimmed with molding called *stair cove*.
- A *handrail* is usually required on any stairs with 4 or more risers.
- **Balusters** are the vertical pieces that support the handrail at each step.
- The *newel post* is a heavier vertical support used at the bottom of the handrail.
- The balusters, newel post, and handrail together are called a *balustrade*.

The trim parts and balustrade are shown in **Figure 30-2**.

Types of Stairs

Stairs can be built with open stringers or housed stringers. *Open stringers* are cut in a sawtooth pattern to form a surface for fastening the treads (see **Figure 30-3**). *Housed stringers* are routed out, so the treads fit between them (see **Figure 30-4**). Stairs are also called open or closed depending on whether the space between the treads is enclosed with risers. Both the kind of stringers and the risers




Figure 30-3. Open stringers and open risers.




Figure 30-4. Housed stringers and closed risers.




Figure 30-5. Stair layouts.

are shown on a section through the stairs. If the stringers are housed, the top of the far stringer shows on the section view.

Stairs are also named according to their layout, as seen in a plan view (see **Figure 30-5**). Straight stairs are the simplest design. They may or may not include a landing. L-shaped and U-shaped stairs are used where space does not permit a straight run. L-shaped and U-shaped stairs have a landing at the change in directions. The carriages for L-shaped and U-shaped stairs include vertical supports under the landing (see **Figure 30-6**). Spiral stairs require the least floor space. They are made up of winder treads, usually supported by a center column.

Temporary stairs used only during construction are usually of cruder construction. They are often made of 2×10 stringers with wooden cleats to support the treads. Service stairs in unoccupied spaces, such as a cellar, are often made of 2×12 open stringers with 2×10 treads. Stairs for exterior

decks are also sometimes built with 2×12 open stringers (see **Figure 30-7**). However, the carpenter should remember that these stairs are important to the overall appearance of the deck.

Calculating Risers and Treads

Nearly all stair details include a notation showing the number of treads with their width and the number of risers with their height, as shown in **Figure 30-6**. Occasionally only the total run, total rise, number of treads, and number of risers are given on the drawings, as shown in **Figure 30-7**. Notice that there is one more riser than there are treads. The builder must calculate the size of the treads and risers. The steepness of the stairs depends on the relationship between tread width and riser height. If the treads are wide and the risers low, the stairs are gradual. If the treads are narrow and the risers high, the stairs are steep. To climb stairs with wide treads and high risers requires an uncomfortably long stride. To climb stairs with narrow treads and low risers requires an uncomfortably short stride. Building codes specify the maximum height of risers and depth of treads. Section R311.7.5.1 and R311.7.5.2 of the *International Building Code*[®] specifies that risers cannot be more than $7\frac{3}{4}$ inches high and treads must be at least 10 inches deep. Although lower risers and deeper treads are allowed by the code, very low risers combined with very deep treads can make for awkward stairs. Stairs are designed by architects to comply with these rules and to be comfortable to climb and descend.

To build the stairs in **Figure 30-7** within these rules, the risers must be $7\frac{1}{2}$ inches high and the treads must be 10 inches wide. The height of the risers can be found by dividing the total rise by the number of risers ($3'-1\frac{1}{2}''$ or $37\frac{1}{2} \div 5 = 7\frac{1}{2}''$). (See Math Review 10 in Appendix B.) The width of the treads is found by dividing the total run by the number of treads ($3'-4''$ or $400 \div 4 = 10'$).

To calculate the size of the treads and risers in stairs with landings, treat each part as a separate stair. However, the treads and risers should be the same size in each part.




Figure 30-6. Stair detail with 2 × 4 studs to support the landing.




Figure 30–7. Typical detail for deck stairs.



USING WHAT YOU LEARNED

Although interior staircases are often built off-site by a millwork company, stairs attached to exterior decks are usually built on-site by a carpenter. This means that the carpenter must be able to determine the sizes of all the stair parts by studying the construction drawings. How many risers and the desired height are required for the stairs going from the ground to the lower south deck of the Lake House? These stairs are described on Floor Framing Plan 1/6. A callout indicates that there are four risers and each riser is $7\frac{3}{4}$ inches high.

Assignment

Refer to the Lake House drawings (in the packet) to complete the assignment.

Questions 1 through 6 refer to the stairs between the south decks of the Lake House.

1. What is the total run of the stairs between the decks?
2. What is the width of each tread?
3. What is the length of each tread?
4. What is the rise of each step in these stairs?
5. How many stringers are used under these stairs?
6. What size material is used for the stringers?

Questions 7 through 13 refer to the stairs from the kitchen to the bedroom level in the Lake House.

7. How many risers are there, and how high is each riser?

8. How many treads are there, and how wide (front to back not including nosing) is each tread?
9. What is the total rise of the stairs?
10. Is this stair built with open or housed stringers?
11. The railing at this stair extends the length of the kitchen hall. If vertical railing supports are spaced at 16" O.C., how many vertical supports are used?
12. How long is each vertical railing support?
13. What material is used for the horizontal rails?

UNIT 31

Insulation and Room Finishing

Objectives

After completing this unit, you will be able to perform the following tasks:

- Identify the insulation to be used in walls, floors, and ceilings.
- Identify the wall, ceiling, and floor covering material to be used.
- List all the kinds of interior molding to be used.

Insulation

Thermal insulation is any material that is used to resist the flow of heat. In very warm climates, thermal insulation is used to resist the flow of heat from the outside to the inside. In cold climates, thermal insulation is used to resist the flow of heat from the inside to the outside. Insulating material is rated according to its ability to resist the flow of heat. The measure of this resistance is the R value of the material. The higher the *R value*, the better the material insulates. Typical R values for sidewall or attic insulation range from R-13 to R-38 (see **Figure 31–1**).



GREEN NOTE

The R-value of insulation can range from R-3.14 per inch for some batt insulation to as high as R-7.20 per inch for polyisocyanurate foam, but there are other factors to consider such as embodied energy and ease of installation. Most important is the quality of the installation, especially for batt insulation, which is still the most common type of insulation in frame homes. Compressing batt insulation only 5 percent can reduce its R-value by up to 50 percent; and gaps are, of course, uninsulated openings. Spray insulations are much less susceptible to compression.

Thermal insulation is generally available in four forms. *Foamed-in-place* materials are synthetic compounds that are sprayed onto a surface and that then produce an insulating foam by a chemical reaction (see **Figure 31–2**). *Rigid boards* are plastic foams that have been produced in board form at a factory. Another common type of rigid insulation is made of fiberglass that is manufactured in rigid form instead of as flexible blankets (see **Figure 31–3**). Rigid boards are frequently used for foundation insulation, under concrete slabs, and for sheathing. *Blanket insulation* is in the form of flexible rolls or *batts* usually made of fiberglass wool (see **Figure 31–4**). Loose *pouring insulation* can be any of a variety of materials that can be poured into place and has good insulating property. A common pouring insulation is loose fiberglass (see **Figure 31–5**).

The insulation is shown in the building sections. If the insulation is to be installed between studs, joists, or rafters, it will be sized accordingly. For example, if batts are to be used in a 2 × 4 wall, the insulation will be indicated as 3½ inches thick—the width of a 2 × 4. One of the main reasons many houses

Type	Typical Thicknesses and R Values	Comments
Fiberglass blankets & batts	3/4", R-3 2 1/2", R-8 3 1/2", R-11 3 1/2", R-13 3 1/2", R-15 6", R-19 9", R-30 12", R-38	Flexible blanket-like material. Available with or without vapor barrier on one side
Fiberglass blowing wool	R value depends on depth of coverage, but is slightly less than fiberglass blankets.	Other types of blowing or pouring insulation include cellulose and mineral wool.
Rigid fiberglass board	1", R-4.4	Material is similar to fiberglass blankets, but with rigid binder to create rigid boards. Usually faced with aluminum foil.
Closed-cell urethane foamed board	1/2", R-3.12 3/4", R-4.70 1", R-6.25 1 1/2", R-7.81 2", R-12.5	Plastic that has been cured in a foamed state to introduce bubbles of air. This creates a rigid board.
Foamed-in-place urethane	R value depends on thickness depth, but is approximately the same as rigid urethane boards.	Other plastic materials may also be foamed in place.
Polyisocyanurate foam	1", R-7.20 2", R-14.40	Usually available as rigid foam boards.

Figure 31–1. Common types of thermal insulation.



Courtesy of CertainTeed Corporation

Figure 31–2. Foamed-in-place insulation.

are framed with 2 × 6s is to increase the space for insulation between the studs. Where insulation is used in ventilated spaces, there should be room for the necessary air circulation (see **Figure 31–6**).



Courtesy of Owens Corning Fiberglas Corporation.

Figure 31–3. Rigid insulation.

Where the insulation includes a vapor barrier, such as kraft paper, foil, or polyethylene, the vapor barrier is installed on the heated side of the wall. This prevents the moisture in the warm air from

Courtesy of Owens Corning Fiberglas Corporation.




Figure 31-4. Blanket insulation.

Courtesy of Owens Corning Fiberglas Corporation.



Figure 31-5. Blowing wool.



Courtesy of Home Planners, Inc.

Figure 31-6. The insulation must not block the airflow.

passing through the wall and condensing on the cold side of the wall. Such condensation can reduce the R value of the insulation and cause painted surfaces to blister and peel.

Wall and Ceiling Covering

By far the most widely used wall surface material is **gypsum wallboard**. The most common thicknesses are 3/8 inch, 1/2 inch, and 5/8 inch. If gypsum board (sometimes




Figure 31-7. Furring is used to provide a nailing surface when framing is spaced too wide or over masonry and concrete.

called *Sheetrock™*) is to be used over framing that is spaced more than 16 inches O.C. or over masonry, the designer may call for furring. **Furring** consists of narrow strips of wood, usually spaced at 16 or 12 inches O.C. to which the wall covering is fastened (see **Figure 31-7**). The furring, if any is to be used, and the thickness of the gypsum wallboard are indicated on the wall sections.

Ceramic tile also is frequently used on bathroom walls. Ceramic tile may be installed over a base of cement board or special tile backerboard.

Gypsum wallboard is the most common ceiling treatment in new home construction. Suspended ceilings are common in commercial construction. Suspended ceilings consist of panels or ceiling tiles supported in a lightweight metal framework. The metal framework is suspended several inches below the ceiling framing on steel wires (see **Figure 31-8**).



Figure 31-8. Suspended ceiling.

Building sections or wall sections usually include a typical wall and ceiling. This is representative of what is planned for most of the walls and ceilings in the house. However, there may be some exceptions, such as the bathrooms or kitchen, where mold and water-resistant wallboard is required. Somewhere within the contract documents, you should find a complete list of all room finishes. This may be on one of the drawings, or it may be written into the specifications. **Figure 31–9** shows a room finish schedule that might be included on the drawings. It is common for finish color to be left for the owner to choose.

Finished Floors

A list of possible floor materials would be very long. However, most of the materials fall into one of the following categories: wood, carpet, ceramic, masonry, and resilient materials such as vinyl tile. The finished floor covering is easily found in a schedule of room finishes, but the underlayment for each category is different. **Underlayment** is any material that is used to prepare the **subfloor** to receive the finished floor.

Architectural drafters differ in how they indicate what underlayment is to be used and how the finished floor is to be installed. Some do not include any underlayment on the drawings but rely on the builder’s knowledge of good construction practices. This is a dangerous practice. If you find this situation, the architect should be

asked for clarification. Sometimes when the drawings do not describe the underlayment, the specifications do. Some drafters indicate the underlayment on the floor plans. Other drafters include the details and section of each area with different types of finished floors, so the underlayment can be shown there.

Interior Molding

Molding is used to decorate surfaces, protect the edges and corners of surfaces, and conceal joints or seams between surfaces. Molding may be made of wood, plastic, or metal and is available in many shapes and styles. The shapes of commonly used wood molding have been standardized. Each shape is identified by a number, **Figure 31–10**.

Most interior molding is shown on detail drawings. The following are some of the most common uses for interior molding:

- Window casing
- Window **stool**
- Door casing
- Base (bottom of wall)
- **Cove** (top of wall)
- Chair rail (middle of wall)
- Trim around the fireplace mantel
- Trim around built-in cabinets

ROOM	FLOOR	WALLS	CEILING
KITCHEN	QUARRY TILE	GYP. BD. w/WALL PAPER	12"X12" TILE
DINING ROOM	OAK PARQUET	GYP. BD.	GYP. BD.
LIVING ROOM	CARPET/PART. BD.	GYP. BD.	GYP. BD.
FAMILY ROOM	CARPET/PART. BD.	HD. BD. PANEL/GYP. BD.	GYP. BD.
BEDROOM #1	CARPET/PART. BD.	GYP. BD.	GYP. BD.
BEDROOM #2	CARPET/PART. BD.	GYP. BD.	GYP. BD.
BEDROOM #3	CARPET/PART. BD.	GYP. BD.	GYP. BD.
BATH #1	CERAMIC TILE	CERAMIC TILE/CONC. BD.	MOSTURE RESIST. GYP. BD.
BATH #2	CERAMIC TILE	CERAMIC TILE/CONC. BD.	MOSTURE RESIST. GYP. BD.
CLOSETS	CARPET/PART. BD.	GYP. BD.	GYP. BD.
FOYER	SLATE	GYP. BD. w/WALL PAPER	GYP. BD.

Figure 31–9. Room finish schedule.
















Figure 31-10. Common shapes of wood molding.


QUARTER ROUNDS







HALF ROUNDS









FLAT ASTRAGALS





BASE SHOES





SHELF EDGE / SCREEN MOLD





GLASS BEADS










BASE CAPS




DRIP CAPS




CORNER GUARDS






BATTENS



BRICK MOLD



ROUNDS



SQUARES






Figure 31-10. (Continued)




Figure 31-10. (Continues)

CASING





Figure 31-10. (Continued)

BASE MOLDINGS



STOPS

























































Figure 31-10. (Continues)






	WM 903	$\frac{7}{16} \times 2 \frac{1}{4}$		WM 913	$\frac{3}{8} \times 2 \frac{1}{4}$		WM 933	$\frac{7}{16} \times 2 \frac{1}{4}$		WM 943	$\frac{3}{8} \times 2 \frac{1}{4}$
	WM 904	$\frac{7}{16} \times 1 \frac{3}{4}$		WM 914	$\frac{3}{8} \times 1 \frac{3}{4}$		WM 934	$\frac{7}{16} \times 1 \frac{3}{4}$		WM 944	$\frac{3}{8} \times 1 \frac{3}{4}$
	WM 905	$\frac{7}{16} \times 1 \frac{5}{8}$		WM 915	$\frac{3}{8} \times 1 \frac{5}{8}$		WM 935	$\frac{7}{16} \times 1 \frac{5}{8}$		WM 945	$\frac{3}{8} \times 1 \frac{5}{8}$
	WM 906	$\frac{7}{16} \times 1 \frac{3}{8}$		WM 916	$\frac{3}{8} \times 1 \frac{3}{8}$		WM 936	$\frac{7}{16} \times 1 \frac{3}{8}$		WM 946	$\frac{3}{8} \times 1 \frac{3}{8}$
	WM 907	$\frac{7}{16} \times 1 \frac{1}{4}$		WM 917	$\frac{3}{8} \times 1 \frac{1}{4}$		WM 937	$\frac{7}{16} \times 1 \frac{1}{4}$		WM 947	$\frac{3}{8} \times 1 \frac{1}{4}$
	WM 908	$\frac{7}{16} \times 1 \frac{1}{8}$		WM 918	$\frac{3}{8} \times 1 \frac{1}{8}$		WM 938	$\frac{7}{16} \times 1 \frac{1}{8}$		WM 948	$\frac{3}{8} \times 1 \frac{1}{8}$
	WM 910	$\frac{7}{16} \times \frac{7}{8}$		WM 920	$\frac{3}{8} \times \frac{7}{8}$		WM 940	$\frac{7}{16} \times \frac{7}{8}$		WM 950	$\frac{3}{8} \times \frac{7}{8}$
	WM 911	$\frac{7}{16} \times \frac{3}{4}$		WM 921	$\frac{3}{8} \times \frac{3}{4}$		WM 941	$\frac{7}{16} \times \frac{3}{4}$		WM 951	$\frac{3}{8} \times \frac{3}{4}$

PANEL STRIPS
MULLION CASINGS

	WM 955	$\frac{3}{8} \times 2 \frac{1}{4}$
	WM 956	$\frac{3}{8} \times 2$
	WM 957	$\frac{3}{8} \times 1 \frac{3}{4}$
	WM 960	$\frac{3}{8} \times 2 \frac{1}{4}$
	WM 962	$\frac{3}{8} \times 2$
	WM 963	$\frac{3}{8} \times 1 \frac{3}{4}$
	WM 965	$\frac{3}{8} \times 2 \frac{1}{4}$
	WM 967	$\frac{3}{8} \times 2$
	WM 968	$\frac{3}{8} \times 1 \frac{3}{4}$
	WM 970	$\frac{3}{8} \times 2 \frac{1}{4}$
	WM 972	$\frac{3}{8} \times 2$
	WM 973	$\frac{3}{8} \times 1 \frac{3}{4}$
	WM 975	$\frac{3}{8} \times 2 \frac{1}{4}$
	WM 977	$\frac{3}{8} \times 2$
	WM 978	$\frac{3}{8} \times 1 \frac{3}{4}$
	WM 980	$\frac{3}{8} \times 2 \frac{1}{4}$
	WM 982	$\frac{3}{8} \times 2$
	WM 983	$\frac{3}{8} \times 1 \frac{3}{4}$
	WM 985	$\frac{3}{8} \times 2 \frac{1}{4}$
	WM 987	$\frac{3}{8} \times 2$
	WM 988	$\frac{3}{8} \times 1 \frac{3}{4}$

RABBETED STOOLS

SPECIFY WIDTH OF RABBET
AND DEGREE OF BEVEL



WM 1131	$1 \frac{1}{16} \times 3 \frac{5}{8}$
WM 1133	$1 \frac{1}{16} \times 3 \frac{1}{4}$
WM 1134	$1 \frac{1}{16} \times 2 \frac{3}{4}$
WM 1153	$\frac{11}{16} \times 3 \frac{1}{4}$
WM 1154	$\frac{11}{16} \times 2 \frac{3}{4}$
WM 1155	$\frac{11}{16} \times 2 \frac{1}{2}$
WM 1156	$\frac{11}{16} \times 2 \frac{1}{4}$
WM 1161	$1 \frac{1}{16} \times 3 \frac{5}{8}$
WM 1163	$1 \frac{1}{16} \times 3 \frac{1}{4}$
WM 1164	$1 \frac{1}{16} \times 2 \frac{3}{4}$
WM 1193	$\frac{11}{16} \times 3 \frac{1}{4}$
WM 1194	$\frac{11}{16} \times 2 \frac{3}{4}$
WM 1195	$\frac{11}{16} \times 2 \frac{1}{2}$
WM 1196	$\frac{11}{16} \times 2 \frac{1}{4}$

Figure 31-10. (Continued)



USING WHAT YOU LEARNED

It is important to search the construction drawings to determine what kind and size of material is used for interior trim throughout the house. In the Lake House, what kind and size of material is used as trim at the bottoms of the walls in the lower level, where the floors are concrete? Wall Section 3/4 shows 1" × 4" cellular PVC base trim at this location. Cellular PVC is not affected by the moisture that may be in the concrete.

Assignment

Refer to the Lake House drawings in your textbook packet to complete the assignment.

1. What size or rating and what kind of insulation are to be used in each of the following locations?
 - a. Framed exterior walls
 - b. Roof
 - c. Under heat sink
 - d. Masonry walls of playroom
2. What type of molding is to be used as casing around interior doors?
3. What type of molding is used at the bottom of interior walls and partitions?
4. What kind of trim is used to cover the lower edges of exposed LVL beams?
5. Describe the wall finish in the playroom including:
 - a. What the wall finish material is fastened to
 - b. The kind of material used for wall finish
6. What material is used for ceiling finish in the playroom?
7. What material is used for subflooring on typical framed floors?
8. What is the finished floor material at the heat sink?
9. What covers the interior faces of LVL beams?
10. What is the finished wall material in the bedrooms?

UNIT 32

Cabinets

Objectives

After completing this unit, you will be able to perform the following tasks:

- List the sizes and types of cabinets shown on a set of drawings.
- Identify cabinet types and dimensions in manufacturer literature.

Showing Cabinets on Drawings

The layout of the cabinets can be determined by reading the floor plan and cabinet elevations together. The floor plan normally includes reference marks indicating each cabinet elevation (see **Figure 32–1**). The floor plan shows the location of major appliances and may include some overall layout dimensions.

When the building has separate electrical drawings, the electrical installer must coordinate these designated outlet locations between the electrical and architectural drawings. There may be electrical outlets shown on the architectural drawings and not shown on the electrical drawings. These variances must be resolved early in the rough-in stage of construction.

More complete cabinet information is usually shown on the cabinet elevations (see **Figure 32–2**). Cabinet elevations are drawn for each direction from which cabinets can be viewed. These elevations show the types of cabinets, their sizes, and their arrangement. Cabinet types and sizes are recognized by a combination of drawing representations and commonly used letter/number designations. Some drawings rely heavily on standard dimensioning and





Figure 32–1. Kitchen floor plan with key to cabinet elevations.




Courtesy of Home Planners, Inc.

Figure 32-2. Elevations for Figure 32-1.

pictorial representation. This is true of the case shown in **Figure 32-2**. Other drawings include a letter/number designation for each cabinet, as shown in **Figure 32-3**. The letter part of the designation represents the type of cabinet. Architects and drafters vary in how they use letter designations, but they are usually easy to understand after a moment's study. Some typical letter designations are shown in **Figure 32-4**.

The numbers in the cabinet designation represent the dimensions of the cabinet. Base cabinets are a standard height (usually 34½ inches, resulting

in 36 inches when a 1½-inch countertop is added) and a standard front-to-back depth (usually 24 inches). Therefore, base cabinet designations only include two digits to represent width in inches. Wall cabinets are a standard front-to-back depth (usually 12 inches), but the width and height vary. Therefore, wall cabinet designations include four digits—two for width and two for height. The first and second digits usually indicate width, and the third and fourth digits usually indicate height. **Figure 32-5** explains a typical cabinet designation.



KITCHEN ELEVATIONS

Figure 32-3. Letter/number designations for cabinets.

LETTER	CABINET TYPE
W	WALL CABINET
WC	CORNER WALL CABINET
B	BASE CABINET
D OR DB	DRAWER BASE CABINET
BC	BASE CORNER CABINET
RC	REVOLVING CORNER CABINET
SF	SINK FRONT (ALSO FOR COOKTOP)
SB	SINK BASE (ALSO FOR COOKTOP)
U	UTILITY OR BROOM CLOSET
OV	OVEN CABINET

Figure 32-4. Key to typical cabinet designations.




Figure 32-5. Typical cabinet designations.

In addition to cabinets, most cabinet manufacturers provide a variety of accessories:

- Shelves are finished to match the cabinets, so they can be used in open areas.
- Valances are prefinished decorative pieces to use between wall cabinets (over a sink, for example).
- Filler pieces are prefinished boards used to enclose narrow spaces between cabinets.
- A variety of molding may be used for trim.



USING WHAT YOU LEARNED

Workers from many building trades must be able to understand cabinet size designations. Electricians, for example, need to know where the edge of a particular cabinet will be in order to install an outlet. Plumbers need to know cabinet types and sizes in order to locate piping for sinks, dishwashers, and icemakers. Of course, the carpenters who install the cabinets need to know the right location for installing each cabinet.

Describe the cabinet located directly above the dishwasher. The notation is W2418. The W indicates that it is a standard wall cabinet. The first two numerals, 24, indicate that it is 24 inches wide. The 18 indicates that it is 18 inches high.

Assignment

Refer to the Lake House drawings in your textbook packet to complete the assignment.

Make a list of all of the Lake House kitchen cabinets, including type of cabinet, height, width, and depth.

UNIT 33

Lake House Specifications

Objectives

After completing this unit, you will be able to perform the following tasks:

- Find specific information in construction specifications.
- Apply information from specifications to specific construction drawings.

Construction drawings provide much information about how a building is to be constructed—the positions and sizes of the parts and materials to be used. Some information is more practically recorded in written form and the construction specifications, often referred to as the *specs* provide that information. For example, it is not practical to show the grade of lumber to be used for roof framing or to indicate who is responsible for clean-up after construction is finished. For single-family homes, all of the necessary technical information is often conveyed on the drawings. In this case, there are likely to be extra notes on the drawings to convey the information that would otherwise be conveyed in separate specifications. The drawings for the Hidden Valley townhouse in Section 3 are a good example of notes on drawings that provide technical specifications. In this unit, we consider specifications that are written separately from the drawings.

CSI Format

Large and complex buildings can require a lot of information to be conveyed in the specs. Specs for a large commercial construction project can be hundreds of pages. To make it easier to find information, specification writers follow the Construction Specifications Institute's MasterFormat (*CSI format*) for organizing their specs. MasterFormat standardizes titles and section numbers for organizing data about construction requirements, products, and activities. It can include up to 48 divisions with numbered sections in each division (see **Figure 33-1**).

While this format makes organization of large projects easier to follow, it would be very cumbersome for a small project, like a single-family home. A more practical and often used system is to partially follow the CSI format. The major divisions follow the CSI format, but the numbering of subsections is modified or dropped altogether.

The format of the specs for the Lake House is an adaptation of CSI format. The major divisions follow CSI numbering, with unused divisions omitted. The subsections have been rearranged to better fit the needs of the project. Each of the technical divisions begins with a brief description of the work covered by that division. Also included are a description of the materials needed for that work and subsections for each type of work in the applicable division. To find a particular part of the construction project in the specs, use the following steps:

1. Look up the appropriate division on the Table of Contents.
2. Read the "Work Included" at the beginning of the division to be sure you have the right division.
3. Find the description of the necessary materials right after the "Work Included."
4. Read the applicable subsection covering the work you want to do.

Division	Title	Division	Title
1	General Requirements	27	Communications
2	Existing Conditions	28	Electronic Safety and Security
3	Concrete		Divisions 29 and 30 are reserved for future expansion.
4	Masonry	31	Earthwork
5	Metals	32	Exterior Improvements
6	Wood, Plastics, and Composites	33	Utilities
7	Thermal and Moisture Protection	34	Transportation
8	Openings	35	Waterway and Marine Construction
9	Finishes		Divisions 36 through 39 are reserved for future expansion.
10	Specialties	40	Process Integration
11	Equipment	41	Material Processing and Handling Equipment
12	Furnishings	42	Process Heating, Cooling, and Drying Equipment
13	Special Construction	43	Process Gas and Liquid Handling, Purification and Storage Equipment
14	Conveying equipment	44	Pollution Control Equipment
	Divisions 15 through 20 are reserved for future expansion.	45	Industry Specific Manufacturing Equipment
21	Fire Suppression	46	Water and Wastewater Equipment
22	Plumbing		Division 47 is reserved for future expansion.
23	Heating, Ventilating, and Air Conditioning	48	Electrical Power Generation
	Division 24 is reserved for future expansion.		
25	Integrated Automation		
26	Electrical		

Figure 33-1. MasterFormat for numbering construction standards.

SPECIFICATIONS FOR LAKE HOUSE

CONTENTS

GENERAL CONDITIONS		DOORS & WINDOWS	08000
GENERAL REQUIREMENTS	01000	FINISHES	09000
SITE WORK	02000	FIREPLACE	10000
CONCRETE	03000	EQUIPMENT	11000
MASONRY	04000	PLUMBING	220000
STRUCTURAL STEEL	05000	HEATING, VENTILATING, AND	
WOOD & PLASTIC	06000	AIR CONDITIONING	230000
THERMAL & MOISTURE PROTECTION	07000	ELECTRICAL	260000

(Divisions 12000 through 210000, 220000, and 250000 are not used.)

GENERAL CONDITIONS

The General Conditions of the Contract for Construction, AIA Document A 107, whether or not bound herein, are hereby incorporated into and made a part of this contract and these specifications.

01000 GENERAL REQUIREMENTS

A. ARCHITECT'S SUPERVISION

The architect will have continual supervisory responsibility for this job.

B. TEMPORARY CONVENIENCES /

The general contractor shall provide suitable temporary conveniences for the use of all workers on this job. Facilities shall be within a weathertight, painted enclosure complying with legal requirements. The general contractor shall maintain all temporary toilet facilities in a sanitary condition.

C. PUMPING

The general contractor shall keep the excavation and the basement free from water at all times and shall provide, maintain, and operate at his own expense such pumping equipment as shall be necessary.

D. PROTECTION

The general contractor shall protect all existing driveways, parking areas, side walks, curbs, and existing paved areas on, or adjacent to the owner's property.

E. GRADE LINES, LEVELS, AND SURVEYS

The owner shall establish the lot lines.

The general contractor shall:

1. Establish and maintain bench marks.
2. Verify all grade lines, levels, and dimensions as shown on the drawings, and report any errors or inconsistencies before commencing work.
3. Layout the building accurately under the supervision of the architect.

F. FINAL CLEANING

In addition to the general room cleaning, the general contractor shall do the following special cleaning upon completion of the work:

1. Wash and polish all glass and cabinets.
2. Clean and polish all granite.
3. Clean and polish all hardware.
4. Remove all marks, stains, fingerprints, and other soil or dirt from walls, woodwork, and floors.

G. GUARANTEES

The general contractor shall guarantee all work performed under the contract against faulty materials or workmanship. The guarantee shall be in writing with duplicate copies delivered to the architect. In case of work performed by subcontractors where guarantees are required, the general contractor shall secure written guarantees from these subcontractors. Copies of these guarantees shall

be delivered to the architect upon completion of the work. Guarantees shall be signed by both the subcontractor and the general contractor.

H. FOREMAN

The general contractor shall have a responsible foreman at the building site from the start to the completion of construction. The foreman shall be on duty during all working hours.

I. FIRE INSURANCE

The owner shall effect and maintain builder's risk completed value on this job.

02000 SITE WORK

WORK INCLUDED

This work shall include, but shall not be limited by the following:

- A. Clearing the site.
- B. Excavating, backfilling, grading, and related items.
- C. Removal of excess earth.
- D. Protection of existing trees to remain on the site.

All excavation and backfilling required for heating, plumbing and electrical work will be done by the respective contractors and are not included under site work.

It is the contractor's responsibility to field inspect existing conditions to determine the scope of the work.

02100 CLEARING

- A. Clean the area within the limits of the building of all trees, shrubs, or other obstructions as necessary.
- B. Within the limits of grading work as shown on the drawings remove such trees, shrubs, or other obstructions as are indicated on the drawings to be removed, without injury to trunks, interfering branches, and roots of trees to remain. Do cutting and trimming only as directed. Box and protect all trees and shrubs in the construction area to remain; maintain boxing until finished grading is completed.
- C. Remove all debris from the site; do not use it for fill.

02200 EXCAVATION

- A. Carefully remove all sod and soil throughout the area of the building and where finish grade levels are changed. Pile on site where directed. This soil is to be used later for finish grading.
- B. Do all excavation required for footings, piers, walls, trenches, areas, pits, and foundations. Remove all materials encountered in obtaining indicated lines and grades required. Beds for all foundations and footings must have solid, level, and undisturbed bed bottoms. No backfill will be allowed and all footings shall rest on unexcavated earth.
- C. The contractor shall notify the architect when the excavation is complete so that he may inspect all soil before the concrete is placed.
- D. Excavate to elevations and dimensions indicated, leaving sufficient space to permit erection concrete forms, walls, waterproofing, masonry, and inspection of foundations. Protect the bottom of the excavation from frost.

02260 BACKFILL

- A. All outside walls shall be backfilled to within 6 inches of the finished grade with clean fill. Backfill shall be thoroughly compacted.
- B. Unless otherwise directed by the architect, no backfill shall be placed before the first floor framing is in place. No backfill shall be placed until all walls have developed such strength to resist thrust due to filling operations.

02270 GRADING

- A. Do all excavating, filling, and rough grading to bring the entire area outside of the building to levels shown on the drawings.
- B. Where existing trees are to remain, if the new grade is lower than the natural grade under the trees, a sloping mound shall be left under the base of the tree extending out as far as the branches; if the grade is higher, a well shall be constructed around the base of the tree to provide the roots with air and moisture.
- C. After rough grading has been completed and approved, spread topsoil evenly to the previously stripped area. Prepare the topsoil to receive grass seed by removing stone, debris, and unsuitable materials. Hand rake to remove water pockets and irregularities. Seeding will be done by the owner.
- D. Furnish and place run of bank gravel as approved under all floor slabs.

03000 CONCRETE

WORK INCLUDED

Provide all materials, labor, equipment, and services necessary to furnish, deliver, and install all work of this section, as shown on the drawings, as specified herein, and/or as required by job conditions including, but not limited to the following:

- A. Concrete for all footings and piers.
- B. Concrete for all foundation walls.
- C. Concrete for all slabs on ground.
- D. Concrete for slab at heat sink.
- E. Furnishing and installation of all required anchors.
- F. Supplying, fabrication, and placement of all reinforcing bars and mesh and wire reinforcement for concrete where shown, called for, or required with proper supporting devices.
- G. Erection of all forms required for concrete work and removal upon completion of the work.
- H. The finishing of all concrete work as hereinafter specified.
- I. Porous fill below slabs on ground.

03010 MATERIAL

- A. Fine Aggregate
Fine aggregates for concrete shall consist of natural sand having clean, hard, sharp, uncoated grains free from injurious amounts of dust, lumps, soft or flaky particles, shale, alkali, organic matter, loam, or other deleterious substances.
- B. Coarse Aggregate (stone)
Coarse aggregates shall consist of crushed stone or gravel having clean, hard, strong, durable, uncoated particles, free from injurious amounts of soft, friable, thin,

elongated or laminated pieces, alkali, organic, or other deleterious matter.

- C. Water
All water used in connection with concrete work shall be clean and free from deleterious materials or shall be water used for drinking daily.
- D. Portland Cement
Portland cement shall be an approved domestic brand complying with Standard Specifications for Portland Cement, ASTM Designation C-150, Type 1. Only one brand of cement shall be used throughout the course of the work.
- E. All concrete is to be machine mixed in an approved mixer with a water metering device. Concrete is to reach a compressive strength of 2500 psi after 28 days.
- F. Reinforcement
All reinforcing, unless otherwise shown or specified, shall conform to ASTM A-615, Grade 60. Wire mesh reinforcing shall have a minimum ultimate tensile strength of 70,000 psi, and shall conform to ASTM Specifications A-185, latest edition.

03320 INSPECTION & PLACING

- A. All reinforcing shall be free of rust, scale, oil, or other coatings that tend to reduce the bond to concrete. All reinforcing is to be tied with 18 gauge wire at intersections and shall be held securely in position during the pouring of concrete.
- B. The architect will inspect all footing beds, forms, and reinforcing, just prior to placing concrete for footings, foundation, and slabs.
- C. All concrete shall be placed upon clean surfaces, and properly compacted fill, free from standing water. The concrete shall be compacted and worked into corners and around reinforcing.
- D. All concrete to be true and level as indicated on drawings to within $\pm \frac{1}{4}$ inch in 10 feet.

03330 FINISHING

- A. Slabs in occupied spaces shall be troweled smooth and free of trowel marks.
- B. Slabs in unoccupied spaces will have wood float finish.

04000 MASONRY

WORK INCLUDED

This work shall include but not be limited by the following:

- A. Brickwork
- B. Concrete block work
- C. Mortar for brick and block work

04010 MATERIALS

- A. Delivery and storage
All material shall be delivered, stored, and handled so as to prevent the inclusion of foreign materials and the damage of the materials by water or breakage.

Packaged materials shall be delivered and stored in the original packages until they are ready for use.

- B. Materials showing evidence of water or other damage shall be rejected.
- C. Brick shall be chosen by the owner from approved samples.
- D. Concrete block shall be load bearing, hollow, concrete masonry units and shall conform to the standard specifications of ASTM C-145-71.
- E. Mortar used for laying brick and concrete block shall consist of (1) one part masonry cement to (3) parts sand. The mortar ingredients shall comply with the following requirements:
 - 1. Masonry cement: ASTM C-91 T Type 2.
 - 2. Aggregates: ASTM C-144.
 - 3. Water: Clean, fresh, free from acid, alkali, sewage, or organic material.

04220 INSTALLATION

- A. All work shall be laid true to dimensions, plumb, square, and in bond and properly anchored.
- B. Joints shall be finished as follows:
- C. All brick shall be laid on full mortar bed with a shoved joint. All joints shall be completely filled with mortar. All horizontal and vertical joints shall be raked 3/8 inch deep.
- D. All mortar joints for concrete block masonry shall have full mortar coverage on vertical and horizontal face shells.
- E. Vertical joints shall be shoved tight. Full mortar bedding shall have ruled joints.
- F. Concealed work shall have joints cut flush.
- G. Fill voids in top course with masonry and set anchor bolts as shown on construction drawings.
- H. Protection: Cover the walls each night and when the work is discontinued due to weather.

04240 CLEANING AND POINTING

- A. Point up all the voids and open joints with mortar. Remove all of the excess mortar and dirty spots from the entire surface.
- B. Upon completion all brickwork shall be thoroughly cleaned with clean water and stiff fiber brushes and then rinsed with clean water. The use of acids or wire brushes is not permitted.

05000 STRUCTURAL STEEL

WORK INCLUDED

This work shall include but not be limited by the following:

- A. Structural tube columns.
- B. Welded flanges and plates.
- C. Structural steel rafters and beams.
- D. Stanchions at railings: This contractor shall supply fabricated stanchions to be installed by others.
- E. Grouting base plates.

05010 MATERIALS

- A. All structural steel to conform to ASTM A-36.
- B. Welding electrodes to conform to American Welding Society A5.1, E70 series.

05100 FABRICATION & ERECTION

- A. Drilling or punching of holes in columns, beams, and rafters shall not be permitted unless approved.
- B. Welds shall be by qualified operators and shall achieve complete penetration without voids, cracks, or porosity.
- C. Concealed structural steel shall have one coat of approved rust-resistant primer.

06000 WOOD & PLASTICS

WORK INCLUDED

All lumber, plywood, rough hardware, trim, paneling, and finish carpentry joinery and millwork required or implied by drawings and/or specifications. Cabinets and countertops are not included in this section.

06010 MATERIAL

- A. Grade or trademark is required on each piece of lumber; only official marks of association under whose rules it is graded will be accepted.
- B. Plywood shall conform to U.S. Product Standards PS-66 and shall be branded or stamped with type and grade.
- C. Moisture content shall not exceed 19% for framing lumber, 12% for plywood, and 8% for finish millwork.
- D. Work that is to be finished or painted shall be free from defects or blemishes on surfaces exposed to view that will show after the finish coat of paint or stain is applied. Defective materials not up to specifications for quality and grade for its intended use, or otherwise not in proper condition, shall be rejected.
- E. Rough lumber shall be dressed (4) four sides, air dried, well seasoned, sound, and free from splits, cracks, shakes, and waness, loose or unsound knots, and decay and excessive warp. Species and grades shall be those listed:
 - Douglas fir or hem-fir for rough carpentry
 - Each piece marked as to grade and free from defect.
 - No. 1 light framing with not more than 25% No. 2 framing allowed for all lumber 236 or larger.
 - No. 2 construction grade for studs.
 - Treated lumber: Southern yellow pine, ACQ-D treated per AWPA standards. Finish lumber and millwork: clear white pine or ponderosa pine.
- F. All nails, spikes, screws, bolts, joist hangers, and timber connectors as indicated, noted, or detailed on drawings, and as required to produce a safe, substantial, and workmanlike job in all respects.

06100 ROUGH CARPENTRY

- A. Install all rough wood framing, nailers, edge members, curbs, blocking, grounds, rough sills, backing, furring, and the like as indicated, detailed, noted, or required to properly support, back up, and complete the work of this section and of any or all trades under these contracts.
 - Securely attach and anchor to adjacent construction as detailed or as approved if detail is not provided.
 - Shim to line if so required to provide a uniform base for any other work.
- B. Provide double studs adjacent to and headers of size indicated over all openings.
- C. TJI joists and rafters to be installed according to manufacturer's instructions.

06200 FINISH CARPENTRY

- A. Provide all rabbets, splines, ploughs, and other cuts as detailed or required for neat, solid, fitting and joining.
- B. Finish millwork where indicated to have a clear finish shall be dressed and sanded, free from machine and tool marks, abrasions, raised grain and other defects on surfaces exposed to view. Construction and workmanship of millwork items shall conform to or exceed the requirements of AWI and good shop practices.
- C. Joints shall be tight and sopped formed as to conceal shrinkage.
- D. Interior millwork, running finish, and trim shall be in as long lengths as practicable, shall be spliced only where necessary, and only when approved by the Architect. All such splices shall be beveled and jointed where solid fastenings can be made.

07000 THERMAL & MOISTURE PROTECTION

WORK INCLUDED

- A. Dampproofing basement walls
- B. Vapor barriers
- C. Thermal insulation
- D. Roofing
- E. Flashing
- F. Caulking and sealants

07010 MATERIALS

- A. Dampproofing on basement walls to be Sonneborne Building Products, Semi-mastic Hydrocide 600 or approved equal.
- B. Vapor barriers under concrete slabs to be 4 mill thick polyethylene.
- C. Vapor barriers on insulated walls and roofs to be 4 mill thick polyethylene.
- D. Insulation exposed to earth shall be Dow Styrofoam SM, R-5.4 per inch.

- E. All rigid board insulation not exposed to earth shall be Owens Corning, High-R Sheathing, R-7.2 per inch.
- F. Batt insulation shall be Owens Corning Eco Touch Fiberglas unfaced, or approved equal.
 - 3 ½" thickness, R-11
 - 6" thickness, R-19
 - 9" thickness, R-30
- G. Metal flashing, 28 gauge Aluminum
- H. Caulking to be acrylic polymer conforming to F.F. TT-S-00230

07150 DAMPPROOFING

- A. Apply two coats of asphalt Dampproofing over all concrete or masonry wall surfaces to receive earth backfill.
- B. Apply polyethylene vapor barrier over gravel fill at all concrete slabs.
- C. Vapor barrier sheets to be lapped 6" minimum.
- D. Apply polyethylene vapor barrier to the heated side of all insulated frame walls and roofs.

07200 THERMAL INSULATION

- A. Pack all voids and cavities in exterior walls and roof. Avoid compressing batt insulation.
- B. Cut and fit insulation and vapor barriers as necessary for snug fit.
- C. Allow minimum air space of 1/2" between insulation and roof sheathing.
- D. Rigid insulation is to be nailed and glued with Dow Mastic number 11, according to the manufacturer's instructions.

07300 ROOFING

- A. Roofing shall be Image II, Standing Seam, 24 gauge steel, color by owner from approved samples.
- B. Roofing to installed according to manufacturer's instructions.

07600 FLASHING

- A. Apply factory painted metal drip edge at all roof edges.
- B. Chimney to be flashed at roof with Majestic number 9-6-12 galvanized flashing.
- C. Flash all pipes at roof with neoprene flashing of the proper size.
- D. Flash at all intersections of roofs and vertical surfaces as otherwise shown on construction drawings.

07900 CAULKING

Caulk all windows, doors, and other openings.

08000 DOORS & WINDOWS

WORK INCLUDED

All doors, door frames, windows, skylights, trim for each, and all hardware not included elsewhere.

08010 PRODUCTS

- A. Hollow metal doors to be manufactured by Pease, or approved equal.
- B. Wood doors by Iroquois Millwork or approved equal. Birch plywood skin with phenolic impregnated Kraft core.
- C. All door frames to be of clear pine in standard patterns as shown on the construction drawings. Side lites to be Iroquois, Weather Guard SL with 5/8" insulating glass.
- D. Windows to be Andersen, Series 200. Windows to include aluminum screens by the same manufacturer.
- E. Skylight to be Skylight Concepts number CMDADE1850.
- F. Door trim to be standard WM patterns milled from clear pine.
- G. Contractor shall allow \$1,500 for locksets, latches, bifold hardware, hinges, weather stripping, medicine cabinets, closet rods, and shower curtain rods.

08100 DOORS

- A. Frames to be plumb and square with accurately fitted joints. Set exposed nails with a nail set.
- B. Accurately align doors with frames and adjust hardware as necessary for smooth operation.
- C. Install molding as shown on construction drawings with accurately mitered corners.

08500 WINDOWS & SKYLIGHTS

- A. Install all windows true and plumb, and according to manufacturer's recommendations to produce a weathertight installation.
- B. Install all hardware and accessories and check all moving sections for smooth operation.

08900 HARDWARE

- A. Install all door and window hardware according to the manufacturer's recommendations and check for smooth operation.
- B. Install a closet rod in each closet. Closet rods to be secured through wall finish to blocking installed with rough carpentry.
- C. Install shower curtain rods over tub and shower stall. Shower curtain rods to be secured through wall finish to blocking installed with rough carpentry.
- D. Install a medicine cabinet (by owner) over each lavatory.

09000 FINISHES

WORK INCLUDED

- A. Gypsum wallboard
- B. Ceramic tile in baths and toilet rooms
- C. Quarry tile floors
- D. Painting and varnishing

09250 WALLBOARD

MATERIAL

- A. All wallboard material to be the product of one manufacturer; U.S. Gypsum, Flintkote, or approved equal. Drywall in baths, toilet rooms, and tub room to be moisture resistant.

INSTALLATION

- A. Gypsum wallboard shall be installed with joints centered over framing or furring.
- B. Fasten gypsum wallboard with power-driven drywall screw located not over 12" O.C. at all edges and in the field.
- C. Outside corners are to be protected with metal corner bead.
- D. Finish all joints with a minimum of three coats of joint compound and standard gypsum board reinforcing tape in accordance with the manufacturer's printed instructions.
- E. Dimples at screw heads shall receive three coats of compound.

09300 TILE

MATERIAL

- A. Wall tile to be American Olean Tile Company standard grade bright glazed in a color selected. Bathroom accessories to be same manufacturer and color.
- B. Floor tile in bath, toilet, and tub rooms to be American Olean unglazed 1' x 1" ceramic mosaic tile in color selected.
- C. Quarry tile to be installed in this specification will be 6" x 6" shale-and-clay tile provided by owner.
- D. Marble thresholds at all doors adjacent to mosaic tile floors shall be Vermont Marble 7/8" x 3 1/2".

INSTALLATION

- A. Layout ceramic tile on walls and floors so that no tiles less than half-size occur.
- B. Cut and fit tile around toilets, tubs, and other abutting devices.
- C. Install all floor tile by thin-set method in accordance with TCA recommendations.
- D. Install wall tile in mastic cement conforming to the recommendations of the tile manufacturer.
- E. Grout all tile work to completely fill joints.
- F. Clean all tile surfaces to present a workmanlike job.
- G. Install 12 bathroom accessories as follows:
 - 2 soap dishes
 - 3 toilet paper holders
 - 7 towel bars

09900 PAINTING

MATERIAL

- A. Exterior stain: One coat Minwax exterior stain or approved equal, in color by owner.
- B. Interior walls – flat: Two coats Martin Senour, Bright Life latex flat or approved equal, in colors by owner.
- C. Interior walls – semi gloss: Two coats Martin Senour, Bright Life latex semi gloss or approved equal, in colors by owner.



GREEN NOTE

Volatile organic compounds (VOCs) are emitted as gases from certain solids or liquids. VOCs include a variety of chemicals, some of which may have short- and long-term adverse health effects. Many of the products used in the construction and maintenance of homes for decades emit VOCs: paint and varnish, carpets, drapes, and cleaning agents, to name a few. It has only been in recent years that we have been aware of these VOCs. The level of VOCs in some products is no regulated by law. Most of the products named above are now available with either very low or zero VOCs and it is common for construction specifications to specify the acceptable levels of VOCs in products to be used in construction.

- D. Interior painted woodwork: Two coats Martin Senour, Bright Life latex semi gloss or approved equal, in colors by owner.
- E. Metal: Two coats DeRusto rust resistant enamel or approved equal, colors by owner.
- F. Polyurethane: Two coats United Gilsonite Laboratories, ZAR gloss.
- G. Primers: All primer to be that recommended by manufacturer of top coat.

APPLICATION

- A. Repair all minor defects by patching, puttying, or filling as normally performed by painting contractors.
- B. Prime uncoated wood surfaces with tinted primer and touch up previously painted surfaces.
- C. Sand all surfaces smooth before each coat of paint to produce a smooth and uniform job at completion.
- D. Protect all adjacent surfaces and other work incorporated into project against damage or defacement.
- E. Coat all surfaces according to the following painting schedule and as indicated on the drawings. All colors are to be selected by the owner.

Exterior Walls and Trim	Stain
Metal Railings	Rust-Resistant Enamel
Playroom	Walls Flat/Ceiling Flat
All Baths	Walls Semigloss/Ceilings Semigloss
Halls and closets	Walls Flat/Ceiling Flat
Living room	Walls Flat/Ceiling Flat
Dining room	Walls Flat/Ceiling Flat
Kitchen	Walls Semigloss/Ceilings Semigloss
Bedrooms	Walls Flat/Ceiling Flat

Loft	All Except Floor And Ladder: Flat
Loft floor and ladder	Polyurethane
Interior doors	Polyurethane
Interior stairs	Polyurethane
Unscheduled interior trim	Semigloss

10000 FIREPLACE

WORK INCLUDED

Provide and install fireplace, chimney, and accessories as indicated on the construction drawings. Related masonry and granite cap are not included in this section.

10310 EQUIPMENT

- A. Majestic Company fireplace number SR36A.
- B. Majestic Company chimney with 8" flue.
- C. All chimney accessories required to conform with printed instructions of Majestic Company.

10320 INSTALLATION

Fireplace and chimney are to be installed according to printed instructions of Majestic Company and as indicated on the construction drawings. All equipment is to be installed level and plumb and finished to provide a workmanlike appearance.

11000 EQUIPMENT

WORK INCLUDED

- A. Provide and install kitchen cabinets. This section does not include kitchen sink or related plumbing.
- B. Provide and install vanity cabinets. This section does not include lavatories or related plumbing.
- C. Provide and install granite countertops, vanity tops, fireplace cap. Provide necessary cutouts for kitchen sink, by plumbing contractor; cooktop, by owner; oven, by owner; and chimney, by masonry contractor.

11910 MATERIAL

- A. Cabinets and vanities shall be Merillat, Classic style.
- B. Granite countertops and fireplace cap to be supplied by Granite Mountain Stone Design in color selected by owner from approved samples. Granite to be 3 cm thickness.

11920 INSTALLATION

- A. Cabinets shall be installed level and true with no less than 4 screws per base unit and present a workmanlike appearance.
- B. Granite shall be adhered to cabinet frames with a full bead of silicone.

- C. All granite shall be installed with as few joints as possible. Joints shall be tight and filled with resinous material according to the manufacturer's instructions. Exposed edges shall be polished to match the finish of the top.
- D. Provide necessary cutouts for installation of kitchen sink, cooktop, and grill.
- E. Provide cutout for fireplace chimney with 1/8" clearance.

22000 PLUMBING

This division includes all plumbing. It is omitted here because these topics have not been covered earlier in the textbook.

23000 HEATING VENTILATING AND AIR CONDITIONING (HVAC)

This division includes heating, ventilating, and air conditioning. It is omitted here because these topics have not been covered earlier in the textbook.

26000 ELECTRICAL

This division covers all aspects of electrical work. It is omitted here because these topics have not been covered earlier in the textbook.



USING WHAT YOU LEARNED

The specifications for a construction project are part of the contract for the work to be performed, so it is very important to carefully read and fully understand what is written in the specs. The key to accurately applying the specs is to know where to find the information they contain. Look at the Table of Contents if there is one and find the division you are working on. Where in the lake house specifications would you find instructions for how to treat remaining trees that are above the natural grade when the site is being graded?

In Division 02000, Section 02270 is grading. Item B of that section says, "Where existing trees are to remain, if the new grade is lower than the natural grade under the trees, a sloping mound shall be left under the base of the tree extending out as far as the branches."

Assignment

Refer to the Lake House specifications to complete the assignment.

1. What division covers vapor barriers under slabs?
2. What is the material and thickness of the vapor barrier under the heat sink?
3. What material and rating is the thermal insulation under the heat sink?
4. What is the strength requirement for the concrete in the heat sink?
5. How is the concrete slab in the heat sink to be finished?
6. What make and model number is the skylight?
7. What division of the specs includes installing shower curtain rods?
8. What brand and type of paint is to be used on the kitchen walls?
9. Who is to choose the color of the paint for the kitchen walls?
10. What brand and type of paint is to be used on the trim around the skylight?

A. Refer to the Lake House drawings in your textbook packet to determine each of the following dimensions.



1. Northwest corner of the site to the high-water mark at the west boundary
2. Septic tank to the nearest property line
3. Width of the walk on the west side of the house
4. Width of the south end of the drive (in front of the garage)
5. Depth of the earth fill over the septic drainfield
6. Elevation at the butt of the most southerly maple tree to remain
7. Outside of the garage foundation (width \times length)
8. Outside of the garage footing (width \times length)
9. North to south spacing of the square steel columns
10. Length of the northwest square steel column
11. Length of the haunch under the slab between the north steel columns
12. East-west dimension inside the lower level bathroom at the widest end
13. Closet in bedroom #1 (width \times length)
14. Inside of bedroom #1 (width \times length)
15. Deck between the kitchen and the garage (width \times length)
16. Length of the joists in the loft
17. Height of the foundation wall at the overhead garage door
18. Elevation at the bottom of the concrete piers for the kitchen deck
19. Difference in elevations at the bottom of the south garage footing and the bottom of the nearest house footing
20. Elevation at the bottom of the deepest excavation
21. Width of the cabinet over the refrigerator
22. Width of the cabinet closest to the living room stairs
23. Total thickness of a typical exterior frame wall (allow $\frac{1}{2}$ inch for siding)
24. Lineal feet of soldier-course bricks in the fireplace
25. Lineal feet of 2×10 lumber in the eave of the corrugated roof
26. Finish floor to the top surface of the freestanding closet/cabinet unit in the kitchen (include surface material)
27. Length of the studs in the wall separating the playroom from the crawl space under the kitchen
28. Length of the steel dowels that anchor the foundation walls to the footings
29. Length of the $C8 \times 11\frac{1}{2}$ structural steel beam
30. Outside surface of the foundation under the dining room to the centerline of the deck footings
31. Door in the south end of the garage (width \times height \times thickness)
32. Length of the 2×4 studs under the living room bench
33. Width of the treads (front to back excluding nose) in the stairs from the kitchen to the bedroom level
34. Rough opening for the door from the hall into bedroom #1 (width \times height)
35. Thickness of the concrete at the haunches

B. Describe the material at each of the following locations in the Lake House. Include such considerations as the kind of material, nominal size of masonry units, and nominal size of lumber.

1. Tile field pipe
2. Reinforcement in the concrete slabs
3. Rungs in the ladder to loft
4. Hip rafter in the northeast corner of house
5. Roof insulation
6. Roof deck
7. Exterior wall studs
8. Rafter headers at skylight
9. Purlins under the corrugated roof
10. Finished surface on the west wall of playroom
11. Reinforcement in the footings
12. Anchor bolts in the wood sill
13. Wood sill
14. Vapor barrier under the concrete slab
15. Subfloor in the bedrooms
16. Floor joists in the kitchen
17. Floor joists in the bedrooms
18. Stair stringers between the decks
19. Top rail around the south decks
20. Top course of the foundation at heat sink
21. Expansion joint at the edge of heat sink
22. Rafters above the loft
23. Posts supporting the LVL beams
24. Girder under the west wall of bedroom #1
25. Base plates on the posts supporting LVL beams
26. Girder under the kitchen deck joists
27. Finished surface of the living room bench
28. Housed stringer on the north side of stair to bedrooms
29. Stair treads
30. Door casings (interior)
31. Door casings (exterior)
32. Window casings (interior)
33. Glazing (glass) in the window on south side of bedroom #1
34. Planks on the kitchen deck
35. Foundation at the west side of the kitchen deck

C. Answer each of these questions about the Lake House.

1. How many cubic yards of concrete are required for the concrete slab at elevation 337.00 feet?
2. What is the length of the concrete piers between the kitchen and the garage?
3. How many lineal feet of 1× pine trim are needed to cover the bottom of the LVL beam over the kitchen?
4. How long are the rafters in the corrugated roof? (Refer to the illustrated rafter table.)
5. How long is the hip rafter at the northeast corner of the roof? (Refer to the illustrated rafter table.)



D. Answer the following questions.

- Who should design roof trusses?
 - architect
 - carpenter
 - engineer
 - any of the above
- Which drawing will include information about the slope of a roof?
 - building elevation
 - truss delivery sheet
 - truss detail drawing
 - all of the above
- What is a piggyback truss?
 - a truss that is designed to be used as the top half of a large truss
 - a truss design that uses extra web members
 - a truss that is to be placed against the side of another truss
 - a particular brand of roof truss
- Which sheet would be the easiest one on which to find the required number of trusses of a particular type?
 - floor plan
 - truss delivery sheet
 - truss detail sheet
 - building elevation
- What is the most reliable place to find the spacing between trusses?
 - truss layout
 - floor plan
 - truss detail sheet
 - truss delivery sheet



3 PART

MULTIFAMILY CONSTRUCTION: URBAN COURTS

All architects use drawings to communicate their designs to those who must review them and those who will bring the design to life. Not all architects do this in exactly the same way. Some architects and drafters organize their drawings differently and some construction projects call for communicating different kinds of information. Part 3 provides you the opportunity to see some variations in how architects present information on drawings and in styles of construction.

The Urban Courts are one of the three housing styles included in a large development in downtown Sacramento, California. The Urban Courts drawings were selected for reference in Part 3 because they represent quality construction in a region where many construction practices and architectural styles are different from those in other parts of North America. The courts have multiple floor levels and provide homes for two families in a single building.

A complete set of drawings for the Urban Courts is far too large to include in the drawing packet that accompanies this textbook. The original sheet numbers have been retained, so the sheets in your packet are not numbered sequentially. As you work through the units of Part 3 and the corresponding drawings, take the time to understand all the information about a particular building feature and study all the drawings related to it.

UNIT 34

Orienting the Drawings

Objectives

After completing this unit, you will be able to perform the following tasks:

- Explain the information found on a typical cover sheet.
- Locate a particular building or plan within a large development.
- Visualize a building design by reading the drawings.

Organization of the Drawings

The drawings for a single- or multifamily dwelling include many sheets. Some of the drawings are produced by the architect or the architect's drafters; some may be produced by an engineer's office; and others by a specialty contractor, such as fire protection, plumbing, etc. Leafing through the entire set every time you need information from a particular drawing would be time consuming and confusing. Architects follow similar pattern in organizing their drawings. The general order of drawing sheets is similar to that of specifications: site plans are first; foundation plans and floor plans, next; building elevations, third; then, structural; mechanical, next to last; and electrical, last. The cover sheet usually includes an index or table of contents for the drawing set (see **Figure 34–1**). The drawing set for Urban Courts is too many sheets to include all of them in the drawing packet with this textbook. Only the sheets that are marked with an asterisk (*) in **Figure 34–1** are included in the packet. The complete cover sheet is included in the drawing packet with this textbook.

Notice that some of the listings for some of the sheets are encircled with a scalloped line. These are sheets that were modified after the original drawings were produced. A small numbered triangle matches numbered triangles found in the title block of the drawing (see **Figure 34–2**). The same technique, enclosing in a scalloped line or cloud, is used for revisions to the drawings themselves.

Some other useful information shown on the cover sheet for the Urban Courts are:

- **Symbol Legend**
Explains the symbols that are used for sections, elevations, keynotes (explained later), and revisions.
- **Graphic Legend**
Explains the symbols used in this drawing set. Some may be conventional symbols used throughout the industry and some may be peculiar to this drawing set.
- **Abbreviations**
Some of these abbreviations are customary throughout the industry, some customary in the region in which this work is done, and some may be peculiar to this drawing set. Without this index of abbreviations, some such as the difference between P/L and PL might be confusing.

Sheet Index

Architectural		Structural	
* A1.0	COVER SHEET	SN.1	GENERAL STRUCTURAL NOTES & DETAILS
A1.1	CODE COMPLIANCE	SN.2	GENERAL STRUCTURAL NOTES & DETAILS
A1.2	PHASE 1 – 1-HOUR FIRE PROTECTION	SN.3	GENERAL STRUCTURAL NOTES & DETAILS
A2.1	DIMENSION CONTROL PLAN	SN.4	GENERAL STRUCTURAL NOTES & DETAILS
* A3.1	FIRST FLOOR PLAN	* S7.1	FOUNDATION PLAN
* A3.2	SECOND FLOOR PLAN	* S7.2	SECOND FLOOR FRAMING
* A3.3	THIRD FLOOR PLAN	S7.3	THIRD FLOOR/ROOF FRAMING
* A3.4	FOURTH FLOOR PLAN	S7.4	FOURTH FLOOR/ROOF FRAMING
A4.1	INTERIOR ELEVATIONS	S7.5	ROOF FRAMING
* A5.010	EXTERIOR ELEVATIONS "A" (FRONT/REAR)	PT1	STRUCTURAL DETAILS
* A5.011	EXTERIOR ELEVATIONS "A" (RIGHT/LEFT)	* SD1	STRUCTURAL DETAILS
A5.012	ROOF PLAN "A"	SD2	STRUCTURAL DETAILS
A5.050	EXTERIOR ELEVATIONS "A4" TRIM (FRONT/REAR)	* SD3	STRUCTURAL DETAILS
A5.051	EXTERIOR ELEVATIONS "A4" TRIM (RIGHT/ LEFT)	SWSB1	SIMPSON STRONGWALL FRAME DETAILS
A5.052	ROOF PLAN "A4" TRIM	SWSB2	SIMPSON STRONGWALL FRAME DETAILS
* A5.4	BUILDING SECTIONS (ELEVATION "A")	Energy Calculations	
A6.010	EXTERIOR ELEVATIONS "B" (FRONT/REAR)	T24-0	MFIR MANDATORY MEASURES
A6.011	EXTERIOR ELEVATIONS "B" (RIGHT/LEFT)	T24-1	2013 ENERGY COMPLIANCE - URBAN COURTS BLD 1 - UNIT A
A6.012	ROOF PLAN "B"	T24-1W	2013 ENERGY COMPLIANCE - URBAN COURTS BLD 1 - UNIT A (WINDOW OPTION)
A7.010	EXTERIOR ELEVATIONS "C" (FRONT/REAR)	T24-1	2013 ENERGY COMPLIANCE - URBAN COURTS BLD 1 - UNIT B
A7.011	EXTERIOR ELEVATIONS "C" (RIGHT/LEFT)	T24-1W	2013 ENERGY COMPLIANCE - URBAN COURTS BLD 1 - UNIT B (WINDOW OPTION)
A7.012	ROOF PLAN "C"	Mechanical	
A7.050	EXTERIOR ELEVATIONS "C4" TRIM (FRONT/REAR)	M-1.0	HVAC SCHEDULE AND DETAILS
A7.051	EXTERIOR ELEVATIONS "C4" TRIM (RIGHT/ LEFT)	M-2.0	HVAC LAYOUT - URBAN COURTS BLD-1 PLAN A
A7.052	ROOF PLAN "C4" TRIM	M-3.0	HVAC SCHEDULE AND DETAILS
E.1	UTILITY PLAN, FIRST & SECOND FLOORS	M-4.0	HVAC LAYOUT - URBAN COURTS BLD-1 PLAN B
E.2	UTILITY PLAN, THIRD & FOURTH FLOORS	Fire Sprinklers	
AD1	EXTERIOR DETAILS - ROOF	FP-2	FIRE SPRINKLER PLAN
AD2	EXTERIOR DETAILS - SOFFIT & BRACES	FP-1	SITE PLAN & DETAILS
AD3	EXTERIOR DETAILS - WINDOWS		
AD4	EXTERIOR DETAILS - DOORS		
AD5	EXTERIOR DETAILS - MATERIAL		
AD6	DETAILS		
* FP1	DETAILS - FIRE PROTECTION		

Figure 34-1. Sheet Index for Urban Courts, Building 1.

- **Project Team**

It is sometimes helpful to know how to contact a particular member of the project team when a question arises about a confusing detail or an apparent conflict. The workers on the job site should

go to their foreman for such questions. The foreman should go to the superintendent if necessary; and the superintendent might go to the appropriate member of the project team.

Sheet Revisions Key		
#	DATE:	COMMENT
	01.13.15	INITIAL PLAN CHECK SUBMITTAL
2	02.03.15	PLAN REVIEW 1
3	02.11.15	OWNER MODIFICATIONS
4	03.03.15	PLAN REVIEW 2
5	04.13.15	CLARIFICATION
6	05.29.15	WINDOW MODIFICATIONS
8	06.30.15	FRAME WALK MODIFICATIONS

Figure 34–2. Sheet revisions key.

Identifying Buildings and Plans

Multifamily dwellings are often built in large developments—with many similar buildings in a single development. Some developments are completed in phases. One phase is completely constructed and begins earning income for the developer before the next stage is started. **Figure 34–3** shows the site plan for such a development. This project is to be developed in four phases. Each phase is outlined with a heavy broken line on the site plan.

The first phase of the development includes 11 buildings. Each building is labeled as to building type and the parts that make up the building (see **Figure 34–4**). Building type II is made up of four separate units, each with its own floor plan. Each unit is built like a separate building joined to the next (see **Figure 34–5**). Each plan is identified by a letter or letter and numeral. (The term *plan* is used to refer to a particular arrangement of rooms or design. This should not be confused with the use of *plan* to refer to a type of drawing.)

The plans in Building II are A, B1, B2, and A R. Each plan type is described on separate drawings.

One technique that is used to create similar, yet different, plans is to reverse them. A reversed plan is created by building the plan as though seen in a mirror. The reversed plan has the same features and the same dimensions, but their arrangement is reversed (see **Figure 34–4**). In Building II of this development, the

south end is a reversal of Plan A. This is designated on the site plan and in **Figure 34–6** as A R. The letter *R* indicates a reverse plan.



GREEN NOTE

One way of reducing the impact of housing on the environment is to increase the housing density in a development. Moving people closer together, leaves more space for the unbuilt environment. Many zoning ordinances require housing developments to include a certain percentage of green space. Housing density can be further increased by the use of multifamily buildings. Also, because these dwelling units share walls and have fewer exterior walls, they tend to be more energy efficient.

Visualizing the Plan

The first step in becoming familiar with any plan should be to mentally walk through the plan. This technique is described in Unit 18, for the Lake House. Refer to the Urban Courts drawings as you mentally walk through Building 1.

The First Floor Plan on Sheet A3.1 shows three options for the entry area. They are Elevations A, B, and C. This architect refers to optional designs as separate elevations. This study will focus on Elevation A.

Enter through the door at the lower right corner of the First Floor Plan. On your left are two doors, one into the garage for Unit A and one into the garage for Unit B. There is an overhead door at the far end of each garage. The two-side exterior walls are drawn with a material symbol that we have not seen. They have references to keynotes 5 and 25. Keynote 5 indicates that these are stone veneer walls. Keynote 25 tells us that they are 1-hour rated fire walls. The interior wall separating the two garages is also a 1-hour fire wall, but in this case, we know that because of the symbol used to draw the wall. That symbol is explained on the cover sheet.

Straight ahead of the entry door is a stair to the second floor. Go to the Second Floor Plan on Sheet A3.2. At the top of the stair, there is a window onto the balcony and an entry door into Unit A. To the right, as we enter the unit, there is a living room with three



Courtesy of Berkus-Group Architects.


Figure 34–3. Site plan.

windows in the back wall. To the right of the wall with windows is a door onto the balcony.

Walking back through the living room enter the kitchen area. Between the kitchen range and the refrigerator you enter the master bedroom suite. Notice the notation in the opening indicating that there is a soffit overhead just before you enter the suite. Immediately past the soffit is a coat closet on your left. The bedroom closet is on your right. Continuing past the closets there is a passageway on the left. On the left as you enter the passageway is the laundry with a washer and dryer. Straight


ahead is the master bath, with a vanity on the right, a shower straight ahead, and a separate toilet room on the left.

Return to the stairway and climb the stair to a landing where the stair makes a U turn and continues up. Now refer to the Third Floor Plan on Sheet A3.3. At the top of the stair the Unit B entry is on your left. Inside the door, immediately on your right is a coat closet. Past the closet turn right into the master suite. Straight ahead, on the rear wall of the building is a closet. On the left is the master bedroom. There is a sliding barn door inside the bedroom. Opposite the bedroom doorway is the bathroom



Courtesy of Berkus-Group Architects.

Figure 34-4. This is a section of the site plan at the size it was drawn.



Courtesy of Berkus-Group Architects.

Figure 34-5. Building type II includes four housing units.

door. Inside the bathroom there is a toilet on the right, a vanity on the left, and a shower straight ahead.

Back out through the passageway and enter the kitchen area on your right. On the left is a storage

closet. The kitchen has an island sink and cabinets and appliances on two walls. Beyond the kitchen is the living room, at the front of the building. Turn left at the front wall of the building into a passageway with the




Figure 34-6. A reversed plan is similar to what would be seen by looking at the plan in a mirror.

laundry door on the left. Beyond the laundry room is a stair leading up.

Refer to the Fourth Floor Plan on Sheet A3.4. The stairs lead up to a loft, providing more living space. There is also a storage area. On the left wall of the

loft is a sliding door onto the roof deck. The roof is sloped $\frac{1}{4}$ " in 1 foot, but that is gradual enough to allow for outdoor furniture. Two sides of the roof deck are open, but protected by a railing, described in Keynote 17.



USING WHAT YOU LEARNED

When similar style buildings are built in one development, it is desirable to make them appear to be different from one another. This can be done by using mirror images of the floor plans and elevations, by varying the architectural trim, and even by slight modifications in the buildings' exterior elevations. Some of these techniques are used in the Urban Courts. List all of the variations that are to be built in Block 3 (see **Figure 34-7**): Building 1, Elevation A; Building 1, Elevation B; Building 1, Elevation C; Building 2, Elevation A; Building 2, Elevation B; Building 2, Elevation C; and each of these reversed (mirror images).



URBAN COURTS
 PHASE 1 / BLOCK 3 - 1-HOUR FIRE PROTECTION

Courtesy of The Mill at Broadway, Jeffrey DeMure + Associates Architects Planners, Inc.

Figure 34-7. Urban Courts sheet A1.2.

Assignment

Refer to the Urban Courts drawings in your textbook packet to complete this assignment.

1. Define the following abbreviations:

- a) SOFF
- b) TOS
- c) CR
- d) P/L
- e) PL

2. What sheet has details for exterior doors?

3. Sheets A5.01 through A5.052 have been changed since the originals were drawn. Who requested the changes?

4. **Figure 34-7** is Sheet A1.2 of the Urban Courts drawings. How many times is Building type 1, Elevation A, Reversed to be built in Block 3?

5. What wall surface material is to be used on the faces of the wall separating the two garages?

6. What fire protection requirements are stated for the doors that separate the garages from the living space?

7. List the types of windows and their sizes for the master bedroom of Unit A.

8. What size framing material is to be used for the wall separating the living room from the balcony in Unit A?

9. Between the coat closet and the master bedroom in Unit B there is a soffit overhead. What are the dimensions of the soffit, including the dimension from the finished floor to the surface of the soffit?

10. What type of wall construction is specified for the back wall of the storage closet on the third floor?

UNIT 35

Fire-Rated and Acoustical Considerations

Objectives

After completing this unit, you will be able to perform the following tasks:

- Identify and explain the construction of fire-rated walls.
- Find and interpret detailed information on acoustical considerations in walls, floors, and ceilings.

Multifamily buildings are constructed the same way as single-family buildings in most respects. A wall that is shared by two living units in a multifamily structure is called a *party wall* or *common wall* (see **Figure 35-1**). In addition to the usual requirements of a wall, a party wall provides more fire resistance and sound privacy. When two living units are separated by a floor and ceiling, that construction needs to provide the same protection a party wall would provide.

Fire-Rated Construction

Fire-rated construction serves two purposes in the event of a fire. It slows the spread of fire, and it maintains structural support longer than nonfire-rated construction. Approved fire caulking or fill must be used at all utility-line fire-rated wall penetrations.

The most obvious way in which a wall, floor, ceiling, or roof can slow the spread of fire is by having a fire-resistant surface. Plaster and gypsum wallboard are fire-resistant materials. They do not burn, and they do not easily transmit the heat of fire to the framing members on the other side. Unfortunately standard gypsum wallboard breaks down and crumbles in very high heat. Fire-rated wallboard is used where a fire-rated wall is required. Fire-rated gypsum wallboard is Type X or Type C wallboard. (See **Figure 35-2**). Varying degrees of fire resistance can be achieved by using a second layer of fire-rated drywall on one or both sides of the wall. Other materials, such as OSB that has been treated to resist the spread of fire, might be used in place of gypsum wallboard.

Fire-rated construction is frequently used to separate garages and mechanical rooms from living spaces. Party walls are also fire rated to prevent a fire from spreading between housing units. To completely separate the housing units, a fire-rated party wall should extend all the way from the foundation to the roof.

Most building codes allow an alternative to extending the party wall through the roof. The fire-rated construction may end at the bottom of the roof as long as the roof is of fire-rated construction (see **Figure 35-3**). This usually means that the roofing material resists fire for as long as the party wall does. For example, if the party wall is required to be a 1-hour code wall (it resists fire for 1 hour), the roof must be covered only with material that also resists fire for 1 hour.

Fire-rated walls must also prevent fire from spreading vertically inside the wall. If left open, the spaces between the studs in a frame wall act like chimneys, allowing flame to spread very quickly from one level to another. To prevent vertical flame spread, stud spaces are not permitted to be more than




Figure 35-1. A party wall separates two or more units.




Figure 35-2. By using two layers of fire-resistant panels on each side, this wall has a 2-hour fire rating. Flameblock is OSB that has been treated with a compound called Pyrotite to resist fire.




Figure 35-3. Fire-rated party wall in attic space.

10-feet high. The spaces between the studs are closed off with **firestops** at each level (see **Figure 35-4**). Instead of wood firestops, the wall cavity can be blocked off with fire-resistant fiberglass insulation as shown in **Figure 35-2**.

Openings are usually avoided in fire-rated walls. Where it is necessary to include a door, it is made of fire-resistant material. The fire rating of the door must comply with the building code. Doors in fire walls are equipped with a self-closing mechanism.

Sound Control in Walls

To provide privacy between the housing units, common walls and floors should not allow the sound from one unit to be heard in the next unit. The measurement of the capability of a building element to reduce the passage of sound is its *sound transmission classification* (STC) (see **Figure 35-5**).

The word *acoustic* is often used when talking about sound control. It simply means having to do with sound or hearing.

Sound is transmitted by vibrations in any material: solid, liquid, or gas. To slow the passage of sound, a party wall must reduce the flow of vibrations. The materials used in the construction of most walls vibrate relatively well. Also, they transmit these vibrations to the air inside the wall. Sound can bend around corners and find its way through the smallest of openings. The air carries the sound to the other side of the wall, where it is transmitted to the air on the opposite side of the wall. The drywall joint between the wall and the ceiling may require sound deadening putty to prevent sound from passing through that joint. The electrical installer may be required to utilize acoustical insulation or some other sound attenuation material around flush device boxes. Raceways may require installations that reduce sound transmission, such as expansion joints, flexible raceway, or raceway offsetting through the party wall.

The STC rating of a wall can be improved greatly by not allowing the studs to contact both surfaces. This may be accomplished in one of two ways. One method is to




Figure 35-4. Firestops are installed between studs to prevent vertical drafts inside the wall.

STC RATING	EFFECTIVENESS
25	Normal speech can be understood quite easily.
35	Loud speech can be heard but not understood.
45	Must strain to hear loud speech.
48	Some loud speech can barely be heard.
50	Loud speech cannot be heard.

Figure 35-5. Sound transmission classes.




Figure 35-6. Typical sound-insulated wall.

attach clips made for sound insulation to the studs and then fasten the wallboard to these clips. The clips absorb the vibrations. Using the clips and sound-deadening fiberboard results in an STC rating of 52.

An STC of 45 is achieved without clips by using 2 × 4 studs and 2 × 6 plates. The studs are staggered on opposite sides of the wall so that no studs contact both surfaces (see **Figure 35-6**). The STC can

be increased to 49 by including fiberglass insulation. Separating the two sides of the wall framing on separate plates and insulating both sides of the wall cavity yields an even higher STC rating (see **Figure 35-7**). There are many other products and designs that can be used to control the sound transmission through a wall. It is essential that those who assemble common walls understand and follow the architect's design.




Figure 35-7. Double wall with insulation in both cavities yields an STC of 61.

Sound Control in Floor/Ceiling Assemblies

The principles that are used to stop the flow of sound through walls also apply to the floor/ceiling assembly, but wall construction is different from floor/ceiling construction. Some provision must be made to either absorb or block the vibrations that are sound. The IRC requires an STC rating of at least 45 for common walls and for floor/ceiling assemblies.

Another type of sound comes into play for floor/ceiling assemblies. When a person wearing hard-soled shoes walks across a wood floor the sound created by the impact of the footsteps can be a real annoyance to those living in the rooms below. The acoustics industry has devised a rating system for impact noise insulation. The Impact Isolation Class (IIC) is a rating of the floor/ceiling assembly's ability to isolate the sound from footfall and other impact sources. The IRC requires an IIC of 45 or more for common floor/ceiling assemblies between dwelling units. A 45 IIC rated floor would not

be satisfactory to many people. A rating of 65 would satisfy most individuals.

There are so many options for floor surface materials, sound deadening products, and ceiling materials that it is not possible to list even the most common options here. For example, the floor/ceiling assembly shown in **Figure 35-8** would yield an IIC of 51 to 56 and an STC of 56 to 60.

Keynotes

On larger construction projects, the drawings might become very cluttered and confusing to read if all of the information is drawn and described on them. Also there can be multiple places where the same information applies. To avoid this confusion much of the information may be shown in keynotes. A numbered mark, in this case, a small rectangle containing a number, is placed on the drawing. A column of notes on the right side of the drawing sheet explains what each of those keynotes indicates (see **Figure 35-9**).




Figure 35–8. A typical floor/ceiling assembly rated IIC 51-56 and STC 56-60.




Figure 35–9. Floor plan keynote 11.



USING WHAT YOU LEARNED

The building code requires some provision for preventing the vertical spread of fire in the cavity of a frame wall that is more than one story high. The interior wall between the stairs and the living spaces is such a wall. What provision is made for resisting the vertical spread of fire in this wall?

The logical place to begin is by looking at the floor plan to identify the wall in question. The second floor plan shows both the stairs and the living space of Unit A. Keynote 26 (see the boxed number on the plan) identifies this as a 2-hour common wall and refers to Detail 9/FP1. That detail shows several features that provide fire resistance. Both sides of the wall are sheathed with 7/16" Flameblock, a fire retardant OSB material, and both sides have 5/8" Type X gypsum board. The interior of the wall has fire blocking at 10' O.C. vertically and batt insulation, both of which resist the vertical spread of flames.

Assignment

Refer to the Urban Courts drawings in your textbook packet to complete the assignment.

1. List the type, thickness, and number of layers of gypsum wallboard for each of the following walls:
 - a. wall separating the two garages
 - b. wall between the entry area and Unit B garage
 - c. wall between kitchen and master bedroom closet on second floor
 - d. wall between the third floor kitchen storage room and the stairway
 - e. wall on the right as you ascend the stairs to the fourth floor
2. List each of the components of the assembly that make up the floor of the third floor master bedroom and the ceiling of the second floor living room.
3. What is used to stop the vertical spread of fires inside the 1-hour exterior walls of the Urban Courts?
4. What is done to stop the transmission of sound through the floor/ceiling assembly between the third floor kitchen and the second floor kitchen?
5. What is the STC rating of the floor/ceiling assembly in Question 4?
6. What is the slope of the roof above the third floor living room?
7. What is the height of the railing on the second floor balcony?
8. How many lineal feet of standard 2×4 walls are on the third floor? Do not deduct for doors or windows.

Seismic Considerations

36 UNIT

Where Earthquakes Occur

In some areas of the United States, earthquakes are a potential hazard and buildings in those areas must resist these seismic forces.

Earthquakes are one of the three types of loads that buildings must support by providing load paths through the structure and back down to the ground:

- Dead loads—the weight of the building materials.
- Live loads—loads that change or move around the building, such as people and furniture.
- Dynamic loads—loads that produce varying amounts of force, such as snow, wind, or earthquakes (seismic loads).

Many of the methods used to resist earthquake damage will also prevent damage from strong winds. This chapter will concentrate on how buildings resist seismic forces and how to identify those design elements on construction drawings.

The Seismic Design Category map shown in four parts in **Figure 36–1** shows the seismic design standard for all areas of the country. The chart in **Figure 36–2** describes the potential risk for each category.

Notice that most areas of high seismic activity are in the western states including Alaska and Hawaii. California is particularly high in active seismic areas.

The Urban Courts drawings in your drawing packet show a multistory apartment complex in Sacramento, California, with a Seismic Design Category of D. This project requires extensive seismic-resisting elements. This unit discusses and explains those elements using selected drawings from the project's structural drawings.

Forces Created By Earthquakes


The amount of damage done by a seismic event depends on several factors including distance from the earthquake's origin (epicenter), the strength and type of earthquake, site soil conditions, and the type of building construction. During a seismic event several types of energy waves are introduced into the structure. These include forces that shake the building back and forth, like moving a dish of jello rapidly left and right, and waves, much like ocean swells that lift the building up and then drop it. (See **Figure 36–3**.)

The side-to-side motion can come from any direction and causes the building to sway, particularly on the top floors. The ground waves can also tilt the

Objectives

After completing this unit, you will be able to perform the following tasks:

- Identify the Seismic Design Category for a given location.
- Explain how earthquakes affect buildings.
- Find information about seismic considerations on construction drawings.



Map prepared by U.S. Geological Survey in collaboration with the Federal Emergency Management Agency (FEMA) funded Building Seismic Safety Council's (BSSC) Code Resource Support Committee (CRSC).

Copyright © 2015 International Code Council, Inc., www.iccsafe.org. All rights reserved. Excerpts reprinted with permission.

Figure 36–1. Seismic Design Category map.




Figure 36-1. (Continues)





Figure 36-1. (Continued)



Copyright © 2015 International Code Council, Inc., www.iccsafe.org. All rights reserved. Excerpts reprinted with permission.

Figure 36-1. (Continued)

Seismic Design Category (SDC)	What Does It Mean?
A	Very small seismic vulnerability
B	Low to moderate seismic vulnerability
C	Moderate seismic vulnerability
D	High seismic vulnerability
E & F	Very high seismic vulnerability and near a major fault

Copyright © 2015 International Code Council, Inc., www.iccsafe.org. All rights reserved. Excerpts reprinted with permission.

Figure 36–2. Seismic Design Category risk.

building as well cause the building to lift off the foundation. Either of these forces can cause building floors to separate, the building to overturn, or the supporting walls to rack and fail. This racking would be similar to a free-standing row of books being pushed at the top edge until the row fell.

To resist this damage, the structural drawings for a building that might be subjected to seismic activity specify methods to ensure that

- the foundation design addresses specific site soil conditions.
- the foundation will hold together as one structural unit.
- the walls will be securely attached to the foundation.
- the walls will resist racking and overturning.
- the walls and floors of each story will be securely attached to the story above and below.
- the floor and roof will lend antiracking ability to the structure.

These structural design features allow the structure to absorb the energy of the earthquake and provide a load path for the energy to travel back into the ground while leaving the structure intact.

Soils Conditions



The site requires a geotechnical soils report, performed by a soils engineer. This provides information on soil types, the strength characteristics of the various soils present, landslide potential, and any other geologically related hazards.

Structures built on rock typically perform better than those built on soils, particularly loose soils. During earthquakes some soils are subject to liquefaction,

where the soil acts like a liquid, offering the structure no support. The geotechnical report addresses all these concerns and provides information on preparing the site for the foundation. The report also provides the structural engineer the site and soil information needed to design the foundation.

Reading Structural Drawings

The Structural Drawings for Urban Courts that are included in your packet are two plan sheets, S7.1 and S7.2, and two sheets of details, SD1 and SD3. Familiarize yourself with the various views, schedules, and notes and how they are referenced in the plans. Note that most details on S7.1 will be found on SD1 and most details on S7.2 will be found on SD3. The foundation and framing plans have schedules, such as Shearwall Schedule; Notes, such as General Floor Framing Notes; and other miscellaneous Notes. They also have other plan views but are titled Elevations B or C not to be confused with architectural elevations.

Schedules use different shapes, such as  or  to denote a reference to different schedules just as in architectural drawings.

The reference to details is the same as in the architectural drawings—a circle with the detail sheet number on the bottom and the detail number on the top.

Foundation Concrete is a very durable material and a good choice for building foundations, but it does have one drawback. While concrete is very strong in compression, it is weak in tension. Looking at the profile or elevation of a slab, the forces placed on the slab tend to make it deflect or bend causing a compression face and a tension face, **Figure 36–4**.





Figure 36–3. (A) When the first ground motion (from the left) arrives, the foundation and lower floors move to the right, but the upper floors remain in place momentarily. The upper floors eventually catch up to the bottom floors, but not before the ground moves to the right. Thus, shaking back and forth causes the building to sway, putting tremendous forces on the connections. (B) Surface waves roll under the building creating uplift that can move a building off its foundation or even overturn the structure.





Figure 36–4. Concrete slab loaded and failing in tension. Rebar reinforcement and post tensioning are used to strengthen the slab.

Because steel has high tensile strength, steel rebar is added to the tension side of the slab, usually the bottom. This adds tension strength to the slab. To add even more strength to the slab on the Urban Courts project, a process called post tensioning is used in addition to using rebar.

Post tensioning involves the placement of a grid of plastic coated cables in the concrete forms prior to concrete placement. Both ends of each cable penetrate the form and extend past the edge of the slab after concrete placement. Once the concrete is placed the concrete is allowed to partially cure, usually about seven days or until a specific compressive strength is achieved. One end of the tensioning cable is then anchored and a hydraulic tensioner is used to stretch the cable inside the slab. The plastic coating allows the cable to stretch inside the now solid concrete. The cables are tensioned to approximately 33,000 pounds. Specifications for the spacing and how much the cable will be elongated once tensioned are shown on Urban Courts Sheet S7.1.

Post tensioning is similar to prestressed concrete beams used in highway bridges and the result is the same. The cables are pulling the sides of the concrete slab together and the slab gains a much higher resistance to tension stresses.

Sheet S7.1 has a holddown schedule, and **Figure 36–5** shows a typical holddown assembly. Holddowns are used to anchor the first-story walls to the



Courtesy of Simpson Strong-Tie Company Inc.

Figure 36–5. HDU holddowns connect to imbedded bolts and are one type of holddown used in the Urban Courts project to connect walls. HDUs resist overturning and shear forces.

foundation and resist the overturning forces discussed earlier. Holdowns are manufactured in a variety of configurations; they can attach to a bolt embedded in the concrete or be set directly in the concrete. Usually they bolt to a post or studs in the wall, but can also be nailed to the post or studs. They are a critical part of the shear wall design. The other anchoring system is a series of foundation anchor bolts embedded in the concrete that bolt the wall bottom plate to the concrete, this resists both uplift and lateral displacement.

Walls

Urban Courts is a four-story wood frame building. Wood is a very forgiving material in earthquakes; it tends to bend and return to its original shape, but that same flexibility makes it too flexible for very large or tall buildings.

Any building in earthquake country needs to be braced to resist shear forces. Shear forces are those that move long walls or floors and distort the structure by racking. (See **Figure 36–6**.)

The standard shear resisting method used for walls is to apply structural sheathing such as plywood or OSB, nailed to the studs and plates in a prescribed manner. Because shear walls must resist the forces of an earthquake, the size, placement, and spacing of nails is especially important. In areas with very little seismic activity, it is not customary for construction drawings to specify nailing schedules, but in high-seismic areas nailing is typically specified by the structural engineer. Sheet S7.1 has a Shear Wall Schedule that includes information on sill plate thickness, nailing schedules, and whether structural panels are required on one or both faces of the wall. This schedule also calls out anchor bolt spacing and alternative connection methods.

Notice the garage door openings on the bottom floor. Since the shear panels cannot continue across




Figure 36–6. Wracking occurs when a frame wall is pushed sideways.

those openings, the narrow wall on one side of the opening is panelled each side and has heavy hold downs tying it to the foundation (see **J** in Shear Wall Schedule). There is also shear transferred from floor two to the first-story wall. A critical design consideration is that the shear wall sections stack vertically, upper-level shear walls occurring directly above the shear walls below.

On Sheet S7.2, there are references to strap holdowns connecting each story to the story above, holding the building together vertically and transferring shear from floor to floor. Details of these connections, including the straps are included on Sheet SD2.

Floor and Roof

An uninterrupted expanse of floor or roof sheathing creates a strong horizontal shear-resisting diaphragm that not only prevents the building from twisting or racking horizontally but can also share its shear strength with the walls below. Shear transfer details are shown on Sheet SD3. Also detailed are Drag Collectors, reinforced floor and roof members that collect both tension and compression loads from walls and transfer them to the roof or floor. These are particularly necessary where there are reentrant (inside) corners or other discontinuous load paths in the walls.



USING WHAT YOU LEARNED

The size and spacing of nails in a shear wall is very important. What size nails are used to nail the edges of the structural panel to the outside of the shear wall beside the garage doors and what is the proper spacing of those nails? Find the shear wall in question on the structural plans. This is identified as **J** on the Post Tension Foundation Plan, Sheet S7.1. The **J** indicates an entry on the Shear Wall Schedule. That schedule specifies that the ½" plywood is to be nailed at its edges with 10d nails spaced 2" O.C.







Assignment

Use the Urban Courts Structural and Architectural Drawings to answer the following questions.

1. Using the foundation plan, what does the **7** in the center of the west (left) garage door signify?
2. A wall separates Unit B garage from the storage and stair area. How is that wall secured to the floor?
3. What is the bottom plate material?
4. What is the minimum distance in height from the top of the footing to the adjacent grade?
5. How long will Post Tensioned Strand 3 be after tensioning?
6. What is the required shear panel thickness on the longest exterior wall of Unit A garage?
7. What type of nails are used for the wall in Question 6 and how often is the edge nailed?
8. Along the same Unit A garage wall is a reserved space. What is the purpose of this space and why can't it be placed anywhere along the wall?
9. What details show the floor strap holddown?
10. On Sheet S7.2, what does **3** denote? Where does this detail occur?
11. What hanger is called out at the upper right corner of the Second Floor Framing Plan?

Refer to the Urban Courts Drawings in your textbook drawing packet to answer the following questions.

1. What is represented by the symbols shown here?

- a. 
- b. 
- c. 
- d. 
- e. 
- f. 

2. Define the abbreviations as used on the Urban Courts drawings.

- a. HDR
- b. UON
- c. AFF
- d. SLP
- e. CLR

3. On what sheet number would you find the following:

- a. details for exterior doors
- b. front building elevation for buildings with Elevation A
- c. foundation plan

4. How many times does Building 2 with Elevation C appear in phase 1, block 3? (See **Figure 34-7**.)

5. What is known about Building 57, based on the information shown on **Figure 34-7**?

6. What type of glass is indicated for the front entrance?

7. What framing material is to be used for the front wall on the first floor?

8. What is represented by the dashed line on the first floor plan in the area of the wall-bike storage?
9. Describe the window on the second floor in the stairway looking out onto the balcony.
10. Why is the floor in the first floor living room different from the floor in the second floor living room?
11. On the stair landing shown on the third floor plan, there is a short section of wall with only an outline and no internal symbol adjoining the back wall of the storage closet. Describe the construction of the short section of wall with no internal symbol.
12. How many lineal feet of standard 2×6 frame wall are there on the third floor?
13. List the types of wall construction shown on the fourth floor plan.
14. On the second floor plan, why is the wall between the living room and the balcony of different construction than the wall between the kitchen and the master bedroom?
15. What components of the exterior wall in the third floor kitchen are used to reduce the spread of fire?
16. List all of the components of the wall separating the third floor kitchen and the stairs starting at the kitchen side of the wall and ending at the stair side.
17. What is the STC rating of the common wall between the second floor kitchen and the stairs?
18. What is the fire resistance rating of the common wall between the second floor kitchen and the stairs?
19. What is the minimum allowable height for the nonabsorbent wall finish in the showers?
20. What provides fire resistance at the rim board on exterior walls?
21. For walls shown with the symbol below, is the insulation to be faced or unfaced?




22. What is the minimum embedded depth for an anchor bolt securing a sill to the slab?
23. What is the purpose of Detail A on Sheet S7.1 titled High Load Diaphragm?
24. What holdown is used to anchor the front wall to the foundation?
25. What is the post material that the holdown in Question 25 is attached to?
26. How far must the anchor bolt for the holdown at the right rear corner be embedded in the concrete?
27. What is the stud spacing for the wall between the two garages?
28. The Post Tensioned Foundation Plan on Sheet S7.1 has several boxed callouts referring to Maximum Cable Spacing. What are the cables the notes refer to?
29. On Sheet SD3, both Detail 1 and Detail 2 are both titled Floor Shear Transfer, and both have 2 alternates. What is the difference between the views on these two details?
30. Which shearwall is most often used on the second floor?
See Second Floor Shearwall Plan

Multiple Choice

Select the best answer for the question.

31. Which type of gypsum board is most fire resistant?
 - a. type X
 - b. type M
 - c. type F
 - d. type L
32. Why is blocking paced between studs in walls over 10 feet tall?
 - a. to prevent wracking
 - b. to prevent vertical flame spread
 - c. to resist shear forces
 - d. all of the above

33. What is STC an abbreviation for?
- sound tested construction
 - seismic tensile control
 - sound transmission category
 - sound transmission classification
34. Which is a rating of a floor/ceiling assembly's ability to control the sound of footfalls?
- FFI
 - CRC
 - IIC
 - ASTM
35. What structural panel(s) is(are) required on the exterior side wall of the Unit A garage?
- 3/8" plywood on the exterior only
 - 3/8" plywood on both sides
 - 1/2" CDX on the exterior only
 - No structural panels are required
36. For the wall separating the Unit A garage and the entry area, how deep must the anchor bolts be embedded in the concrete slab?
- 7"
 - 10"
 - 12"
 - 17"
37. What material is to be used for the post at the right rear corner of the garage?
- 2 × 4
 - two 2 × 4s
 - 6 × 6
 - 8 × 8
38. How many and what size fasteners are used to attach the holdown to the post at the right rear corner of the garage?
- 8; 3/8 × 5 lag screws
 - 12; 10d nails
 - 12; 1/4 × 2 1/2 wood screws
 - 36; 1/4 × 2 1/2 wood screws
39. What is the required thickness of a sill plate in a shearwall marked **F**?
- 2 inches
 - 3 inches
 - 4 inches
 - The thickness cannot be determined without more information.
40. What secures beam FB12 to the post that supports it at the end nearest the front wall?
- 4 16d nails
 - HUC416 hanger
 - LTP4 clips
 - 2 CS16 straps



HEAVY COMMERCIAL CONSTRUCTION: SCHOOL ADDITION

Part 4 presents a thorough examination of the information found on prints for heavy commercial construction. The materials and methods used for large buildings are different from those used in light-frame construction. Also, the drawing set for a commercial project usually includes many more sheets than are found in the drawing sets for smaller buildings. To understand these drawings and make practical use of them, you need to understand the organization of the drawings and how the heavier materials are described on the drawings.

Part 4 also discusses the drawings used for air conditioning and heating, plumbing, and electrical systems. For those who work in the mechanical or electrical trades, the importance of understanding the drawings for these systems is obvious. However, all the trades work in the same spaces, and the work of one trade affects the other trades. Estimators, superintendents, inspectors, and many other construction professions also require an understanding of all the construction trades.

The School Addition project in your textbook packet drawings is an excellent building for inclusion in this book. It uses structural steel framing, reinforced concrete foundations, and a varied assortment of other materials typically



associated with heavy construction. Unlike most large commercial buildings, however, the School Addition is small enough, so that most of the drawings can be packaged with this book. Some drawings have been eliminated, either because they pertain to other work done on the existing school building or because they do not provide new opportunities for the study of commercial construction drawings. All the School Addition drawings are numbered as they were in the complete set, and the textbook makes frequent reference to the drawing numbers. The Material Keynotes, which are explained in this part of your textbook, are printed in Appendix A at the end.



Heavy Commercial Construction

37

UNIT

Architectural Style

Large buildings, such as the School Addition described in the drawings in your textbook packet, are usually designed in a different style from one- and two-family homes or even larger light-frame buildings, such as the Urban Courts.

Most larger commercial buildings are too large to employ the same construction methods as those used with homes and smaller buildings and have different architectural styles than they do (see **Figure 37–1**). For example, commercial buildings usually have a larger roof area, so it is not practical to slope the roof. This means that not only does the flat roof change the appearance of the building, but it necessitates the use of different roof framing and roof covering materials. Commercial buildings are designed to be as maintenance free as possible. The wood or vinyl molding that decorates the exterior of many houses would require too much maintenance for a commercial office building. This is not to say that a commercial building cannot be architecturally pleasing. In fact, because more money is generally available to design and construct large commercial buildings, they often tend to be extremely attractive and viewed as works of art. However, the aesthetic qualities in a commercial building are generally built into the overall design of the building, rather than applied after the shell is erected.

Larger buildings require greater strength. The weight of the materials required to build the School Addition is many times the weight of the materials to build even a large house. Also, the external loads (wind, snow, etc.) on a larger building are greater than those on a smaller building. All these greater loads require stronger structural members, more precisely engineered construction methods, and fastenings that transmit the loads from one structural member to the next. This usually dictates the use of structural steel and reinforced concrete for the structural elements of the building—the frame and foundation.

Structural Steel

Steel is made by alloying small amounts of carbon and other elements with iron. The amount of carbon in the steel determines its toughness. Other elements, such as chromium, copper, nickel, or titanium, are used to produce specific properties. Alloying chromium with the steel, for example, makes stainless steel. Structural steel is mild steel (a small amount of carbon is used) that is rolled into specific shapes used for construction. The most common structural

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe the major differences between light-frame construction and heavy commercial construction.
- Describe common structural steel shapes and their designations.
- Explain the differences between foundations for heavy structures and those for light-frame buildings.



Figure 37–1. Generally, medium to large commercial buildings are very functional in design.

shapes are shown in **Figure 37–2**. W-shapes are used for most beams and columns in steel-frame buildings. The designator for a structural steel member includes a symbol or capital letter to indicate the basic shape, one or more numbers to indicate the size, and a weight-per-foot designation. For example, drawing S200 for the School Addition (see **Figure 37–3**), shows a $W6 \times 25$ column. This is a *wide-flange* shape, with a 6-inch web, weighing 25 pounds per foot. Standard dimensions for structural steel shapes are published in the *American Institute for Steel Construction (AISC) Manual of Steel Construction*.

Structural steel members are most often joined by welding. Bolts are sometimes used to attach dissimilar materials, such as wood and steel framing members. Where bolts are to be used, they are usually shown by either symbols or a drawing of a bolt on the details (see **Figure 37–4**). Detail J-14 of the drawings for the School Addition (see **Figure 37–4**) introduces a technique that is often used on drawings for commercial construction. Instead of describing all the information on the detail drawing itself, many of the drawing callouts refer to a material legend. The *material legend*, which is a running list on the right side of most of the school drawings, identifies all the material items in the building by a legend number. Roof Edge Detail J-14, the drawing shown in **Figure 37-4**, shows four items identified only as 5.10D. The material legend on Sheet A504 identifies these as anchor bolts.

Welding Symbol

Welds are depicted in drawings by the use of standard welding symbols (see **Figure 37–5**). The American Welding Society (AWS) has developed a standard system for welding symbols. Each part of the welding symbol has a specific meaning. The arrow indicates what steel parts are to be welded. The term *welding symbol* should not be confused with *weld symbol*. The welding symbol is the complete symbol, including arrow, reference line, and any information added to it. The weld symbol indicates the type of weld to be made. The type of weld used most often in structural steel for construction is called a *fillet weld* and is indicated by a triangle. Other types of welds include plug welds, groove welds, and butt welds (see **Figure 37–6**). The reference line is always drawn parallel to the bottom edge of the drawing. The lower side of the reference line is called the *arrow side*. Any information, such as the type of weld, that is shown below the reference line applies to the side of the assembly to which the arrow points. The upper side of the reference line is called the *other side*. Information above the reference line applies to the side of the assembly away from the arrow (see **Figure 37–7**). The tail of the arrow is used to specify welding processes, electrode materials, and any other specifications that cannot be shown elsewhere on the welding symbol.







Shape	Letter Designation	Size Designation
 Wide Flange	W	depth of web × weight per foot
 Standard Beam	S	depth of web × weight per foot
 Channel or Miscellaneous Channel	C or MC	depth × weight per foot
 Structural Tube	TS	width × depth
 Tee	T	depth × weight per foot
 Angle	L	vertical leg × horizontal leg × thickness

Figure 37-2. Common structural shapes and their designations.

Shop Fabrication

Many structural subassemblies are more easily or more accurately fabricated in a shop environment. For example, if a special beam is to be installed with a welded subassembly on its ends, the subassembly would probably be fabricated in the steel shop so the

beam can be delivered to the site ready for erection. A large structural steel frame might require as many *fabrication drawings* (sometimes called *shop drawings*) as structural drawings. Usually, the field contractors do not deal with shop drawings, and they are not covered in this book. However, it is important to




Figure 37-3. Structural steel designation on a drawing.


recognize notes on the structural drawings that indicate a difference between field erection and shop fabrication. One example of such information is the field weld symbol (see **Figure 37-8**). The field weld symbol is a small flag at the break in the arrow of the welding drawing. This symbol indicates the weld is to be done in the field, not in the fabrication shop.

Foundations for Commercial Construction

Houses and small frame buildings usually have very simple foundation systems. The superstructure does not impose a heavy load on the foundation, so a simple *haunched slab* or *inverted-T foundation* is all that is

required to support the building in most soil conditions. As buildings become larger and more complex, they place a greater load on the foundation system. Also, larger buildings tend to be designed with much of the load being transmitted through a relatively small number of columns, instead of being spread over a sill member by closely spaced studs. To support these loads, the foundations of heavy buildings are carefully engineered by structural engineers and are more heavily reinforced than the foundations for smaller buildings.

Generally, continuous wall foundations are similar to those for smaller buildings. They consist of a *spread footing* that supports a continuous concrete wall. Because of the greater size of the structure, the footing and wall may be more massive for a heavy building



ROOF EDGE DETAIL		J-14
A20		3'-0"

Courtesy of Cataldo, Waters, and Griffith Architects, P.C.

Figure 37-4. Bolts are sometimes used for fastening structural members.




Figure 37-5. The basic welding symbol.

FILLET	PLUG OR SLOT	SPOT OR PROJECTION	STUD	SEAM	BACK OR BACKING	SUR-FACING	SCARF (FOR BRAZED JOINT)

FLANGE		GROOVE						
EDGE	CORNER	SQUARE	V	BEVEL	U	J	FLARE-V	FLARE-BEVEL

NOTE: --- REPRESENTS REFERENCE LINE WHICH IS NOT SHOWN AS A SOLID LINE FOR THIS PURPOSE.

Figure 37-6. Weld symbols used to show various types of welds.




Figure 37-7. Arrow-side, other-side significance.




Figure 37-8. This can be recognized as a field weld symbol by the flag. It is a 1/2-inch plug weld on both sides of the part and is to be done with E6010 electrode or filler metal.

and will probably require more and larger-diameter reinforcing steel. The overall layout of the foundation is shown on a foundation plan (see **Figure 37-9**). The dimensions and the reinforcement of the footings and walls are planned by engineers to carry the necessary loads, so it is likely that there will be several detail drawings to further describe the foundation systems at different points in the building (see **Figure 37-10**). Some of the reinforcement may be bars that protrude only a short distance out of the footing and into the wall. Reinforcing bars used in this way are called *dowels* and are used to keep the wall from shifting on the footing.

Column footings are located by the column centerlines. All these footings must be centered under the columns they support unless specifically noted

otherwise. The outline of the footing is shown on the foundation plan using dashed lines. This indicates that the footing is actually hidden from view by the concrete slab. Column footing dimensions are usually shown in a schedule (see **Figure 37-11**). There are usually several column footings of the same size. The mark-schedule system allows the drafter to show all the similar footings with a single entry on the schedule.

Piles are long poles or steel members that are driven into the earth to support columns or other grade beams. Pile foundations support their loads by means of several piles in a cluster, topped with a pile cap made of reinforced concrete. Pile foundations are not as common as spread footings and continuous walls. *Grade beams* are reinforced concrete.





Figure 37-9. The layout of the foundation is shown on the foundation plan.



13
S101

TYPICAL WALL SECTION

SCALE: 3/4" = 1'-0"

Figure 37-10. Foundation detail.

Courtesy of Cataldo, Waters, and Griffith Architects, P.C.

Courtesy of Cataldo, Waters, and Griffith Architects, P.C.

FOOTING SCHEDULE			
MARK	SIZE	REINF.	REMARKS
F1	3'-0" x 3'-0" x 12"	(4) #5 BARS EA. WAY	
F2	4'-0" x 4'-0" x 12"	(5) #5 BARS EA. WAY	
F3	4'-6" x 4'-6" x 12"	(5) #6 BARS EA. WAY	
F4	3'-0" x 4'-6" x 24"	(5) #5 SHORT BARS (7) #5 LONG BARS	OVERPOUR EXISTING BUILDING FOOTING (SIM. TO 14/S101)

Figure 37-11. Footing schedule.



USING WHAT YOU LEARNED


Just as it is important to understand the descriptions and sizes of all of the framing materials for a home construction project, it is also important to understand how the materials for a heavy project are indicated on drawings and in specifications. As stated in this unit, heavy construction projects usually involve a lot of structural steel.

On the second floor of the School Addition, classrooms 203 and 204 are separated by a folding partition. What structural shape and size is the roof beam above the folding partition? Begin by finding the folding partition on the second floor plan, which is C-14 on Sheet A102. Notice a callout for A-3/A504.

That detail shows the folding partition suspended from a partial drawing of a structural shape identified only as 5.10A, which would be a note on the Material Legend on the right side of the sheet. 5.10A simply says it is a steel beam. Based on where it is located (overhead on the second floor), it is most likely the roof beam in question. The Roof Framing Plan would be among the structural drawings, those with the letter S preceding the sheet number. Searching the structural drawings, we find that S201 is titled "Roof Framing Plan & Details." Looking in the corresponding area of the Roof Plan, we find a W18 x 40 beam with a callout referring to 5/S201. Detail 5 is a Folding Partition connection detail and it includes a W18 beam, so that it confirms what we found on the Roof Framing Plan.

Assignment

1. List five features of the School Addition that would be very different on a light-frame building, and explain the differences.
2. Describe each of the structural steel designations listed below:
W14 × 82
MC12 × 45
L6 × 3½ × 5/16
3. What is the structural steel shape and depth of the steel beam shown supporting the roof bar joists in detail 3/S202?
4. Draw a sketch showing where the welds would be made for each of the following symbols:



5. Describe the information given in the welding symbol on detail 3/S202.
6. Based on the information shown on Sheet S100, would you say that the School Addition has a pier foundation, grade beams, or a continuous wall foundation with spread footings?
7. How many pieces of reinforcing steel are shown in the footing on Wall Section 13/S101? Describe each, including its size and purpose.
8. How many 4'-6" × 4'-6" × 12" column footings are shown on the foundation plan for the School Addition?
9. There are several pairs of dashed (hidden) lines running vertically through the interior of the foundation plan. A note on one of these pairs of lines indicates that the slab is to be thickened. Why is it thickened at these points? How much thicker is it at these points than the surrounding area? What additional reinforcement is provided in the thickened portion of the slab?

UNIT 38

Coordination of Drawings

Objectives

After completing this unit, you will be able to perform the following tasks:

- Interpret the indexes and keys normally found on drawings for commercial construction.
- Use the number system for referencing details, sections, and other drawings.
- Explain the use of a grid system to locate columns and piers.
- Use the plans, elevations, and details to describe the layout of the rooms and spaces in a large commercial building.

Indexes

A set of working drawings for a large commercial building might fill more than 100 sheets. The School Addition in your textbook packet, although small by comparison with many large buildings, is part of a renovation and expansion program that spans three buildings and is described on 66 drawing sheets. A key plan in the lower right corners of sheets A101 and A102 shows the addition in relationship to the rest of the Junior/Senior High School building. Finding one's way around these 66 sheets would be a difficult task without some kind of an index. As with most commercial construction drawing sets, the cover page of the drawing set includes the index (see **Figure 38–1**).

It is not reasonable to include all 66 drawing sheets, plus the cover page, in your textbook packet because that would add the equivalent of more than two hundred pages to the book. Therefore, the packet only includes the drawings that are necessary to completely understand the additions to the Junior/Senior High School. The Index of Drawings, found in **Figure 38–1**, lists all the original drawing numbers. The drawing numbers that are underlined indicate the drawings contained in the drawing packet. Parts of other sheets are included as illustrations in this textbook. Drawings for civil (site work) that are not needed for an understanding of the structure and drawings for work on other school property are not included.

The *Drawing Index* includes the number of the drawing and the drawing title. *Drawing numbers* are made up of one or two letters and numerals. The letters indicate the basic type of construction shown on the drawing. Most architects use the letter *A* to indicate architectural drawings, *S* to indicate structural drawings, *C* for civil, and so on. The numbers indicate the sequence of the drawings in that section. Some architects indicate levels of drawings by using a series within a range to designate a level. For example, 100 through 199 might be reserved for foundations, 200 through 299 might be floor plans and elevations showing the overall superstructure, and 300 through 399 might be roof framing. This system is usually quite easy to spot by studying the index briefly.

Material Keying

In light-frame construction of small buildings, it is customary for call-outs on the drawings to label the material used. On larger projects, however, it is common for a material keying system to be used so that the drawings themselves are not cluttered by excessive notation.

GENERAL CONSTRUCTION CONTRACT	
A000	MASTER KEYNOTES
G001	SITE PLAN (JR/SR HIGH SCHOOL)
G002	KEY PLANS (JR/SR HIGH SCHOOL)
G003	KEY PLANS (BERNE ELEMENTARY + WESTERLO ELEMENTARY)
G100	SITE DEMOLITION PLAN (JR/SR HIGH SCHOOL + BERNE ELEMENTARY)
G101	LAYOUT PLAN (JR/SR HIGH SCHOOL)
G102	GRADING PLAN (JR/SR HIGH SCHOOL)
G103	PLANS + DETAILS (JR/SR HIGH SCHOOL)
G201	PARTIAL SITE PLAN, SOUTH (JR/SR HIGH SCHOOL)
G202	PARTIAL SITE PLAN, NORTH (JR/SR HIGH SCHOOL)
G203	PLAN AND DETAILS - SEWAGE DISPOSAL (JR/SR HIGH SCHOOL + BERNE ELEMENTARY)
G204	PLAN AND DETAILS; NEW WELL (JR/SR HIGH SCHOOL + BERNE ELEMENTARY)
G205	DRAINAGE PROFILES AND DETAILS (JR/SR HIGH SCHOOL + BERNE ELEMENTARY)
G206	DETAILS SEWAGE DISPOSAL (JR/SR HIGH SCHOOL + BERNE ELEMENTARY)
G207	PLANS AND DETAILS (JR/SR HIGH SCHOOL + BERNE ELEMENTARY)
G208	SECTIONS AND DETAILS (JR/SR HIGH SCHOOL + BERNE ELEMENTARY)
A001	ROOM FINISH SCHEDULE, DOOR SCHEDULE AND DETAILS (JR/SR HIGH SCHOOL)
A101	FIRST FLOOR PLAN (JR/SR HIGH SCHOOL)
A102	SECOND FLOOR PLAN (JR/SR HIGH SCHOOL)
A103	CAFETERIA + BOILER ROOM PLAN, DEMOLITION PLAN + DETAILS (JR/SR HIGH SCHOOL)
A104	FLOOR PLAN + DETAILS (BUS GARAGE)
A201	EXTERIOR ELEVATIONS + BUILDING SECTIONS (JR/SR HIGH SCHOOL)
A301	STAIR PLANS + SECTIONS (JR/SR HIGH SCHOOL)
A302	STAIR DETAILS (JR/SR HIGH SCHOOL)
A303	RAMP + ELEVATOR (JR/SR HIGH SCHOOL)
A501	WALL SECTIONS (JR/SR HIGH SCHOOL)
A502	WALL SECTIONS (JR/SR HIGH SCHOOL)
A503	PLAN DETAILS (JR/SR HIGH SCHOOL)
A504	WALL DETAILS (JR/SR HIGH SCHOOL)

Cataldo, Waters, and Griffith Architects, P.C.

Figure 38-1. Index from the cover page of school drawings. (Continues)

A5 1 0	WINDOW TYPES AND DETAILS (JR/SR HIGH SCHOOL)
A5 1 1	EXTERIOR ELEVATIONS (WESTERLO ELEMENTARY)
A5 1 2	WINDOW TYPES & DETAILS (WESTERLO ELEMENTARY)
A5 2 0	ROOF PLAN & DETAILS (JR/SR HIGH SCHOOL)
A6 1 0	INTERIOR ELEVATIONS & TOILET ROOM FLOOR PLAN (JR/SR HIGH SCHOOL)
S1 0 0	FOUNDATION PLAN & NOTES (JR/SR HIGH SCHOOL)
S1 0 1	FOUNDATION DETAILS (JR/SR HIGH SCHOOL)
S2 0 0	SECOND FLOOR FRAMING PLAN & DETAILS (JR/SR HIGH SCHOOL)
S2 0 1	ROOF FRAMING PLAN & DETAILS (JR/SR HIGH SCHOOL)
S2 0 2	STEEL FRAMING DETAILS (JR/SR HIGH SCHOOL)
S2 0 3	MISCELLANEOUS STEEL DETAILS & MASONRY REINFORCING DETAILS (JR/SR HIGH SCHOOL)
	ROOF RECONSTRUCTION CONTRACT
A5 2 1	ROOF PLAN & DETAILS (JR/SR HIGH SCHOOL)
A5 2 2	ROOF PLAN & DETAILS (BERNE ELEMENTARY)
A5 2 3	ROOF PLAN & DETAILS (BERNE ELEMENTARY)
	ASBESTOS ABATEMENT CONTRACT
ASB-1	ASBESTOS ABATEMENT - PLANS AND DETAILS (JR/SR HIGH SCHOOL)
ASB-2	PARTIAL PLAN - BOILER ROOM (JR/SR HIGH SCHOOL)
ASB-2 0 1	ASBESTOS ABATEMENT - PLANS AND DETAIL (WESTERLO ELEMENTARY)
	PLUMBING CONTRACT
P-1	PARTIAL PLAN - ADDITION, FIRST FLOOR AND SECOND FLOOR (JR/SR HIGH SCHOOL)
P-2	PARTIAL PLAN - CAFETERIA EXPANSION; DETAILS (JR/SR HIGH SCHOOL)
	HEATING, VENTILATING & AIR CONDITIONING CONTRACT
H-1	FIRST & SECOND FLOOR PLAN ADDITION; SYMBOL LEGEND (JR/SR HIGH SCHOOL)
H-2	PARTIAL PLAN BOILER ROOM; REMOVALS AND NEW WORK (JR/SR HIGH SCHOOL)
H-3	PARTIAL PLAN - CAFETERIA EXPANSION; DETAILS (JR/SR HIGH SCHOOL)
H-4	SCHEDULES AND DETAILS (JR/SR HIGH SCHOOL)

Cataldo, Waters, and Griffith Architects, P.C.

Figure 38-1. (Continued)

H-5	DETAILS (JR/SR HIGH SCHOOL)
H101	PARTIAL PLAN - BOILER ROOM; DETAILS; SCHEDULES (WESTERLO ELEMENTARY)
H201	PARTIAL PLAN, BOILER ROOM, DETAILS, SCHEDULES (WESTERLO ELEMENTARY)
H202	DETAILS AND SCHEDULES (WESTERLO ELEMENTARY)
	ELECTRICAL CONTRACT
E-1	FIRST + SECOND FLOOR PLAN, ADDITION LIGHTING (JR/SR HIGH SCHOOL)
E-2	FIRST + SECOND FLOOR PLAN, ADDITION UTILITIES (JR/SR HIGH SCHOOL)
E-3	PARTIAL PLANS CAFETERIA + COMPUTER LABS (JR/SR HIGH SCHOOL)
E-4	BASEMENT PLAN, PART PLANS BOILER ROOM, DETAILS (JR/SR HIGH SCHOOL)
E-5	FIRST FLOOR PLAN, DETAILS (JR/SR HIGH SCHOOL)
E-6	SECOND FLOOR PLAN, DETAILS (JR/SR HIGH SCHOOL)
E-7	SCHEDULES (JR/SR HIGH SCHOOL)
E101	GROUND FLOOR PLAN; DETAILS; SCHEDULES (WESTERLO ELEMENTARY)
E102	FIRST FLOOR PLAN; DETAILS; SCHEDULES (WESTERLO ELEMENTARY)
E103	SECOND FLOOR PLAN; DETAILS; SCHEDULES (WESTERLO ELEMENTARY)

Cataldo, Waters, and Griffin Architects, P.C.

Figure 38-1. (Continued)

The following, which is reprinted from the cover page of the School Addition drawings, explains the system:

MATERIAL KEYING SYSTEM

A KEYNOTING SYSTEM IS USED ON THE DRAWINGS FOR MATERIALS REFERENCES AND NOTES. REFER TO THE KEYNOTE LEGEND ON THE DRAWINGS FOR THE INFORMATION WHICH RELATES TO EACH KEYNOTE SYMBOL ON THE RESPECTIVE DRAWING.


EACH KEYNOTE SYMBOL CONSISTS OF A NUMBER FOLLOWED BY A LETTER SUFFIX. THE NUMBER RELATES TO THE SPECIFICATION SECTION WHICH GENERALLY COVERS THE ITEM THAT IS REFERENCED, AND THE LETTER SUFFIX COMBINED WITH THE NUMBER CREATES A KEYNOTE SYMBOL WHICH IDENTIFIES THE SPECIFIC REFERENCE NOTATION USED ON THE DRAWING. THE LETTER SUFFIX DOES NOT RELATE TO ANY CORRESPONDING REFERENCE LETTER IN THE SPECIFICATION.

THE ORGANIZATION OF THE KEYNOTING SYSTEM ON THE DRAWINGS, WITH THE KEYNOTE REFERENCE NUMBERS RELATED TO THE SPECIFICATIONS SECTIONS NUMBERING SYSTEM, SHALL NOT CONTROL THE

CONTRACTOR IN DIVIDING THE WORK AMONG SUB-CONTRACTORS OR IN ESTABLISHING THE EXTENT OF WORK TO BE PERFORMED BY ANY TRADE.

As the material keying system reflects the numbering of the C.S.I. Master Format, you may find it helpful to keep a bookmark in your text at **Figure 33-1**. The entire Master Format is too lengthy to include in this book, but that figure includes all of the Division numbers.

Figure 38-2 illustrates how this keynote system works. Notice that many of the callouts on this detail are a decimal number followed by a letter. That is the *keynote symbol*. Referring to the Index of Drawings (see **Figure 38-1**), we find that Sheet A000 is Master Keynotes. The complete legend of Master Keynotes, as it appeared on Sheet A000, is reprinted in Appendix A. The keynotes that pertain to a particular drawing sheet are also copied on the right end of the drawing sheet. In **Figure 38-2** the keynotes on the right side of the figure pertain to the drawings that were together on Sheet A302, where J-14 was located. The top right callout on J-14 has a keynote symbol, 3.30A. Referring to the material keying legend, 3.30A is cast-in-place concrete.



MATERIAL KEYING LEGEND (SEE SPECIFICATIONS*)	
3.30	CONCRETE SEE STRUCTURAL DRAWINGS*
3.30A	CAST-IN-PLACE CONCRETE
4.20	UNITE MASONRY CONCRETE MASONRY UNITS
5.10	STRUCTURAL STEEL SEE STRUCTURAL DRAWINGS*
5.10A	STEEL BEAM
5.20	STEEL JOISTS SEE STRUCTURAL DRAWINGS*
5.50	MISCELLANEOUS METALS
5.50A	MISCELLANEOUS SHAPE AND SIZE AS NOTED
5.50B	STEEL ANGLE
5.50C	1- $\frac{1}{4}$ " NOMINAL STEEL PIPE (1.66" O.D.) POST 4'-0" O.C. MAXIMUM
5.50D	10 GAUGE METAL PAN RISERS & TREADS
5.50E	MC 12 \times 10.6 STRINGER
5.50F	3- $\frac{1}{2}$ " \times 2- $\frac{1}{2}$ " \times $\frac{1}{4}$ "—LLV—PAN SUPPORT AT 3'-0" O.C. MAXIMUM
5.50G	1- $\frac{1}{2}$ " \times 1- $\frac{1}{2}$ " \times $\frac{1}{4}$ " STEEL ANGLE CARRIERS
5.50G	1- $\frac{1}{4}$ " NOMINAL STEEL PIPE (1.66" O.D.) HANDRAIL/GUARDRAIL
5.50AM	1" NOMINAL STEEL PIPE HANDRAIL (1.315" O.D.)
5.50AP	STEEL WALL BRACKET, JULIUS BLUM #662, OR EQUAL
5.50AY	STEEL PLATE, SIZE AS NOTE

Figure 38–2. Material keynote system.

This keynote replaces the customary callout on the drawing that would indicate that the landing and tread surfaces are cast-in-place concrete. More specific information, such as the grade of concrete and type of finish, would be indicated in Division 3 of the specifications. We know this because virtually all large construction projects use the C.S.I. Master Format to organize the specifications and Division 3 of the C.S.I. format is Concrete. Moving counterclockwise around the drawing, the next keynote symbol is 5.50E and is referenced to the stair stringer that is *beyond* the main part of the drawing. According to the material keying legend, 5.50E is covered in Division 5, Section 5.50 of the specifications, Miscellaneous Metals, and is an MC12 \times 10.6 stringer. (Unit 39 explains the meaning of this structural steel designation.)

Many of the material keynotes are referenced on several of the drawing sheets. In that case, they are reproduced on each of those sheets, as well as on the master legend on Sheet A000. All of the whole sheets with this book include the material keying legends as they were intended by the architects.

Reference Symbols Used on Drawings

A large building such as the School Addition requires a large number of sections and details to describe all aspects of the structure. The symbols for section views and the symbols for detail drawings are similar in appearance and format but have one significant difference. While both commonly use a circle as a symbol, the circle on a plan or other large-scale drawing to indicate existing detail contains the detail number above a horizontal line. Below the horizontal line is the sheet number on which the detail appears. Some element of the symbol, such as a rectangular flag, indicates that it is a detail drawing symbol. Section view symbols use the same scheme for specifying section number and sheet number but use a pointer instead of a rectangular flag to indicate the direction in which the section is viewed. **Figure 38–3** is reprinted from the cover page for the School Addition. In this case, Section B-2, which would be found on Sheet A100, is drawn with a view of the building from the top of the page toward the bottom.



Figure 38-3. Detail and section-view symbols.

(The Index of Drawings shows that the A series of drawings includes A000 and A101 through A610, but no A100. Apparently, A100 is just a hypothetical sheet for the sake of explaining how symbols are used.)

An example from the drawings that are used with this textbook can be seen on the First Floor Plan, Sheet A101. At the extreme right and left ends of the floor plan there is a section-view symbol, with its pointers directed toward the top of the drawing (north, according to the symbol in the lower right corner of the drawing). This symbol refers to Section View J-14 on Sheet A201. Section J-14 is in the top right of Sheet A201 and is a full cross-section view of the building as seen by a person standing on the south side of the building and looking north. The detail drawing symbol also can be found on the First Floor Plan, located just above the section-view symbol at the left end of the building. The direction of the rectangular flag indicates that it is also drawn as though viewed while facing north. That detail, which is at a larger scale ($\frac{3}{4}'' = 1'-0''$) than the building sections ($\frac{1}{8}'' = 1'-0''$), is number A-4 on Sheet A502. Detail A-4 includes further detail symbols, such as one about halfway up the wall referring to E-2 on A504, an expansion joint detail, at $3'' = 1'-0''$.

Interior elevations, which are often used to show the locations of fixtures, built-in furniture, and special architectural details, are usually referenced with their own type of symbols on floor plans. The symbol for an interior elevation also shows the direction from which the elevation is viewed, and it includes the number of the elevation and the sheet on which that elevation drawing appears. The symbol in **Figure 38-4** references elevation drawing L-10, which would be found on Sheet A103. The direction the triangular shape of the symbol points is the direction in which the elevation is viewed.



Figure 38-4. Elevation reference symbol.

Structural Grid Coordinate

Buildings with columns of reinforced concrete or structural steel as a main element of the building frame are laid out on a structural grid. The plans are drawn with a system of horizontal and vertical reference lines, so that all columns and details can be referenced to this grid. Vertical lines are numbered, and horizontal lines are lettered; or the system is reversed, with horizontal lines numbered and vertical lines lettered (see **Figure 38-5**). Columns are located by grid lines through their centers. The locations of major architectural components, such as walls, are located by dimensions that are referenced to the grid lines. The dimensions from the grid lines to the faces of exterior walls are usually given at the corners of the building. Interior partitions and other architectural elements may be located by dimensioning to the faces of these exterior walls, which are referenced to the structural grid.

Mental Walk-Through

As with each of the buildings discussed earlier in this textbook, one of the first steps you should take to familiarize yourself with the School Addition is to take a *mental walk-through*. Start at the front entrance to the first floor, in the lower right corner of the First Floor Plan. Enter door 101, and step into a stairwell marked stair #1. At the far end of the stairwell is door 102, which opens into a corridor. If you turn right in the corridor, you can walk up a ramp into the existing building, 10 inches higher than the first floor of the addition. Across the main corridor of the addition are the doors into two toilet rooms. A symbol in front of those doors indicates that Elevation A-8 on A610 will show you what the toilet room doors look like. As you continue your walk-through, you will come to many more elevation symbols. Look at each of the elevations on your walk-through to help you form a mental picture of the addition. You will also see several detail and section symbols. It will not be necessary to check each of these to form a mental picture of the addition, but you should look up a couple of each, just to make sure you are comfortable locating them.




Figure 38-5. Structural grid coordinate system.

Moving to the west in the main corridor, you come to a door (103) on your left. This is the entrance to a storage room. A dimension inside the storage room indicates that it is 13'-8½" wide. The exterior wall (south wall) of the storage room is on grid line F (see the left end of the floor plan). The wall with the door is on grid line D, which is 32'-7½" from grid line F. You could determine the actual face-to-face dimension between the north and south walls by looking at the details and sections, but that is not necessary for this mental picture of the building. Notice that where the east and west walls of the storage room intersect with the wall of the corridor, there are two heavy dashed crosses, indicating columns. Most walls are on column lines. These are on vertical grid lines 6 and 7.

Now walk through the janitor closet (JAN. CL.), each of the classrooms, and all corridors and stairwells.

Only a few highlights are described in this textbook, but after you have followed the walk-through described here, you should take a second walk-through, noticing and studying everything until you can visualize it.

Along both sides of the corridor are several references to Material Keynote 10.50A. Find that keynote on the legend at the right end of the drawing sheet or on the master keynote legend.

Through door 105 you enter classroom 103. On the floor plan, room 103 is only separated from room 104 by a single dashed line. That warrants investigation. A detail symbol directs you to A-6 on Sheet A504. That is a large-scale section view of a track detail. Looking again at the floor plan, you see a material keynote reference near the lower end of the dashed line: 10.62A. According to the legend, 10.62A is a folding partition, so rooms 103 and 104 are separated by a folding partition.

Across the corridor from classroom 103 is stair #2, which goes to the second floor. At the extreme left end of the corridor is a large rectangular area identified by keynote 14.20A, an elevator. Take the elevator to the second floor.

When you step off the elevator, you are on the second floor. Your walk-through is continued on Sheet

A102, Second Floor Plan. The second floor of the addition is almost identical to the first floor. It would be foolhardy to take for granted that the two levels are identical, but a quick survey shows that they have the same rooms in approximately the same layout. The rooms on the second floor are numbered in the 200 series to indicate that they are on the second floor.



USING WHAT YOU LEARNED

When working on projects that are based on a structural grid, and that is nearly all large buildings, it is vital to understand the grid and to be able to identify it quickly on the drawings. The School Addition is based on a grid with horizontal grid lines A through F and vertical grid lines 1 through 9. Major architectural and structural features are dimensioned at these grid lines.

For example, how far is the centerline of the folding partition separating Classrooms 103 and 104 from the western most grid line? This question can be answered by studying the first floor plan. The westernmost grid line is line 1, as numbered at the top left corner of the floor plan. The folding partition is shown by a broken line, with a callout for Detail A-6/A504 which confirms that this line is the partition. The partition aligns with the grid line near door 106 in the north wall of classroom 104. At the top of the drawing we see that this is grid line 3. Grid line 2 is $14' - 2\frac{1}{2}''$ from grid line 3 and grid line 1 is also $14' - 2\frac{1}{2}''$ from grid line 2, so the distance from grid line 1 to grid line 3 is $28' - 5''$. That is the dimension from the western grid line to the centerline of the partition.

Assignment

Refer to the drawings of the School Addition included in your textbook packet to complete this assignment.

1. List the sheet numbers for all the structural drawings for the addition.
2. On what sheet would you look to find wall details?
3. On what sheet would you find a framing plan for the roof?
4. What is indicated by Keynote 10.80C?
5. What keynote number is used to indicate plywood?
6. On the First Floor Plan, at about the midpoint of the north wall, a circle is drawn over a triangular flag. The notation inside the circle is J-6/A201. Explain what this symbol indicates and where further information can be found.
7. According to the building elevations and several wall details, there is a precast concrete sill or band that is about waist high on the exterior walls. What is the dimension from the top of the foundation to the bottom of this sill or band?
8. What is the height of the concrete block wall on the north wall of the first floor corridor?
9. What is the material on the lower surface of the canopy over the entrance at door 101?
10. What are the dimensions of the liquid marker board and tackboards on the west wall of classroom 107?
11. What are the dimensions of the mirrors in the toilet rooms?
12. Describe the location of column D3, relative to the floor plans.
13. What is the center-to-center spacing between columns F7 and F9?
14. What are the overall outside dimensions of the precast concrete band, such as is used near the base of typical exterior walls?
15. There is a door from a classroom (112) in the existing building into the storage room in the northeast corner of the addition. The door is made of what material?
16. Describe the differences between the rooms adjacent to the elevator on the first floor and on the second floor.

UNIT 39

Structural Drawings

Objectives

After completing this unit, you will be able to perform the following tasks:

- Describe the footings for columns and walls, including dimensions and reinforcement.
- Interpret the information found on a foundation plan, including dimensions of foundation walls, reinforcement of foundations, and the locations of the various elements.
- Describe each column, beam, and lintel shown on the structural drawings.
- Interpret structural details and sections.

Foundations for Commercial Buildings

The foundations for large, commercial buildings perform the same functions as those for light-frame buildings. The foundation supports the loads (weight) imposed on the superstructure and spreads those loads over a large enough area so that the earth can support it uniformly. In most commercial construction, the foundation system is composed of spread footings and stem walls and pads that act as footings under columns. These are the same elements that are found in most one- and two-family homes. The biggest difference in the foundation for a commercial building and that for a small house is the thickness of the concrete and the amount of reinforcing steel. There are apt to be more detail drawings for the foundation of a larger building, because of the need to describe the different sizes and shapes of footings and the reinforcement at many points in the foundation. The same knowledge is required to read the foundation plan for a large building as for a smaller one.

The drawings consist of a plan that shows the layout of the foundation and the major dimensions and detail drawings that describe reinforcement, expansion joints, and variations in design at special locations. The placement of column footings is indicated by referencing the structural grid coordinates. The structural grid indicates where the centerline of the column will be, but it is very important that the footing be placed accurately on this center. If the column does not rest on the center of the footing, the footing may tip due to the uneven pressure on the soil below (see **Figure 39–1**).

Structural Steel Framing

A structural steel building frame consists of *columns* (vertical members) and *beams* (horizontal members.) The largest beams, called *girders*, attach to the columns (see **Figure 39–2**). *Joists* are intermediate beams and are supported at their ends by the girders. *Lintels* are the beams that support the weight above an opening, such as a door, window, or nonstructural panel. If the first floor is a concrete slab, it is described on the foundation plans and details. The second and higher floors are described on framing plans, as is the roof frame. Many buildings have several floors that are framed alike. In this case a note might indicate that a framing plan is typical.

Framing plans for structural steel are drawn on the structural grid coordinate system (see **Figure 39–3**). Beams are shown by a single-line symbol with an accompanying note to indicate the structural shape to be used. The lines indicating beams stop short of the symbol for the girder or column when the beam is framed into the supporting member and does not continue over it.




Figure 39-1. The column load must be centered on the footing.




Figure 39-2. Major parts of a building frame.




Figure 39-3. Structural coordinates are shown on the framing plans and floor plans.

The abbreviation *DO*, which stands for *ditto*, indicates that the specification for the first member in a series is to be repeated for all members. A number in parentheses at the end of the designation is used to indicate the elevation of the top of the member. This may be the elevation or the distance above or below the floor line (see **Figure 39-4**).

Joists are frequently *open-web steel joists*, sometimes called *bar joists* (see **Figure 39-5**). Bar joists are manufactured in H, J, and K series, depending on the grade of steel used and their strength requirements. K series are stronger than H series, and H series are stronger than J series. A bar joist designation includes a number to indicate depth, a letter to indicate strength

series, and a number to indicate chord size. For example, the designation 16H6 indicates a 16-inch-deep H series joist with number 6 chords.

The actual lengths of members are not shown on the general contract drawings. This information is shown on shop drawings that are drawn by the steel fabricator some time after the construction drawings are completed. It is an easy matter, however, to find the span of the member by looking at the framing plan. Connections are shown on details and sections.

Lintels are sometimes categorized as *loose steel*. In masonry construction, a steel lintel is placed above each opening to support the weight of the masonry above the opening (see **Figure 39-6**). These lintels are





Figure 39-4. Notations on the drawings indicate the relative elevations of beams.



Courtesy of Willis: Blueprint Reading for Commercial Construction, by Delmar Learning

Figure 39-5. Open-web steel joists (often called bar joists).

not attached to the steel building frame, which is why they are called loose steel. If there are several lintels alike, they are normally shown on the plans by a symbol and are then described more fully in a lintel schedule (see Figure 39-7).

Masonry Reinforcement

Masonry materials have great compressive strength. That is, they resist crushing quite well, but they do not have good tensile strength. The *mortar* in masonry joints is especially poor at resisting the forces that tend to pull it apart, such as a force against the side of a wall or a tendency for the wall to topple. Masonry joint reinforcement is done by embedding specially made welded-wire

reinforcement in the joints (see Figure 39-8). Greater strength can be achieved by building the masonry wall with reinforcement bars in the cores of the masonry units, then filling those cores with concrete. Concrete used for this purpose is called *grout*. Reinforcing steel is also embedded in masonry *walls* to tie structural elements together. For example, it is quite common for rebars to protrude out of the foundation and into the exterior masonry walls. The strength of a masonry wall can be increased considerably by the use of bond beams (see Figure 39-9). A *bond beam* is made by placing a course of U-shaped masonry units at the top of the wall. Reinforcing steel is placed in the channel formed by the U shape; then the channel is filled with grout. The result is a reinforced beam at the top of the wall.




Figure 39-6. A lintel may be considered loose steel if it is not attached to the frame.

LINTEL SCHEDULE				
MARK	MATERIAL	TYPE	MAS. OPNG	REMARKS
L1	WT 8 x 13	┴	SEE ARCH.	ATTACH ONE END TO COL. SEE 1/5200
L2	WT 8 x 13	┴	"	END BEARING BOTH ENDS
L3	WT 8 x 13	┴	"	CONTINUOUS W/CENTER SUPPORT ON T.S. 4 x 4
L4	WT 4 x 9	┴	"	AT ALL BELOW WINDOW UNIT VENTILATOR OPENINGS
L5	(2) $\frac{1}{4}$ " ϕ 6 x 4 x $\frac{5}{16}$ W/ $\frac{1}{4}$ " x 9 $\frac{1}{2}$ CONT. BOTH FL	┴┴	"	LINTEL IN FIRE WALL WELD BOT. FL TO ANGLES.
L6	(2) $\frac{1}{4}$ " ϕ 6 x 4 x $\frac{5}{16}$	JL	"	IN EXIST. BLDG. WALL
L7	(3) $\frac{1}{4}$ " ϕ 4 x 3 $\frac{1}{2}$ x $\frac{5}{16}$	JJL	"	AT CAFETERIA HVAC UNIT WALL OPENINGS COORDINATE WITH G-7/H3 AND A103 (2-LOCATIONS)

Figure 39-7. Lintel schedule.




Figure 39–8. Masonry joint reinforcement.




Figure 39–9. A bond beam is used to strengthen the top of the wall.



USING WHAT YOU LEARNED

The structural drawings for the School Addition in your textbook packet contain information about how the new addition is to be anchored to the existing building. If this anchoring is not done correctly, the risk that the buildings will separate over time increases. At the ground level, there will be a ramp down from the existing building to the addition. How is that ramp anchored to the existing building?

Being at the ground level, the ramp is shown on the Foundation Plan on Sheet S100. Section View 11/S101 shows a cross section of the ramp. At the far right of that section view is a callout that reads **#4 × 1'-6" DOWELS @12" O.C. DRILLED & GROUTED INTO EXIST. SLAB 6.**

Assignment

Refer to the drawings of the School Addition in your textbook packet to complete this assignment.

1. What are the dimensions of the footing for the northwestern most column?
2. What is the width and depth of the footing at the west end of the addition?
3. What is the elevation of the top of the floor in the elevator pit?
4. How many lineal feet of #5 reinforcement bars are needed for the footing under the east wall of the addition?
5. What size and kind of material is used to prevent the foundation wall from moving on the footings? How much of this material is needed for the west end of the addition?
6. How many pieces of what size reinforcing steel are to be used in the footing for the column between the entrances to classrooms 103 and 104?
7. How closely is the vertical reinforcement spaced in a typical section of the foundation wall?
8. What is the overall length of each piece of rebar used to secure the interior masonry partitions to the concrete slab?
9. What is the spacing of the dowels used to secure the exterior masonry walls to the foundation?
10. Describe how the corridor walls are secured to the columns.
11. How many pieces of W18 × 50 steel are used in the construction of the addition?
12. What size and shape structural steel supports the north ends of the floor joists under classroom 203?
13. What size and shape structural steel supports the ends of the girder in the second floor at the front (side with the door) of the elevator shaft?
14. What is the nominal depth of the joist in the second floor corridor?
15. What is the elevation of the top of the second floor girder between D5 and D6, relative to the second finish floor elevation of 110'-3"?
16. What is the shape and size of the member that supports the masonry above the windows in classroom 108?

UNIT 40

HVAC & Plumbing Drawings

Objectives

After completing this unit, you will be able to perform the following tasks:

- Identify and briefly describe the major pieces of HVAC equipment to be used in a building.
- List the sizes of pipes and fittings shown on mechanical plans, and explain the major functions of each.
- Describe the sizes and shapes of air-handling ducts shown on mechanical drawings.

Heating, ventilating, air conditioning, and plumbing are often referred to as the mechanical systems. For residential construction, these systems are rarely covered in depth with drawings. The subcontractors who will install these systems can do most of the work with the very minimal information shown on the floor plans. If additional drawings are necessary, those subcontractors will prepare their own. In commercial construction, however, such as the school addition, the mechanical systems are more complex and the drawing set usually includes drawings for *HVAC (heating, ventilating, and air conditioning)* and for plumbing. The original School Addition drawings include two plumbing drawings, identified by the P prefix in the sheet number; and five HVAC drawings, identified by an H prefix. The School Addition drawings included in your textbook contain only one plumbing drawing and one HVAC drawing.

Heating, Ventilating, and Air Conditioning Plans

The HVAC system for a building larger than a single-family house is designed by an engineer who specializes in this work. The drawings for this work are usually drawn on a basic outline of the floor plan for the building. This allows the mechanical drawings to show where HVAC and plumbing equipment is located in relation to rooms, walls, floors, and so on. The coordination of structural, mechanical, and electrical work is often an issue of some concern on construction projects, and so it is important to understand where and how pipes will pass between beams or through walls.

Most commercial buildings are heated by burning fuel (natural gas or fuel oil) and distributing the resulting heat in the form of warm air, hot water, or steam. Warm-air heating systems require ducts throughout the building to carry the warm air to the occupied spaces and to return the cool air to the source. A warm-air system has the advantage of allowing for inexpensive air conditioning. The same ducts can be used to distribute either warm air in winter or cool air in summer. The ducts, however, require much more space in ceilings and walls and are harder to route through and between structural elements than are pipes. When hot water or steam is used to transport the heat to the occupied space, two pipes are required: one to supply the hot water or steam and one to return the cooler medium to its source. The basic type of system is readily apparent to anyone looking at the HVAC plans. The plans for an air-handling system include ductwork. The plans for a hydronic system include more pipes and fittings.

Unit Ventilators

At first look, the heating plans for the School Addition might appear foreign and difficult to understand, but like most of the drawings you have studied before this point, these drawings are easy to understand when taken one step at a time. Notice that each of the rooms in the addition has a rectangle on the outside wall with a callout of UV-1, UV-2, or something similar. These indicate that this building is heated by unit ventilators. **Figure 40–1** is the Schedule of Unit Ventilators. (In the actual drawing package it was H-7 on Sheet H-4.) A *unit ventilator* is a unit that combines a means of mixing room air and outside air to ventilate the room while also warming it. The warmth is provided by the hot water that is piped in from the boiler.

Figure 40–2 explains the principles of a unit ventilator. The heating controls include a function that controls the balance of recirculated inside air and fresh outside air. During the day, when the building is in use, the damper is opened to allow more fresh air to be circulated through the room. At night, the damper is closed, so that less cool air enters the room, resulting in an energy savings. The amount of air that is drawn in from the outside when the dampers are closed as much as possible is indicated on the drawings and on the schedule as *CFM* (*cubic feet per minute*). Other information on the Schedule of Unit Ventilators describes

such things as the total amount of air that passes through the unit, the water temperature intended by the designer, and the speed of the fan.

This school does not include air conditioning. If it did, the unit ventilators would be supplied with cold water when cooling is called for. The same system of balancing inside and outside air would be used for energy conservation and fresh air, but instead of passing the air over heated pipes, it would be passed over cold pipes. The Schedule of Unit Ventilators would include information for air conditioning.

The unit ventilators are only a few feet long; yet the plans show a continuous string of equipment of some sort along the exterior walls of the classrooms. Although not labeled anywhere on the plans, the equipment is bookcases; the Construction Notes refer to them. The manufacturers of unit ventilators also manufacture bookcases and filler pieces that are designed to fit with the ventilators and fill the rest of the wall space. These bookcases have a false back, with space for pipes to and from the ventilators.

In some spaces, such as stairways and storage closets, the heaters are not labeled as *UV* (*unit ventilators*). These are *cabinet unit heaters* (*CUH*) that mount on the surface of the wall and do not have ventilation capability and *fan coil units* (*FCU*) that are intended to provide more heat than ventilation. **Figure 40–3** shows the schedules for the units marked as CUH, UH, and FCU.

UNIT VENTILATOR SCHEDULE												H-7
MARK	MAKE	MODEL	FAN				V/PH/HZ	HEATING				
			TOT CFM	MIN O.A.	RPM	HP		HOT WATER				
								EAT	EWT	GPM	MBH	ΔP
UV-1	AAF	AV-4000	1000	270	650	1/8	120/1/80	50	180	2.0	36	0.99
UV-2	AAF	AV-5000	1250	270	650	1/8	120/1/60	50	180	2.0	42	1.27
UV-3	AAF	AV-3000	750	250	650	1/8	120/1/60	40	180	2.0	28	0.79
UV-4	AAF	AH-3000	750	270	650	1/8	120/1/60	40	180	2.0	36	0.79
UV-5	AAF	AH-3000	750	270		1/2	120/1/60	40	180	2.0	36	0.79

TOT CFM total cubic feet per minute through the unit
 MIN O.A. minimum outside airflow into the unit
 RPM revolutions per minute of the fan
 HP fan motor horsepower
 V/PH/HZ fan motor volts, phase rating (1 or 3), and hertz (frequency or cycle)
 EAT entering air temperature

EWT entering water temperature
 GPM gallons per minute of water through the unit
 MBH thousands of BTUs per hour (a measure of heat output)
 ΔP delta pressure (drop in water pressure through the system)

Figure 40–1. Unit ventilator schedule.




Figure 40-2. Operation of a unit ventilator.

MARK	MAKE	MODEL	STYLE & ARRANGEMENT	STEAM		WATER				CFM	RPM	EAT	MBH	ELECTRICAL	
				PSIG	LB/HR	EWT	Δ T	GPM	Δ P"					V/φ/HZ	HP
CUH-1	STERLING	RWI-1130-04	RECESSED WALL, INVERTER			180	34	2.0	0.44	420	1050	60	33.8	120/1/60	1/10

CABINET UNIT HEATER SCHEDULE

MARK	MAKE	MODEL	TYPE	WATER			MBH	CFM	EAT	LAT	MOTOR		
				ENT.	GFM	Δ P					RPM	H.P.	V/φ/HZ
UH-1	MODINE	HS-18L	HORIZONTAL	180	1.1	0.4	9.4	364	60	84	1550	16MHP	120/1/60

UNIT HEATER SCHEDULE

MARK	MAKE	MODEL	CFM & TOT./F.A.	EXT. S.P.	ELECTRICAL		HEATING				
					WATTS	VOLTS/PH/HZ	EAT	EWT	GPM	MBH	Δ P
FCU-1	AAF	SFG-TFA-3000	350	0	110	120/1/60	50	180	1.0	18	0.1

FAN COIL UNIT SCHEDULE

Cataldo, Waters, and Griffith Architects, P.C.

Figure 40-3. Schedules of cabinet unit heaters, unit heaters, and fan cabinet unit heaters.

Heating Piping

Once the basic type of heating system has been determined, the next step is to understand the piping that carries water to and from the heating units. It is easy to spot the pipes on the heating plan. A solid line indicates supply pipes, and a dashed line indicates return pipes. Pipe sizes are indicated by callouts throughout the plans. Fittings such as valves, elbows, and tees are represented by symbols. **Figure 40-4** shows the most common symbols for mechanical systems. There are standard piping symbols, but each drafter uses a few special representations of his or her own, so a symbol legend is included with the drawings.

Pipes are easier than ducts to coordinate with structural elements because the direction of the pipe can be changed easily and frequently. Pipes might run horizontally in a ceiling for some distance, then loop around a column and drop down to a unit ventilator. It is not practical to show the layout of all pipes with separate plan and riser views. The common method for showing pipes where both horizontal and vertical layout is involved is to use isometric schematics. Plumbing isometrics are discussed in Unit 35. Sheet H-1 of the School Addition drawings combines plan views and isometric schematics. The long runs of pipes are shown in plan view to indicate where the pipes are in relation to the walls. Where the pipes need to drop down from the ceiling to the level of the ventilators, they are shown in isometric views (see **Figure 40-5**).

For the sake of explanation, the following discussion traces the hot-water supply piping (broken line) in room 109, the storage room on the first floor, E-7 on Sheet H-1. Most of what is discussed here is also shown in **Figure 40-5**, but we will start closer to the center of the building, where the branch tees to the right (north) off the main supply running from top to bottom of the drawing. See the symbol legend A-11 on Sheet H-1 to interpret the symbols as you trace the piping. It is recommended that you use a colored pencil to trace the piping as you read this.

The first thing we encounter is a valve, an elbow toward the top of the drawing, and then another elbow back to the right. Construction Note 13 indicates that the pipes pass through a structural steel member. The line is broken for clarity through the area where ductwork is shown that would make reading the piping drawing difficult. Pick the line up again in the storage

room 109. Next we come to a tee where the pipe drops down to the level of the unit ventilator. If we continued on to the right or north, we would come to Construction Note 2, which tells us that the symbol indicates a riser to the second floor. The riser is not shown in the wall, where it would actually be positioned, because doing so would bury the riser symbol in the wall with material symbols and other lines. The pipe going down is actually shown at an angle up and to the right. This is the isometric portion of the drawing. At the level of the unit ventilators, the pipes are arranged in a special way to eliminate noises that might result from expansion and contraction as the water temperature changes (see **Figure 40-6**). The ends of the pipes are shown with break lines, which indicate that the pipes actually continue to their obvious destinations: fittings on the unit ventilators.

Air-Handling Equipment

The unit ventilators introduce fresh air into the School Addition. A separate ventilation system removes stale air from each room of the school. All the rooms in the addition except the smallest closets and the stairways are provided with a system of ducts and a fan to ensure air circulation. A *louvered grille* in the room receives the air and channels it into a duct that carries it to the roof, where a fan exhausts it to the outside.

Figure 40-7 explains the designations for outlet and inlet grilles. The ducts that carry the air to the roof are shown by their outlines and do not indicate their sizes. A square or rectangle with a diagonal line through it indicates where the duct rises to the next floor or the roof. Several notes indicate that ducts rise up to EF-# on the roof. EF is an abbreviation for exhaust fan. The number indicates which of the several exhaust fans on the roof the duct is connected to. Some of the exhaust fans occupy several square feet of space on the roof, so they cannot be placed too close together.

Trace the flow of air as it is exhausted from the janitor's closet on the first floor. The path starts with a louver marked RB (return)—8 × 6 (cross-sectional size in inches)—75 (cubic-feet-per-minute nominal airflow). Between the janitor's closet and the storage room, the air enters a 6 × 6 duct, which goes up through a chase (space between two walls) to the second floor. At the second floor it is joined by the exhaust air from the second floor janitor's closet. On the Second Floor Plan

MECHANICAL SYMBOLS		MECHANICAL SYMBOLS (CONTINUED)	
DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL
RECTANGULAR OR SQUARE SUPPLY DUCT TURNED UP		ELECTRIC OPERATED DAMPER	
RECTANGULAR OR SQUARE SUPPLY DUCT TURNED DOWN		FIRE DAMPER	
RECTANGULAR OR SQUARE EXHAUST DUCT TURNED UP		SMOKE DAMPER	
RECTANGULAR OR SQUARE EXHAUST DUCT TURNED DOWN		ELECTRIC HEATER IN DUCT	
ROUND SUPPLY DUCT TURNED UP		SUPPLY OUTLET WITH SIZE AND AIR QUANTITY SHOWN	
ROUND SUPPLY DUCT TURNED DOWN		DEFLECTOR IN DUCT BEHIND REGISTER OR GRILLE (ARROW INDICATES DIRECTION OF FLOW)	
RECTANGULAR CEILING DIFFUSER		TURNING VANES IN A SQUARE THROAT ELBOW	
ROUND CEILING DIFFUSER		TURNING VANES IN A ROUND THROAT ELBOW	
FLEXIBLE CONNECTION		PLAN VIEW OF TRANSITION	
TRANSITION: FOT = FLAT ON TOP		OFF-SET UP IN DIRECTION OF ARROW	

DUCT DIMENSIONS—FIRST FIGURE IS THE SIDE OF DUCT SHOWN (12 X 10)

Figure 40-4. Mechanical and plumbing symbols.

MECHANICAL SYMBOLS (CONTINUED)	
DESCRIPTION	SYMBOL
ACCOUSTICAL LINING INSIDE INSULATION	
BRANCH TAP IN DUCT	
SPLITTER FITTING WITH DAMPER	
VOLUME-DAMPER	
BACKDRAFT DAMPER	
ACCESS DOOR IN DUCT 10" X 10" SIZE	
PNEUMATIC OPERATED DAMPER	
THREE-WAY VALVE	
PRESSURE REDUCING VALVE	
PRESSURE RELIEF VALVE OR SAFETY VALVE	
SOLENOID VALVE	
PIPE TURNED UP (ELBOW)	
PIPE TURNED DOWN (ELBOW)	
TEE (OUTLET UP)	
TEE (OUTLET DOWN)	

MECHANICAL SYMBOLS (CONTINUED)	
DESCRIPTION	SYMBOL
BACKFLOW PREVENTER	
UNION	
REDUCER	
CHECK VALVE	
GATE VALVE	
GLOBE VALVE	
BALL VALVE	
BUTTERFLY VALVE	
DIAPHRAGM VALVE	
ANGLE GATE VALVE	
ANGLE GLOBE VALVE	
PLUG VALVE	
LOW PRESSURE STEAM	
LOW PRESSURE CONDENSATE	
PUMPED CONDENSATE	
FUEL OIL SUPPLY	
FUEL OIL RETURN	
HOT WATER SUPPLY	
HOT WATER RETURN	
COMPRESSED AIR	
REFRIGERANT SUCTION	

Figure 40-4. (Continues)

MECHANICAL SYMBOLS (CONTINUED)

DESCRIPTION	SYMBOL
REFRIGERANT LIQUID	RL
REFRIGERANT HOT GAS	RHG
CONDENSATE DRAIN	CD
FUEL GAS	G
CHILLED WATER SUPPLY	CWS
CHILLED WATER RETURN	CWR

PLUMBING SYMBOLS

DESCRIPTION	SYMBOL
METER	M
SPRINKLER PIPING	s
SPRINKLER HEAD	
FLOOR DRAIN	F.D.
CLEAN-OUT	C.O.
TUB	
TANK-TYPE WATER CLOSET	
WALL-MOUNTED LAVATORY	
URINAL	
SHOWER	
WATER HEATER	
MANHOLE	

PLUMBING SYMBOLS (CONTINUED)


DESCRIPTION	SYMBOL
WALL HYDRANT	
YARD HYDRANT	
FLUSH VALUE WATER CLOSET	
COUNTER-TYPE LAVATORY	
KITCHEN SINK (DOUBLE BOWL)	
SOIL, WASTE OR DRAIN LINE	
PLUMBING VENT LINE	
COLD WATER (DOMESTIC)	
HOT WATER (DOMESTIC)	
HOT WATER RETURN (DOMESTIC)	
FIRE LINE	
FUEL GAS LINE	
ACID WASTE LINE	
VACUUM LINE	
COMPRESSED AIR LINE	
BACKFLOW PREVENTER	
GATE VALVE	
GLOBE VALVE	
CHECK VALVE (ARROW INDICATES DIRECTION OF FLOW)	

Figure 40-4. (Continued)

PLUMBING PIPE SYMBOLS (CONTINUED)

DESCRIPTION	SYMBOL
UNION	
PIPE TURNED DOWN	
PIPE TURNED UP	
TEE OUTLET UP	
TEE OUTLET DOWN	
TEE OUTLET TO SIDE	
REDUCER	
PIPE SLEEVE	

Figure 40-4. (Continued)



Cataldo, Waters, and Griffith Architects, P.C.

Figure 40-5. This isometric drawing shows how the heating pipes drop down from the ceiling to the level of the ventilators.




Figure 40-6. Noises are eliminated by allowing pipes to expand and contract.

Notice that the *storm drain* and the *sanitary drain* are separate systems. The storm drain only needs to carry rainwater away from the building. The sanitary drain must connect to a sewer or septic system. Although the storm drain and the sanitary drain pipes cross near the janitor's closet on the first floor, they are not connected.

In the region where this building was constructed, drainage pipes outside the building lines are installed by the site contractor, not the plumbing contractor. Therefore, the plumbing drawings only show the storm drain and sanitary drain to a point 5'-0" outside the building lines. A note where each line passes through the building wall indicates the *invert elevation* (elevation of the bottom of the inside of the pipe).

The hot- and cold-water piping is similar to that found in homes, except that the hot water is a two-pipe system. A return hot-water pipe allows the hot water to circulate continuously, ensuring that hot water is readily available at the point of use. The hot-water supply and hot-water return can be distinguished from each other by the number of short dashes in the symbol. These are explained on the symbol legend in the drawing packet. The hot-water return, which is usually smaller than the supply, maintains circulation to a point close to where most of the hot water will be used. It is often not practical to continue a hot-water return pipe to every fixture in an area with several fixtures like the School Addition toilet rooms. **Figure 40-9** shows riser


diagrams for the fixture connections in the School Addition. (A riser diagram shows the vertical arrangement of the piping.) Notice that there is no hot-water return shown on these diagrams, because the return is connected to the supply before the supply reaches the first fixture.

A plumbing riser diagram is only used to indicate design intent and does not indicate a piping route. The sizes indicated by the engineer are minimum sizes. Company preferences and local codes can dictate that larger sizes be used. Notice that Riser 1 and Riser 4 in **Figure 40-9** are identical. This does not mean that they will always be installed the same way. The notes on Riser 1 are different from the notes on Riser 4. The notes on both risers are relevant for Risers 1 and 4, and the vacuum breakers required on S-1 in Riser 1 are also required on S-1 fixtures in Riser 4. The note to route all piping in the casework in Riser 4 is also relevant for the piping in Riser 1.

It is important for plumbers to know and comply with local codes. In Riser 3, the vent serving MB-1 is offset 90° below the fixture. That is an illegal installation by most codes, and the plumber would install the *vent pipe* in accordance with local codes and not use the riser diagram as a guide for routing the pipe. Where the pipes seem to connect but are actually different piping systems, you can outline the pipe route with different color pencils to clarify the different piping systems.

CONSTRUCTION NOTES:

- ① NOT USED
- ② SEE FLOOR PLAN FOR CONTINUATION.
- ③ KITCHENETTE BY G.C. ROUGH-IN AS INDICATED AND REQUIRED.



RISER DIAGRAMS

D-14

Cataldo, Waters, and Griffith Architects, P.C.

Figure 40-9. Riser diagrams for school fixtures.



USING WHAT YOU LEARNED

Even for workers not directly involved in installing the HVAC system in a building, it is useful to understand where piping, ductwork, and other mechanical equipment will be installed. For example, iron workers who install the structural steel need to know where pipes run through bar joists or around steel beams. As an exercise in tracing piping, list all the pipe sizes through which hot water passes from the time it enters the School Addition until it reaches the unit ventilator in Classroom 104. The easiest way to do this is to start at the unit ventilator and work back to where the piping enters the building. Find the Unit Ventilator (UV-2) in Classroom 104 on the First Floor Plan E-7. There are actually two UVs in this classroom, but both have the same size supply pipes. The pipes at this point are near the top of the classroom and labeled as $\frac{3}{4}$ ". Follow the pipes to where they turn east (notice that the North Arrow point to the right) to follow the hall toward the existing building. At this point, they are labeled as 1" pipes. After they pass the tees to Classroom 107, they are $1\frac{1}{4}$ " pipes. Beyond the tees, entering Classroom 103, they are $1\frac{1}{2}$ " pipes, and, after the next tees, entering storage room 101, they are 2". They are 2" all the way to where they enter the addition. So, in the order the water passes through the pipes, they are 2", $1\frac{1}{2}$ ", $1\frac{1}{4}$ ", 1", and $\frac{3}{4}$ ".

Assignment

Refer to the drawings of the School Addition in your textbook packet to complete this assignment.

1. How many unit ventilators are shown on the first floor?
2. How is the machinery room on the first floor behind the elevator heated?
3. List in order the sizes of pipe that the water flows through, starting from the point where the water enters the addition to get to the heating unit in Classroom 210 and then back to the point where it leaves the addition.
4. What are the dimensions of the grille where stale air is vented out of Classroom 209?
5. List in order the sizes of the ductwork that exhaust air passes through from the point where the air leaves Classroom 209 until it is outside the building.
6. List in order the sizes of the ductwork that exhaust air passes through from the point where the air leaves the girls' toilet room on the first floor until it exits the building.
7. How many gallons per minute of water are expected to flow through the heating unit in stair #2?
8. Why are two roof drains shown on the First Floor Plumbing Plan of this two-story building?
9. What is designated as EWC-1 on the plumbing plans?
10. What is the vertical distance between the storm drain and the sanitary drain at the point where they cross?
11. What is the diameter of the pipe that is used for the storm drain where it goes from the second floor to the first floor?
12. What size pipe is used for the domestic hot-water return line?
13. Where does the domestic hot-water return line tee out of the domestic hot-water supply line?
14. Where would you shut off the cold-water supply to the kitchenette unit in Room 101 without shutting off the cold water to the toilet rooms on the same floor?

UNIT 41

Electrical Drawings

Objectives

After completing this unit, you will be able to perform the following tasks:

- Explain the information found on a lighting plan.
- List the equipment served by an individual branch circuit using electrical plans, riser drawings, and schedules.
- Explain the information on a schematic diagram.

Electrical Drawings

Electrical drawings deal predominantly with circuits. Knowledge and understanding of the basic circuits used in buildings is necessary for those working with and interpreting electrical drawings. The four basic methods of showing electrical circuits are:

1. Plan views
2. Single-line diagrams
3. Riser diagrams
4. Schematic diagrams

Plan Views

The electrical floor plan of a building shows all the exterior walls, interior partitions, windows, doors, stairs, cabinets, and so on along with the location of the electrical items and their circuitry.

Power Circuits

The *power circuit* electrical floor plan shows electrical outlets and devices and includes duplex outlets, specialty outlets, telephone, fire alarm, and the like. The conventional method of showing power circuits is to use long dash lines when specified to be installed in the slab or underground and to use solid lines when concealed in ceilings and walls. Short dash lines indicate exposed wiring. Solid lines are often used in commercial installations when the raceway (conduit) is to be exposed (surface mounted). Slash marks through the circuit lines are used to indicate the number of conductors. Full slash marks are the circuit conductors, a longer full slash is the neutral, and half slash marks are the ground wires. When only two wires are required, no slash marks are used. The typical wire size for commercial construction is No. 12 AWG (American wire gauge). The arrows indicate “home runs” to the designated panel. The panel and circuit number designations are adjacent to the arrowheads. **Figure 41–1** lists the typical circuiting symbols. The electrical installer will normally group home runs in a raceway with combinations similar to the following:

- Three-phase systems with three circuit wires and a common neutral in a raceway
- Single-phase systems with two circuit wires and a common neutral in a raceway




Figure 41-1. Circuiting symbols.

Note: To reduce the harmonic problems caused by solid-state devices (nonlinear loads), many electrical designers are requiring separate neutrals with each phase conductor.

Some equipment, such as television, fire alarm, clock, PA, and sound, might not be connected with wiring lines on the plan. This indicates that wiring for that equipment is not part of the general circuit wiring and is probably not to be fed through the same panels as

the rest of the electrical equipment. For example, on the School Addition the PA system and the clocks are fed from the sound system console and do not involve the general circuit wiring.

Lighting Circuits

There is usually a *lighting circuit* electrical floor plan for each level or major space within a building. This floor plan shows light fixtures, emergency lighting, security lighting, and special lighting control (photo cell, motion detector, etc.). Typically included is a reflected ceiling plan (see **Figure 41-2**). That is, it is a plan view but shows what is on the ceiling as though it were reflected onto the floor plan (see **Figure 41-2**). The reflected ceiling plan shows each light fixture with a circle, square, or rectangle that approximates the shape of the fixture. The lighting circuitry on the School Addition is shown with three types of wiring circuit lines, solid for unswitched, dotted for switched, and line-dash-line for the motion sensor circuits. The conventional method of showing lighting circuits is the same as previously explained in the paragraph above on power circuits.

Motion sensors are an interesting feature of the lighting design for the School Addition. The motion sensors are shown as small circles containing the letter *M*. A motion sensor detects any movement in the area of the sensor, so that in a room controlled by a motion sensor, if there is no movement in the room for a period of time, the sensor opens its contacts, like turning a switch off. A motion detector can be used together with a switch so that the lights are controlled normally by the switch. But if someone forgets to turn the lights off, the motion detector will.

A low-voltage lighting control system requires a *relay* that is activated by the light switch. The relay opens or closes the higher-voltage fixture (see **Figure 41-3**). The relays on the School Addition are indicated by the letter *R* in a small square. Notice that every lighting switch is connected to a relay.

Symbols

Electrical symbols are used to simplify the drafting and later the interpreting of the drawings. Electrical symbols are *not standardized* throughout the industry. Most drawings have a symbol legend or list. You must be knowledgeable of the symbols specifically used on each project since designers modify basic symbols to




Figure 41-2. Reflected ceiling plan.

suit their own needs. Many symbols are similar (circle, square, etc.). The addition of a line, dot, shading, letters, numbers, and so forth gives the specific meaning to the symbol. Learning the basic form of the various symbols is the best starting point in developing the ability to interpret the drawings and the unrelated symbol meanings. **Figure 41-4** shows common electrical symbols and abbreviations.

The School Addition drawing E-1, symbol legend A-4, contains an electrical symbol list for the project. From the symbol list, it can be seen that there are duplex receptacles, switches, telephone outlets, special-purpose outlets, and fire alarm devices mounted at various heights. Then there is the General Note in the symbol legend that specifies that all

mounting heights are to be verified and “modified as directed.” This is an example of why the installer must become familiar with the drawings and specifications far in advance of the scheduled time for the installation. The installer must request clarification or direction and give the designers reasonable time to clarify the questionable specified instructions.

Single-Line Diagrams

The electrical service *single-line diagram* on the School Addition is shown on drawing E-2, Single-Line Diagram E-17. The electric power is brought into the school by way of the *service entrance section (SES)* The note “coordinate with the local utility requirements prior to rough-in” indicates that the electrical contractor




Figure 41-3. A relay allows a low-voltage circuit to start and stop a higher-voltage circuit.

is to furnish and install the three 4-inch conduits and that the utility company wants to inspect the conduit installation prior to backfilling the trench where the conduits are installed; however, this should be verified at a preconstruction meeting with the utility company. There are times when an electrical service, or electrical distribution raceway, would require being concrete encased for protection. This type of concrete-encased underground raceway system is called a *duct bank* (see **Figure 41-5**).

The note does not specifically indicate who furnishes and installs the utility feeders in the three 4-inch conduits. This could be an expensive item and should be clarified with the utility company prior to estimating and bidding the project.

To comply with the *National Electrical Code® (NEC®)*, the service entrance section may have up to, but must not exceed, six main disconnecting units (switches or circuit breakers). Four main fused switches are shown in the existing portion of the single-line drawing. Note that this single-line drawing shows only a portion of the complete existing service entrance section. The service entrance section indicates that it is located outside by the NEMA 3R ENCLOSURE. National Electric Manufacturers Association (NEMA) generates specifications that are recognized as design standards for electrical boxes, devices, and equipment. NEMA 3R is a rain-tight designation. The new portion of the single-line drawing shows the electrical distribution to be installed in this School Addition.

Electrical Reference Symbols







ELECTRICAL ABBREVIATIONS

(Apply only when adjacent to an electrical symbol.)

Central Switch Panel	CSP
Dimmer Control Panel	DCP
Dust Tight	DT
Emergency Switch Panel	ESP
Empty	MT
Explosion Proof	EP
Grounded	G
Night Light	NL
Pull Chain	PC
Rain Tight	RT
Recessed	R
Transfer	XFER
Transformer	XFRMR
Vapor Tight	VT
Water Tight	WT
Weather Proof	WP

ELECTRICAL SYMBOLS

Switch Outlets	
Single-Pole Switch	S
Double-Pole Switch	S ₂
Three-Way Switch	S ₃
Four-Way Switch	S ₄
Key-Operated Switch	S _K

Switch and Fusestat Holder	SFH
Switch and Pilot Lamp	Sp
Fan Switch	SF
Switch for Low-Voltage Switching System	S _L
Master Switch for Low-Voltage Switching System	S _{LM}
Switch and Single Receptacle	 S
Switch and Duplex Receptacle	 S
Door Switch	S _D
Time Switch	S _T
Momentary Contact Switch	S _{MC}
Ceiling Pull Switch	 S
“Hand-Off-Auto” Control Switch	 HOA
Multi-Speed Control Switch	 M
Push Button	

Receptacle Outlets

Where weather proof, explosion proof, or other specific types of devices are to be required, use the upper-case subscript letters. For example, weather proof single or duplex receptacles would have the uppercase WP subscript letters noted alongside of the symbol. All outlets should be grounded.





Single Receptacle Outlet	
Duplex Receptacle Outlet	
Triplex Receptacle Outlet	
Quadruplex Receptacle Outlet	

Figure 41-4. Recommended electrical symbols.




Figure 41-4. (Continues)




Figure 41-4. (Continued)




Figure 41-4. (Continues)




Figure 41-4. (Continued)




Figure 41-5. Duct bank system.

The feeders for the new elevator, electrical panels L10 and L11, are fed from existing panel MDP. These new electrical loads are:

1. 60-amp circuit breaker with four #4 AWG, one #10 ground, and one #10 isolated ground in a 1¼-inch conduit feeding the elevator
2. 100-amp circuit breaker with four #1 AWG and one #6 ground in a 1½-inch conduit feeding panel L11
3. 100-amp circuit breaker with four #1 AWG and one #6 ground in a 1½-inch conduit feeding panel L10

A complete building electrical floor plan is not a part of the School Addition drawings, and the existing electrical distribution plan on drawing E-2 shows only a portion of the total electrical distribution section. This required notes 6, 7, and 8 to be added to drawing E-2, Single-Line Diagram E-17, giving the contractor the lengths of the feeders for the elevator, panels L10 and L11, which are to be included in this School Addition. In a typical design, a complete building electrical plan is provided indicating the locations of all existing and new electrical equipment. The feeder length would be determined from that drawing.

Riser Diagrams

A *riser diagram* is so named because it usually shows the path of wiring or raceway from one level of a building to another and because the wiring rises from one floor to the next. A riser diagram does not give information about where equipment is to be located in a room or area. Riser

diagrams are used because they are particularly easy to understand and do not require much explanation.

A *power riser diagram* (see **Figure 41-6**) shows a typical building's electrical service and related components. This figure is not the same electrical service as the School Addition Single-Line Diagram, E-17, on drawing E-2, but comparing the two diagrams shows how a power riser diagram greatly simplifies the interpretation of an installation drawing.

A *special riser diagram* is used for many systems that include:

1. Fire alarm
2. Security
3. Telephone
4. Clock
5. Signal
 - a. Bell
 - b. Call (nurse, emergency, etc.)
 - c. Water sprinkler

The *fire alarm riser diagram* (see **Figure 41-7**) shows the new School Addition fire alarm system with ¾-inch conduits to ramp area 113. The School Addition drawing E-2 shows three ¾-inch conduits with the note "Three (3) ¾-inch existing conduits from the Fire Alarm Control Panel (150 feet)." These three conduits are to be used for the School Addition fire alarm connection to the existing fire alarm system. The original fire alarm control panel was sized to accommodate this School Addition; however, you should verify that the existing





Figure 41-6. Typical riser diagram showing an overview of the building's electrical service and related components.

special systems (fire alarm, security, clock, etc.) will accommodate the additional requirements when adding to or modifying the existing system(s).

The *telephone riser diagram*, **Figure 41-8**, shows an existing 1¼-inch conduit, 150 feet in length, from ramp area 113 to the existing main telephone terminal cabinet. This conduit is to be extended to the telephone terminal board in room 102, First Floor Plan E-7, drawing E-2. The telephone riser diagram shows telephone conduit to be installed in the area above the suspended ceiling from the telephone terminal board to the outlet locations as shown on drawing E-2 and outlet detail A-11.

Schematic Diagrams

A schematic wiring diagram is a drawing that uses symbols and lines to show how the parts of an electrical assembly or unit are connected. A schematic does not necessarily show where parts are actually located, but it does explain how to make electrical connections. Several of the schematics with the School Addition show connections to wires labeled G, N, and H. These stand for *ground*, *neutral*, and *hot*. Schematics are commonly drawn for electrical equipment that involves internal wiring—everything from washing machines to computers. A basic motor control schematic (see



Cataldo, Waters, and Griffith Architects, P.C.

Figure 41-7. Fire alarm riser diagram for the school addition.




Figure 41–8. Telephone riser diagram for the school addition.

Figure 41–9) shows a three-phase power source (L1, L2, and L3) through the starter contacts (M) and the overloads (OL) powering the motor. The starter control is taken from phase L1 through a stop push button, a start push button paralleled with a latching contact M to the starter coil M, and finally through the normally closed

overload contacts back to phase L2. The connection label numbers (1, 2, 3, etc.), which are shown on the schematic, aid the electrician in troubleshooting. Several different labeling methods are used, but they all follow the same principles; so if you understand one method, you can understand the other methods.


Schedules

An electrical schedule is used to systematically list equipment, loads, devices, and information. Schedules organize the information in an easily understood form and can be a valuable method for communicating the design requirements to contractors and their installers.


The *fixture schedule* (see **Figure 41-10**) lists complete information about each fixture type shown on the

lighting plan. The following is a list of the kind of information that is usually shown on a fixture schedule:

- *Mark*—The label used to indicate a fixture type. The mark is written on or next to each fixture on the plan.
- *Make*—The identification of the manufacturer being used to establish the specific design requirements



SCHEMATIC



WIRING DIAGRAM

Figure 41-9. Schematic diagram and wiring diagram for a three-phase, AC magnetic, nonreversing motor starter.

MARK	MAKE	MODEL	VOLTS	WATTS	LAMP		REMARKS
					TYPE	NO./FIXT.	
A	STONCO	VWXL11GC	120	100	100WA19	1	CAST GUARD.
FA	WILLIAMS	1222-RWKA125	120	183	F32T8/SP30	3	SPLIT WIRE IN TANDEM PAIRS - WATTAGE IS FOR 2 FIXTURES W/ TOTAL OF 3 2-LAMP BALLASTS. ELECTRONIC BALLAST.
FA1	WILLIAMS	1222-RWKA125	120	92	F32T8/SP30	3	ELECTRONIC BALLAST.
FB	WILLIAMS	2922-KA	120	61	F32T8/SP30	2	ELECTRONIC BALLAST.
FC	KIRLIN	96617-45-46-61	120	36	PLC13W/27K	2	HPF BALLAST.
FC1	KIRLIN	96617-46-61-SM	120	36	PLC13W/27K	2	HPF BALLAST, SURFACE MOUNT; COLOR AS SELECTED
FD	WILLIAMS	8222	120	61	F32T8/SP30	2	ELECTRONIC BALLAST.
FE	WILLIAMS	1262-RWKA125	120	84	F17T8/SP30	4	ELECTRONIC BALLAST.
FF	TERON	EE26-P-H	120	36	PL13/27	2	HPF BALLAST.
FG	WILLIAMS	2122-IM	120	61	F32T8/SP30	2	ELECTRONIC BALLAST.
FH	WILLIAMS	EPG-R272RWKA-125	120	61	F32T8/SP30	2	TO MATCH EXISTING
M1	KIRLIN	SS-51277-24-43 (35W)-45-46-FR	120	40	35W HPS	1	HPF BALLAST.
M2	STONCO	PAR250LX	120	300	250W HPS	1	HPF BALLAST EQUIP WITH MOUNTING BRACKET ARM.
EXITS	LITHONIA	WLES SERIES	120	65	LED	1	SEE SHEET E-2 FOR LOC. ARROWS & MOUNTING AS IND EQUIP W/ BATTERY BACK-UP
EMERG. LGT. BATT. PACK	EXIDE	B200	120/12	150	H1212		
REMOTE LAMP	EXIDE	H1212	12	24	H1212	2	

Figure 41-10. Fixture schedule.

needed to aesthetically and functionally light the various rooms or areas.

- **Volts**—It is becoming increasingly common for light fixtures to be powered by up to 277/480 volts, while the *switches* might use only 24 volts (low-voltage lighting control) to protect the person using the switch.
- **Watts**—It is necessary to know the wattage of the lamps (bulbs) in each fixture, so that the space will have the amount of illumination intended by the electrical designer.
- **Lamp Type and Quantity**—Lamp manufacturers have similar systems of designating lamp characteristics (see **Figures 41-11, 41-12, and 41-13**).
- **Notes or Remarks**—This column is for information that does not clearly belong under the other headings.

The School Addition Fixture Schedule A-9—Floor Plans E-7 and E-14 on drawing E-1—shows type FA light fixture to be the light source for the classrooms. The School Addition fixture schedule, as shown in **Figure 41-10**, shows that the fixture is manufactured by Williams and the catalog number is 1222-RWKA125 with three F32T8/SP30 lamps rated at 120 volts with a 183-watt load. Also, the Remarks column indicates some special wiring and specific wiring and specific ballast-type requirements. The first and second floor Reflected Ceiling Plans, E-15 and E-16 on drawing E-7, indicate light fixture type FA to be a 2' × 4' light fixture mounted end to end.

Fifteen other light fixture types are shown on the fixture schedule and on the drawings and are identified by their corresponding mark or label. All are rated at 120 volts except one emergency battery-powered

remote lamp, rated at 12 volts. This information is typically given in the specifications but is more readily presented by a schedule.

A *panel schedule* identifies the panels by their mark or label. They are shown by this same designation on the electrical floor plan. The panel schedule for the School Addition lists each of the branch circuits served by a panel, the calculated load for that branch circuit, the voltage of that circuit, and the number of poles and trip rating for each circuit breaker. A panel schedule also might include:

- Type (surface or flush)
- Panel main buss amperes, volts, and phases
- Main circuit breaker/main lugs only
- Breaker frame sizes
- Items fed and/or remarks

On the lighting and power plans, we saw that each device is connected to a branch circuit identified by a panel number (label) and circuit number. Those numbers correspond with the numbers on the panel schedule.

When a commercial project has a kitchen, you should have a *kitchen equipment schedule*. If the drawings do not have one, it is very helpful to make one for the installer. The kitchen equipment schedule should include:

- Equipment number or designation
- Description of each equipment item
- The load in horsepower or kilowatts
- Volts
- Wire size
- Conduit size


How to Read Ordering Guide

	Ordering Abbreviation			Volts	Indicates aluminum base	Filament Code	Approx. Lumens	(M.O.L.) Max. Overall Length				
25	A-15	Med.	10125	25A15	115-125	120	Inside Frosted, Refrig.	B, C-9	1100	250	2 $\frac{3}{8}$	3 $\frac{1}{2}$
	A-17	Med.	10417	25A17/RS	75	120	I.F. Train, Rough Service	B, C-9	1000	228	2 $\frac{3}{8}$	3 $\frac{5}{8}$
	A-19	Med.	10443	25A	6	120	Inside Frosted	C, C-6	1000	357	2 $\frac{1}{2}$	3 $\frac{1}{16}$

Watts ↑
 Bulb ↑
 Base ↑
 One Item No. for each lamp
 25A17/RS
 25 — Lamp Nominal Wattage
 A — A shape
 17 — $\frac{17}{8}$ = 2 $\frac{1}{8}$ " Diameter
 RS — Rough Service
 Package Quantity ↑
 Description ↑
 Footnotes ↑
 Class C - denotes gas filled bulb.
 Class B - denotes vacuum lamp.
 Average Rated Hours Life ↑
 (L.C.L.) Light Center Length ↑

Incandescent Lamps


A Bulb designation consists of a letter(s) to indicate the shape and a figure(s) to indicate the approximate major diameter in eighths of an inch. Bulbs are measured through their greatest diameter, in eighths of an inch. Thus, a F-15 bulb is a flame shape, 15/8 of an inch or 1-7/8 inches in diameter.



Courtesy of Osram Sylvania Inc.

Figure 41–11. Incandescent lamp designations.

How to Read Ordering Guide

				Package Quantity	Description				
20	T-12	24"	Med. Bipin	22075	F20T12/D830	30	Designer "800" 3000K	9000	1350
				22018	F20T12/B	6	Blue ^{2B}	9000	550
				22250	F20T12/D30(ID)	6	Interior Design [®] , Designer [®] 3000K	9000	1300
				22078	F20T12/CW	30	Cool White	9000	1240
				22028	F20T12/GRO	12	GRO-LUX [®] 	9000	↑

↑	Watts	↑	Bulb	↑	One Item No. for each lamp	↑	Footnotes	↑	Average Rated Hours of Life	↑	Approx. Initial Lumens
			T-12 — Tubular 1 1/2" Diameter								

F	— Fluorescent
20	— Watts
T	— Tubular Shape
12	— 1 1/2" (1 1/2) Diameter
D830	— Phosphor Coating Color

FLUORESCENT LAMPS

The bulb shape and size of a fluorescent lamp are expressed by means of a code consisting of the letter "T" (which designates that the bulb is "tubular" in shape) followed by a number which expresses the diameter of the bulb in eighths of an inch. They vary in diameter from T-5 (5/8 inch) to T-17 (2 1/8 inches). In nominal overall length, fluorescent lamps range from 6 to 96 inches, which is always measured from back of lampholder to back of lampholder. For example, the actual overall length of the 40-watt rapid start T-12, 48 inch lamp is 47 3/4 inches. Circline lamps, which are circular, are available in four sizes: 6 1/2 inches, 8 inches, 12 inches and 16 inches outside diameter. There are also U shaped fluorescent types (Curvalume[™]) with T-8 and T-12 bulbs. U shaped types are measured for the distance between the ends. The overall length is measured from the face of the bases to the outside of the glass bend.

Courtesy of Orsam, Sylvania Inc.




Figure 41-12. Fluorescent lamp designs.

HOW TO READ PRODUCT INFORMATION - COMPACT FLUORESCENT

Nominal Wattage	Bulb	MOL (in)	(mm)	Base	Product Number	Ordering Abbreviation	NEMA Generic Designation	Pkg Qty	Avg Rated Life (hrs)	CCT (K)	CRI	Approx Lumens Initial @25°C/77°F (@35°C/95°F)	Mean	Symbols & Footnotes
13	Twist	4.6	117	Med	29116	CF13EL/MINITWIST		6	8000	3000	82	800	640	☑ ☑ 2,21,28, 36,63,64
26	D(T4)	6.8	173	G24D-3	20710	CF26DD/830/ECO	CFQ26W/G24D/30	50	10000	3000	82	1800	1548	☑ 2,21,28, 34,37
32	T(T4)	5.5	140	GX24Q-3	20885	CF32DT/E/IN/835/ECO	CFTR32W/GX24Q/35	50	10000	3500	82	2328 2400	2002 2064	☑ 2,21,28, 33,35,59
40	L(T5)	22.6	573	2G11	20586	FT40DL/841/RS/ECO	FT40W/2G11/RS/41	10	20000	4100	82	3150	2709	☑ 2,21,28

Nominal Wattage	Design wattage on reference ballast. Actual wattage dependent on ballast.
Bulb	Describes the shape of the bulb.
Base	Base designations for compact fluorescent lamps are the NEMA designations. Please see page 111 for base illustrations.
MOL	Maximum overall length. The actual length of the lamp measured from the bottom of the base to the top outside edge of the glass. In many cases, the bottom of the base is the bottom of the center post of the base of the lamp.
Symbols & Footnotes	Most symbols and footnotes that apply to a specific product will appear in this space. The explanations of the symbols and footnotes are at the end of the fluorescent section.
Ordering Abbreviation	A text description of the lamp. Please see below for several examples and explanations of some of the codes.
NEMA Generic Designation	Designation assigned by NEMA (National Electrical Manufacturers Association).
CCT	Correlated Color Temperature. The degree of "whiteness" of the light. Expressed in kelvins (K). Please see page 109 for more information.
CRI	Color Rendering Index. A numbering system for rating the relative color rendering quality of a light source compared to a standard. Please see page 109 for more information.
Initial & Mean Lumens	Initial lumens are measured when the lamp has been operating for 100 hours. Mean lumens are typically measured at 40% of the rated life of the lamp. Compact Fluorescent lamp lumens are measured at 25°C (77°F) and 35°C (95°F)

How to Read Ordering Abbreviations

CF26DD/830		CF32DT/E/IN/835/ECO		FT40DL/841/RS/ECO		CF20EL/830/MED/ECO	
CF	Compact Fluorescent	CF	Compact Fluorescent	FT	Fluorescent Twin	CF	Compact Fluorescent
26	Nominal lamp wattage	32	Nominal lamp wattage	40	Nominal lamp wattage	20	Nominal lamp wattage
DD	DULUX® Double	DT	DULUX Triple	DL	DULUX Long	EL	Electronic Lamp
8	82 CRI	E	Electronic or dimming operation	8	82 CRI	8	82 CRI
30	3000K CCT	IN	Amalgam	41	4100K CCT	30	3000K CCT
		8	82 CRI	RS	Rapid Start	MED	Medium screw base
		35	3500K CCT	ECO	ECOLOGIC	ECO	ECOLOGIC
		ECO	ECOLOGIC				

Courtesy of Orsam, Sylvania Inc.

Figure 41-13. Compact fluorescent lamp designations. (Continues)

- Protection in amperes
- Who will furnish each equipment item (furnished by others or by contractor)
- Installation requirements
- Remarks column for any detailed specific information required

A *receptacle schedule* is valuable when a number of special or specific receptacle types are found on the electrical drawings. If one is not provided, you should make one to expedite the installation time required and reduce the chance of installation error. A receptacle schedule should include:

- The symbol designation used by the designer
- Amperage rating

- Number of wires and poles
- Voltage rating
- NEMA type
- The configuration of the blades or slots
- A manufacturer catalog number reference
- Special information (duplex, single, three phase, etc.)

Note: Receptacle information may be found on an *equipment schedule*.

The local plans review and the utility company typically require a *connected load schedule*. This type of schedule includes:

- Type of load
- Building or area designation




Figure 41-13. (Continued)

- Size of load (kilowatts or horsepower)
- Total electrical load by type or area
- Notes explaining any special methods used in the load calculations

Specifications

The drawings and the *specifications* are the items that establish the intended design and the construction

requirements required by the owner, architect, and engineers. The contractors and their installers must review the *contract* documents for conflicts and/or discrepancies between the contract, the specifications, and the drawings. The drawings should be reviewed for conflicts between sections (architectural, mechanical, plumbing, structural, civil, HVAC, electrical, etc.). The drawings in your specific section should be reviewed for conflicts sheet by sheet.

The electrical specifications give the quality of materials intended to be used and the installation and testing requirements. Sometimes a specific manufacturer or catalog number is specified with no substitution or “equal” allowed. This usually inflates the cost

of the project. There is no standard specification. The contractors and their installers should read through all project specifications and become knowledgeable of their content prior to starting any installation.



USING WHAT YOU LEARNED

A basic skill for reading electrical drawings is knowing which circuits feed each electrical device and the corresponding panel for that circuit. There are two duplex receptacles shown in the elevator area on the first floor plan. Are those receptacles in the elevator car or elsewhere? From which panel are they fed? What circuit are they on? The receptacles are labeled as being “in pit,” so they are not in the elevator car. The numbers 15 and L10 indicate that they are on circuit 15 which is fed from panel L10. This can be verified on the panel schedule E-11 of Sheet E7.

Assignment









Refer to the School Addition drawings in your textbook packet to complete this assignment.

1. What are the four basic methods of showing electrical circuits?
2. How is a home run circuit shown?
3. What is a reflected ceiling plan?
4. In a low-voltage lighting system, what does the light switch activate?
5. Where do you find the industry standardized electrical symbols?
6. What are the four basic types of electrical drawings?
7. What is the name of the method used to show the path of wiring or raceway from one level of a building to another?
8. What is a schematic wiring diagram?
9. What is used to systematically list equipment, loads, devices, and information?
10. Where do you find the quality of material intended to be used on a project?
11. How many F17T8/SP30 lamps are required on the first floor of the addition?
12. Explain why one of the switches in room 109 is listed as S_{3M} and the other is simply S_3 .
13. How are the lights turned on and off in the first-floor corridor?
14. What circuit carries the lights for stair #2?
15. What is the approximate total wattage of the lamps in the boys' toilet room on the first floor?
16. What is the total load for the circuit that serves the lights in the boys' toilet room on the first floor?
17. What is indicated by the D in a square near the doors from the existing building into the addition?
18. What is on circuit L10, 24?
19. Where are the devices on circuit L10, 15?
20. Explain what each of the colored terminals on a classroom lighting control is to be connected to:
 - a. Green
 - b. Orange
 - c. Black
 - d. White
 - e. Blue (inner terminal)
 - f. Blue (outer terminal)

PART 4

Test

A. Which of the symbols shown in Column II is used on the School Addition drawings to represent the objects or materials listed in Column I?


I	II
1. Room number	a. 
2. Building section	b. 
3. Rigid insulation	c. 
4. Window type	d. 
5. Door number	e. 
6. Interior elevation	f. 
7. Wood blocking	g. 
8. Detail key	h. 

B. Refer to the door schedule on School Addition Sheet A001 to write the door numbers from Column II that are associated with the material in Column I.

I	II
1. Wood	216
2. Steel hollow metal	104
3. Plastic	101

C. Name the material for each of the numbered items in the drawing of a bond beam.

1. ____
2. ____
3. ____
4. ____
5. ____



D. Describe the material at each of the following locations in the School Addition.

1. Door frame 103
2. South wall of corridor 106
3. Structural portion of west wall of classroom 104
4. Exterior surface of west wall at corners
5. Exterior surface of west wall below windows
6. Stair treads
7. Vertical reinforcement in elevator pit walls
8. Beam at the top of the west wall of classroom 204
9. Lintel over the windows in the west wall
10. Door frame at entrance to stair #1

E. Refer to the School Addition drawings and write the elevation at the following locations.

1. Second finish floor
2. Top of roof
3. Top of bricks beneath window in classroom 103
4. Top of concrete blocks in first floor corridor walls
5. Top of tackboard on north wall of classroom 103
6. Finish floor in elevator pit
7. Top of foundation wall at typical locations
8. Top of footing for column F3
9. Top of beams in second floor framing between columns in row C

F. Refer to the School Addition drawings to answer the following questions.

1. What is the height of the rough opening for the grille that allows outside air to enter classroom 103?
2. What supports the outer few inches of the roofing membrane in the area where the roof-edge coping meets it?
3. What size are the concrete masonry units in the north wall?
4. What are the three materials that make up the roof decking on the canopy over door 101?
5. What are the drawing and sheet numbers for information about typical column base plates?
6. Give as much information as possible about the welds that fasten the roof framing bar joists to the beams at the tops of the north and south walls.

7. On what branch circuit are the light fixtures in stair #1?
8. How are the light fixtures in the second floor corridor turned on and off?
9. How many lamps are required for all the fixtures in the second floor corridor?
10. What branch circuit supplies the convenience outlets in the second floor corridor?
11. Which terminal on the corridor lighting control unit is connected to the neutral leg of the supply?
12. What is the diameter of the sanitary drain where it leaves the building?
13. What are the pipe sizes that storm water passes through as it flows from the roof drain on the north canopy to the point where it exits the building?
14. Where is the nearest cleanout to the roof drain at the west end of the addition?
15. What type of unit provides heat in storage room 109?



Appendix A

School Addition Master Keynotes

Master Keynotes

- 2.11 Demolition, Removals & Relocation
- 2.20 Site Preparation & Earthwork
 - 2.20A Select Fill - Bank Run Gravel
 - 2.20B Select Granular Material
 - 2.20D Topsoil
 - 2.20F Crushed Gravel
 - 2.20G 4" perforated P.v.c.
 - 2.20I Compacted Subgrade
- 2.22 Structural Excavation, Backfill and Compaction (Building Area)
- 2.60 Pavement and Walks
 - 2.60A Vehicular Area Sub-Base Course Granular
 - 2.60B Asphaltic Concrete - Binder Course
 - 2.60C Asphaltic Concrete Top - Wearing Course
 - 2.60D Concrete Walk/Paving
 - 2.60E Precast Concrete Curb
 - 2.60G Reinforcing Mesh
 - 2.60H Expansion Joint Filler
 - 2.60I Control Joint - 4'-0" O.C. Maximum Saw Cut or Tooled
 - 2.60J Stabilization Fabric
 - 2.60P Asphaltic Concrete-Base Course
 - 2.60Q Detectable Warning Pavers
- 2.61 Pavement Markings
 - 2.61B Painted ANSI Handicap Symbol

- 2.61C Painted Traffic Control Lines
- 2.80 Landscaping
- 2.80A Seeding
- 2.83 Chain Link Fence
- 2.83D 2.875" O.C. Corner Post
- 2.83E 2.875" O.C. Line Post
- 2.83F 1-1/2" Top Rail
- 2.83G 2" Mesh Fabric
- 2.83H 7 Gauge Tension Wire Continuous
- 2.83I Post Cap
- 2.83J 1 1 Gauge Rail Clamps
- 2.83K Sleeve
- 2.83L 1 1 Gauge Bands
- 2.83M 1/4" × 3/4" Turnbuckle
- 2.83N Stretcher Rod
- 2.83O 3/8" Diameter Truss Rod
- 2.83P Pass Thru Cap
- 2.83Q Gate Frame
- 2.83R Top Hinge
- 2.83S Hinge
- 2.83T Fork Latch
- 3.30 Concrete
- See Structural Drawings*
- 3.30A Cast-In-Place-Concrete
- 3.30B Reinforcing Bar
- 3.30D Welded Wire Mesh, Size as Noted
- 3.32 Concrete Slab on Grade
- 3.325 Concrete Slab on Metal Deck
- 3.40 Precast Concrete
- 3.40D Precast Dry Pit
- 3.40E Precast Concrete Wall Unit
- 3.40F Precast Concrete Cap Unit

- 3.40G *Geogrid*
- 4.10 *Mortar and Masonry Grout*
- 4.10A *Grout Solid*
- 4.10B *Mortar Fill*
- 4.20 *Unit Masonry*
- 4.20A *Face Brick - Standard Modular*
- 4.20C *Concrete Masonry Units*
- 4.20D *Horizontal Joint Reinforcing*
- 4.20E *Flexible Masonry Anchors*
- 4.20G *Premolded Control Joint Strips*
- 4.20I *Reinforcing Bars*
- 4.20J *Flexible Masonry Column Tie Anchors*
- 4.20K *Weep Holes*
- 4.20M *Control Joint*
- 4.20P *Slate Sill - 1/4" Chamfer at Exposed Edges*
- 4.20S *Precast Concrete Sill*
- 4.20Y *Precast Concrete Band*
- 4.20A *Expansion Joint Closure*
- 5.10 *Structural Steel*
- See Structural Drawings**
- 5.10A *Steel Beam*
- 5.10B *Steel Angle*
- 5.10D *Anchor Bolt*
- 5.10E *Steel Tube Column*
- 5.10F *Miscellaneous Steel - Shape and Size as Noted*
- 5.10G *Steel Tee*
- 5.20 *Steel Joists*
- See Structural Drawings**
- 5.30 *Metal Decking*
- See Structural Drawings**
- 5.30A *Metal Roof Decking*
- 5.50 *Miscellaneous Metals*

- 5.50A Miscellaneous Steel - Shape and Size as Noted
- 5.50B Steel Angle
- 5.50C 1-1/4" Nominal Steel pipe (1.66" O.D.) Post 4"-0" O.C. Maximum
- 5.50D 10 Gauge Metal Riser, Tread and Landing Pan
- 5.50E MC 12 × 10.6 Stringer
- 5.50F 3-1/2" × 2-1/2" × 1/4" - LLV - Pan Support at 3"-0" O.C. Maximum
- 5.50G 1-1/2" × 1-1/2" × 1/4" Steel Angle Carriers
- 5.50M Galvanized Steel Bent Plate
- 5.50N Galvanized Steel Flat Bar Stock
- 5.50O 3/4" Diameter Galvanized Steel Rungs
- 5.50S Steel Bollards - Fill With Concrete - Bevel Concrete at Top
- 5.50U 1-1/4" Nominal Steel Pipe (1.66" O.D.)
- 5.50Y Countersunk Machine Head Screw/Expansion
- 5.50A FSteel Plate
- 5.50A M1" Nominal Steel Pipe Handrail (1.315" O.D.)
- 5.50A N1" Nominal Steel Pipe Bracket
- 5.50A PSteel Wall Bracket, Julius Blum #622, or Equal
- 5.50A XAluminum Sleeve (.050")
- 5.50A YSteel Plate, Size as Noted
- 5.80 Expansion Joints
- 5.80A Expansion Joint Cover
- 6.10 Rough Carpentry
- 6.10A Wood Blocking
- 6.10B Plywood
- 6.10C Wood Furring
- 6.101 Wood Framing 16" O.C.
- 6.10S Joist Hanger
- 6.10T Pressure Treated Bail; Size as Noted
- 6.10U Pressure Treated Post; Size as Noted
- 6.20 Finish Carpentry
- 6.2 OF Softwood Trim
- 7.15 Dampproofing

- 7.20 Insulation
- 7.20B Batt Insulation
- 7.20C Cavity Wall Insulation
- 7.20H Metal Z Furring
- 7.41 Preformed Wall Panels
- 7.41C Vertical Siding
- 7.41F Trim to Match Siding
- 7.50 Roofing System (EpOM)
- 7.50A Roofing Membrane
- 7.50B Membrane Flashing
- 7.50C Insulation
- 7.50D Thermal Barrier
- 7.50E Tapered Insulation
- 7.50F Vapor Barrier/Air Seal
- 7.50G Ballast and Protective Mat
- 7.50H Fascia System
- 7.50K Fascia Extender
- 7.50M Aluminum Counterflashing
- 7.50N Sealant
- 7.50P Termination Bar
- 7.50Q Expansion Joint Support
- 7.50R Closed Cell Backer Rod
- 7.50T Insert Drain
- 7.50V Recovery Board
- 7.50W Aluminum Trim -.032" Thickness
- 7.51 Roofing System (Silicone)
- 7.51A Silicone Coating
- 7.51B Urethane Insulation
- 7.51D Sealant
- 7.51E Aluminum Foam Stop - 0.050" Thickness
- 7.51J Aluminum Trim - 0.32" Thickness
- 7.51K Insert Drain

- 7.53 Roofing System (EPDM-Foam Adhesive)
 - 7.53A Roofing Membrane
 - 7.53B Foam Adhesive
 - 7.53C Membrane Flashing
 - 7.53D Insulation
 - 7.53H Fascia System
 - 7.53K Fascia Extender
 - 7.53O Sealant
 - 7.53Q Termination Bar
 - 7.53R Closed Cell Backer Rod
 - 7.53T Insert Drain
- 7.60 Flashing and Sheet metal
 - 7.60 A Thru-wall Flashing - Turn-Up at Ends at Wall Openings to Form Dam
- 7.72 Roof Accessories
- 7.90 Caulking and Sealants
 - 7.90A Sealant and Backing Material (Size as Required to Fill Void)
 - 7.90B Foam Joint Filler - Width Shown X Size Required to Fill Void)
 - 7.90C Sealant Bead
 - 7.90G Expansion Joint Filler
- 8.10 Metal Doors and Frames
 - 8.10A Steel Hollow Metal Door Frame
 - 8.10B Steel Hollow Metal Door
 - 8.10E Metal Access Door
 - 8.10F 16 Gauge Hollow Metal Pipe Enclosure
- 8.15 Plastic Doors

See Door Schedule*

 - 8.15A Plastic Door
 - 8.1 5B Aluminum Door Frame System
 - 8.15C .090" Break Metal to Match Door Frame System
 - 8.15G Aluminum Angle (Size as Noted)
 - 8.20 Wood Doors

See Door Schedule*

- 8.20A Wood Door
- 8.33 Rolling Counter Fire Door
- 8.33B Vertical Sliding Pass Window
- 8.33C Stainless Steel Sill
- 8.50 Metal Windows
- 8.50A Aluminum Windows
- 8.50B 1/8" Break Metal to Match Windows
- 8.50C Extruded Aluminum Sill and Clip
- 8.50D Extruded Aluminum Head/Jamb Panning
- 8.50E Extruded Aluminum Trim
- 8.50K Fixed Aluminum Window
- 8.50L Horizontal Rolling Aluminum Window
- 8.50R Foam Tape
- 8.50S Foam Insulation
- 8.50T Double Hung Window
- 8.70 Hardware and Specialties
- See Door Schedule*
- 8.70D Aluminum Threshold Set in Mastic
- 8.80 Glazing
- 8.80A Tempered Insulating Glass
- 8.80B Insulating Glass
- 8.80C Safety Wire Glass
- 8.80D Tempered Glass
- 8.80I Muntins Inside Insulated Glass
- 8.80K Obscure Insulating Glass
- 09805 Encapsulation of Asbestos Containing Material
- 9.25 Gypsum Wallboard
- 9.25A 5/8" Type 'X' Gypsum Wallboard
- 9.25B "J" Casing Bead
- 9.25C Metal Stud System
- 9.25D Metal Furring
- 9.25G Metal Stud Runner - 2" Deep to Provide 1" Expansion for Studs

- 9.25J Gypsum Sheathing
- 9.25k Carrying Channel
- 9.25L 5/8" Exterior Gypsum Ceiling Board
- 9.25N Metal Angle Runner

9.30 Tile

*See Room Finish Schedule**

- 9.30A Glazed Wall Tile
- 9.30B Unglazed Ceramic Mosaic Tile
- 9.30D Glazed Ceramic Tile Wall Base
- 9.30E Marble Thresholds - *See Door Schedule**
- 9.30F Accent Tile - Continuous Around Room
- 9.30Q Unglazed Ceramic Mosaic Tile Base

9.40 Terrazzo

- 9.40A Thin Set Terrazzo
- 9.40C Terrazzo Cove Base

9.50 Acoustical Treatment

*See Room Finish Schedule**

- 9.50A Suspended Ceiling System

9.65 Resilient Flooring

*See Room Finish Schedule**

- 9.65A Vinyl Composition Tile
- 9.65B Vinyl Cove Base
- 9.65D Rubber Stair Treads and Risers
- 9.65E Molded Rubber Tile
- 9.65J Rubber Base

9.80 Special Coating System

- 9.80A Special Coating System
- 9.80B Finish Coat
- 9.80C Base Coat
- 9.80D Reinforcing Mesh
- 9.80E Insulation
- 9.80F Gypsum Sheathing

- 9.80G Metal Studs
- 9.80H Sealant and Backer Rod
- 9.80I Waterproof Base Coat
- 9.80J Routed Joint
- 9.80K Insulation Board Below Grade
- 9.80L Below Grade Waterproofing
- 9.80M Slide Clip
- 9.80N Bent Galvanized Metal (Size and Gauge as Noted)
- 9.80O Expansion Joint
- 9.90 Painting
- See Room Finish Schedule*
- 9.90E-1 Paint E-1
- 9.90E-2 Paint E-2
- 9.90P-1 Paint P-1
- 9.90P-2 Paint P-2
- 9.90P-3 Paint P-3
- 9.90P-4 Paint P-4
- 9.90P-6 Paint P-6
- 9.90P-8 Paint P-8
- 10.10 Chalkboards and Tackboards
- 10.10B Liquid Marker Board
- 10.10C Tackboard
- 10.10F Projection Screen
- 10.25 Firefighting Devices
- 10.25A Fire Extinguisher Cabinet. Paint P-2. Model * 2409-R 2 By Larson Manufacturing Co., or Approved Equal
- 10.42 Signage and Graphics
- 10.42A 12" × 18" Aluminum Handicap Sign
- 10.50 Lockers
- 10.50A Single Tier Lockers
- 10.50G Sloping Top
- 10.50H Metal Base

- 10.50I *Recessed Trim*
- 10.62 *Folding Partitions*
- 10.62A *Folding Partitions*
- 10.62B *Tracks, Support Brackets, Hangar Rods and Finish Trim*
- 10.62D *Liquid Marker Board*
- 10.80 *Toilet Accessories*
- 10.80D *Grab Bars*
- 11.46 *Unit Kitchens*
- 11.46A *Compact Kitchen Unit*
- 12.17 *Entrance Mats*
- 12.17A *Recessed Entrance Mat*
- 12.30 *Casework*
- See Drawings for Casework*
- 12.30A *Plastic Laminate Counter with 4" Backsplash*
- 12.30D *Filler Strip - Size as Required*
- 12.30G *Base Cabinet*
- 12.30I *Lab Countertop*
- 12.30K *Plastic Laminate Top*
- 12.30L *Wall Cabinet*
- 14.20 *Elevators*
- 14.20A *Elevator*

***See reference noted for information elaborating on or work in addition to materials noted here. Provide all materials as required for a complete and proper installation.**



Appendix B

MATH REVIEWS

1. Fractions and Mixed Numbers—Meanings and Definitions	358
2. Adding Fractions	359
3. Adding Combinations of Fractions, Mixed Numbers, and Whole Numbers	360
4. Subtracting Fractions from Fractions	360
5. Subtracting Fractions and Mixed Numbers from Whole Numbers	360
6. Subtracting Fractions and Mixed Numbers from Mixed Numbers	361
7. Multiplying Fractions	361
8. Multiplying Any Combination of Fractions, Mixed Numbers, and Whole Numbers	362
9. Dividing Fractions	362
10. Dividing Any Combination of Fraction, Mixed Numbers, and Whole Numbers	363
11. Rounding Decimal Fractions	363
12. Adding Decimal Fractions	364
13. Subtracting Decimal Fractions	364
14. Multiplying Decimal Fractions	364
15. Dividing Decimal Fractions	365
16. Expressing Common Fractions as Decimal Fractions	366
17. Expressing Decimal Fractions as Common Fractions	366
18. Expressing Inches as Feet and Inches	367
19. Expressing Feet and Inches as Inches	367
20. Expressing Inches as Decimal Fractions of a Foot	367
21. Expressing Decimal Fractions of a Foot as Inches	368
22. Area Measure	368
23. Volume Measure	369
24. Finding an Unknown Side of a Right Triangle, Given Two Sides	372

MATH REVIEW I Fractions and Mixed Numbers—Meanings and Definitions

- A *fraction* is a value that shows the number of equal parts taken from a whole quantity. A fraction consists of a numerator and a denominator.

$$\frac{7}{16} \quad \begin{array}{l} \leftarrow \text{Numerator} \\ \leftarrow \text{Denominator} \end{array}$$

- *Equivalent fractions* are fractions that have the same value. The value of a fraction is not changed by multiplying the numerator and denominator by the same number.

Example Express $\frac{5}{8}$ as thirty-seconds.

Determine what number the denominator is multiplied by to get the desired denominator. ($32 \div 8 = 4$)

Multiply the numerator and denominator by 4.

$$\begin{aligned} \frac{5}{8} &= \frac{?}{32} \\ \frac{5}{8} \times \frac{4}{4} &= \frac{20}{32} \end{aligned}$$

- The *lowest common denominator* of two or more fractions is the smallest denominator that is evenly divisible by each of the denominators of the fractions.

Example 1 The lowest common denominator of $\frac{3}{4}$, $\frac{5}{8}$, $\frac{13}{32}$ is 32, because 32 is the smallest number evenly divisible by 4, 8, and 32.

$$\begin{aligned} 32 \div 4 &= 8 \\ 32 \div 8 &= 4 \\ 32 \div 32 &= 1 \end{aligned}$$

Example 2 The lowest common denominator of $\frac{2}{3}$, $\frac{1}{5}$, $\frac{7}{10}$ is 30, because 30 is the smallest number evenly divisible by 3, 5, and 10.

$$\begin{aligned} 30 \div 3 &= 10 \\ 30 \div 5 &= 6 \\ 30 \div 10 &= 3 \end{aligned}$$

- *Factors* are numbers used in multiplying. For example, 3 and 5 are factors of 15.
- A fraction is in its *lowest terms* when the numerator and the denominator **do not** contain a common factor.

$$3 \times 5 = 15$$

Example Express $\frac{12}{16}$ in lowest terms.

Determine the largest common factor in the numerator and denominator. The numerator and the denominator can be evenly divided by 4.

$$\begin{aligned} \frac{12 \div 4}{16 \div 4} &= \frac{3}{4} \end{aligned}$$

- A *mixed number* is a whole number plus a fraction.

$$6 \quad \frac{15}{16}$$

Whole Number ↑ ↑ Fraction

$$6 + \frac{15}{16} = 6\frac{15}{16}$$

- *Expressing fractions as mixed numbers.* In certain fractions, the numerator is larger than the denominator. To express the fraction as a mixed number, divide the numerator by the denominator. Express the fractional part in lowest terms.

Example Express $\frac{38}{16}$ as a mixed number.

Divide the numerator 38 by the denominator 16.

Express the fractional part $\frac{6}{16}$ in lowest terms.

Combine the whole number and fraction.

$$\begin{aligned} \frac{38}{16} &= 2\frac{6}{16} \\ \frac{6 \div 2}{16 \div 2} &= \frac{3}{8} \\ \frac{38}{16} &= 2\frac{3}{8} \end{aligned}$$

- *Expressing mixed numbers as fractions.* To express a mixed number as a fraction, multiply the whole number by the denominator of the fractional part. Add the numerator of the fractional part. The sum is the numerator of the fraction. The denominator is the same as the denominator of the original fractional part.

Example Express $7\frac{3}{4}$ as a fraction.

Multiply the whole number 7 by the denominator 4 of the fractional part ($7 \times 4 = 28$). Add the numerator 3 of the fractional part to 28. The sum 31 is the numerator of the fraction. The denominator 4 is the same as the denominator of the original fractional part.

$$\frac{7 \times 4 + 3}{4} = \frac{31}{4}$$

or

$$\frac{7}{1} \times \frac{4}{4} = \frac{28}{4}$$

$$\frac{28}{4} + \frac{3}{4} = \frac{31}{4}$$

MATH REVIEW 2 Adding Fractions

- Fractions must have a common denominator in order to be added.
- To add fractions, express the fractions as equivalent fractions having the lowest common denominator. Add the numerators and write their sum over the lowest common denominator. Express the fraction in lowest terms.

Example Add: $\frac{3}{8} + \frac{3}{4} + \frac{3}{16} + \frac{1}{32}$

Express the fractions as equivalent fractions with 32 as the denominator. Add the numerators.

$$\frac{3}{8} = \frac{3}{8} \times \frac{4}{4} = \frac{12}{32}$$

$$\frac{1}{4} = \frac{1}{4} \times \frac{8}{8} = \frac{8}{32}$$

$$\frac{3}{16} = \frac{3}{16} \times \frac{2}{2} = \frac{6}{32}$$

$$+ \frac{1}{32} = \frac{1}{32}$$

$$\frac{27}{32}$$

- After fractions are added, if the numerator is greater than the denominator, the fraction should be expressed as a mixed number.

Example Add: $\frac{1}{2} + \frac{3}{4} + \frac{15}{16} + \frac{11}{16}$

Express the fractions as equivalent fractions with 16 as the denominator. Add the numerators.

Express $\frac{46}{16}$ as a mixed number in lowest terms.

$$\frac{1}{2} = \frac{1}{2} \times \frac{8}{8} = \frac{8}{16}$$

$$\frac{3}{4} = \frac{3}{4} \times \frac{4}{4} = \frac{12}{16}$$

$$\frac{15}{16} = \frac{15}{16}$$

$$+ \frac{11}{16} = \frac{11}{16}$$

$$\frac{46}{16}$$

$$\frac{46}{16} = 2\frac{14}{16} = 2\frac{7}{8}$$

MATH REVIEW 3 Adding Combinations of Fractions, Mixed Numbers, and Whole Numbers

- To add mixed numbers or combinations of fractions, mixed numbers, and whole numbers, express the fractional parts of the numbers as equivalent fractions having the lowest common denominator. Add the whole numbers. Add the fractions. Combine the whole number and the fraction and express in lowest terms.

Example 1 Add: $3\frac{7}{8} + 5\frac{1}{2} + 9\frac{3}{16}$

Express the fractional parts as equivalent fractions with 16 as the common denominator. Add the whole numbers. Add the fractions. Combine the whole number and the fraction. Express the answer in lowest terms.

$$\begin{array}{r} 3\frac{7}{8} = 3\frac{14}{16} \\ 5\frac{1}{2} = 5\frac{8}{16} \\ +9\frac{3}{16} = 9\frac{3}{16} \\ \hline 17\frac{25}{16} = 17 + 1\frac{9}{16} = 18\frac{9}{16} \end{array}$$

Example 2 Add $6\frac{3}{4} + \frac{9}{16} + 7\frac{21}{32} + 15$

Express the fractional parts as equivalent fractions with 32 as the common denominator. Add the whole numbers. Add the fractions. Combine the whole number and the fraction. Express the answer in lowest terms.

$$\begin{array}{r} 6\frac{3}{4} = 6\frac{24}{32} \\ \frac{9}{16} = \frac{18}{32} \\ 7\frac{21}{32} = 7\frac{21}{32} \\ +15 = 15 \\ \hline 28\frac{63}{32} = 28 + 1\frac{31}{32} = 29\frac{31}{32} \end{array}$$

MATH REVIEW 4 Subtracting Fractions from Fractions

- Fractions must have a common denominator in order to be subtracted.
- To subtract a fraction from a fraction, express the fractions as equivalent fractions having the lowest common denominator. Subtract the numerators. Write their difference over the common denominator.

Example Subtract $\frac{3}{4}$ from $\frac{15}{16}$.

Express the fractions as equivalent fractions with 16 as the common denominator. Subtract the numerator 12 from the numerator 15. Write the difference 3 over the common denominator 16.

$$\begin{array}{r} \frac{15}{16} = \frac{15}{16} \\ -\frac{3}{4} = -\frac{12}{16} \\ \hline \frac{3}{16} \end{array}$$

MATH REVIEW 5 Subtracting Fractions and Mixed Numbers from Whole Numbers

- To subtract a fraction or a mixed number from a whole number, express the whole number as an equivalent mixed number. The fraction of the mixed number has the same denominator as the denominator of the fraction that is subtracted. Subtract the numerators of the fractions and write their difference over the common denominator. Subtract the whole numbers. Combine the whole number and fraction. Express the answer in lowest terms.

Example 1 Subtract $\frac{3}{8}$ from 7

Express the whole number as an equivalent mixed number with the same denominator as the denominator of the fraction that is subtracted ($7 = 6\frac{8}{8}$).

Subtract $\frac{3}{8}$ from $\frac{8}{8}$

Combine whole number and fraction.

$$\begin{array}{r} 7 = 6\frac{8}{8} \\ -\frac{3}{8} = -\frac{3}{8} \\ \hline 6\frac{5}{8} \end{array}$$

Example 2 Subtract $5\frac{15}{32}$ from 12

Express the whole number as an equivalent mixed number with the same denominator as the denominator of fraction that is subtracted ($12 = 11\frac{32}{32}$).

Subtract fractions.

Subtract whole numbers.

Combine whole number and fraction.

$$\begin{array}{r} 12 = 11\frac{32}{32} \\ -5\frac{15}{32} = -5\frac{15}{32} \\ \hline 6\frac{17}{32} \end{array}$$

MATH REVIEW 6 Subtracting Fractions and Mixed Numbers from Mixed Numbers

- To subtract a fraction or a mixed number from a mixed number, the fractional part of each number must have the same denominator. Express fractions as equivalent fractions having a common denominator. When the fraction subtracted is larger than the fraction from which it is subtracted, one unit of a whole number is expressed as a fraction with the common denominator. Combine the whole number and fractions. Subtract fractions and subtract whole numbers.

Example 1 Subtract $\frac{7}{8}$ from $4\frac{3}{16}$

Express the fractions as equivalent fractions with the common denominator 16.

Since 14 is larger than 3, express one unit of $4\frac{3}{16}$ as a fraction and combine whole number and fractions.

$$\left(4\frac{3}{16} = 3 + \frac{16}{16} + \frac{3}{16} = 3\frac{19}{16}\right).$$

Subtract.

$$\begin{array}{r} 4\frac{3}{16} = 4\frac{3}{16} = 3\frac{19}{16} \\ -\frac{7}{8} = \frac{14}{16} = -\frac{14}{16} \\ \hline 3\frac{5}{16} \end{array}$$

Example 2 Subtract 13 from 20

Express the fractions as equivalent fractions with the common denominator 32.

Subtract fractions.

Subtract whole numbers.

$$\begin{array}{r} 20\frac{15}{32} = 20\frac{15}{32} \\ -13\frac{1}{4} = -13\frac{8}{32} \\ \hline 7\frac{7}{32} \end{array}$$

MATH REVIEW 7 Multiplying Fractions

- To multiply two or more fractions, multiply the numerators. Multiply the denominators. Write as a fraction with the product of the numerators over the product of the denominators. Express the answer in lowest terms.

Example 1 Multiply $\frac{3}{4} \times \frac{5}{8}$
 Multiply the numerators.
 Multiply the denominators.
 Write as a fraction.

$$\frac{3}{4} \times \frac{5}{8} = \frac{15}{32}$$

Example 2 Multiply
 Multiply the numerators.
 Multiply the denominators.
 Write as a fraction and express answer in lowest terms.

$$\frac{1}{2} \times \frac{2}{3} \times \frac{4}{5} = \frac{8}{30} = \frac{4}{15}$$

MATH REVIEW 8 Multiplying Any Combination of Fractions, Mixed Numbers, and Whole Numbers

- To multiply any combination of fractions, mixed numbers, and whole numbers, write the mixed numbers as fractions. Write whole numbers over the denominator 1. Multiply numerators. Multiply denominators. Express the answer in lowest terms.

Example 1 Multiply $3\frac{1}{4} \times \frac{3}{8}$

$$3\frac{1}{4} \times \frac{3}{8} = \frac{13}{4} \times \frac{3}{8} = \frac{39}{32} = 1\frac{7}{32}$$

Write the mixed number $3\frac{1}{4}$ as the fraction $\frac{13}{4}$.
 Multiply the numerators.
 Multiply the denominators.
 Express as a mixed number.

Example 2 Multiply $2\frac{1}{3} \times 4 \times \frac{4}{5}$

$$2\frac{1}{3} \times 4 \times \frac{4}{5} = \frac{7}{3} \times \frac{4}{1} \times \frac{4}{5} = \frac{112}{15}$$

$$\frac{112}{15} = 7\frac{7}{15}$$

Write the mixed number $2\frac{1}{3}$ as the fraction $\frac{7}{3}$.
 Write the whole number 4 over 1.
 Multiply the numerators.
 Multiply the denominators.
 Express as a mixed number.

MATH REVIEW 9 Dividing Fractions

- Division is the inverse of multiplication. Dividing by 4 is the same as $\frac{1}{4}$. multiplying by j . 4 is the inverse of $\frac{1}{4}$. and is the inverse of 4.

The inverse of $-\frac{5}{16}$ is $\frac{16}{5}$.

- To divide fractions, invert the divisor, change to the inverse operation and multiply. Express the answer in lowest terms.

Example Divide: $\frac{7}{8} \div \frac{2}{3}$

Invert the divisor $\frac{2}{3}$

$\frac{2}{3}$ inverted is $\frac{3}{2}$.

Change to the inverse operation and multiply.

Express as a mixed number.

$$\frac{7}{8} \div \frac{2}{3} = \frac{7}{8} \times \frac{3}{2} = \frac{21}{16} = 1\frac{5}{16}$$

MATH REVIEW 10 Dividing Any Combination of Fraction, Mixed Numbers, and Whole Numbers

- To divide any combination of fractions, mixed numbers, and whole numbers, write the mixed number as fractions. Write whole numbers over the denominator 1. Invert the divisor. Change to the inverse operation and multiply. Express the answer in lowest terms.

Example 1 Divide: $6 \div \frac{7}{10}$

Write the whole number 6 over the denominator 1.

Invert the divisor $\frac{7}{10}$; $\frac{7}{10}$ inverted is $\frac{10}{7}$.

Change to the inverse operation and multiply.

Express as a mixed number.

$$\frac{6}{1} \div \frac{7}{10} =$$

$$\frac{6}{1} \times \frac{10}{7} = \frac{60}{7} = 8\frac{4}{7}$$

Example 2 Divide: $\frac{3}{4} \div 2\frac{1}{5}$

Write the mixed number divisor $2\frac{1}{5}$ as the fraction $\frac{11}{5}$.

Invert the divisor $\frac{11}{5}$; $\frac{11}{5}$ inverted is $\frac{5}{11}$.

Change to the inverse operation and multiply.

$$\frac{3}{4} \div \frac{11}{5} =$$

$$\frac{3}{4} \times \frac{5}{11} = \frac{15}{44}$$

Example 3 Divide: $4\frac{5}{8} \div 7$

Write the mixed number $4\frac{5}{8}$ as the fraction $\frac{37}{8}$.

Write the whole number divisor over the denominator 1.

Invert the divisor $\frac{7}{1}$; $\frac{7}{1}$ inverted is $\frac{1}{7}$.

Change to the inverse operation and multiply.

$$\frac{37}{8} \div \frac{7}{1} =$$

$$\frac{37}{8} \times \frac{1}{7} = \frac{37}{56}$$

MATH REVIEW 11 Rounding Decimal Fractions

- To round a decimal fraction, locate the digit in the number that gives the desired number of decimal places. Increase that digit by 1 if the digit that directly follows is 5 or more. Do not change the value of the digit if the digit that follows is less than 5. Drop all digits that follow.

Example 1 Round 0.63861 to 3 decimal places.

Locate the digit in the third place (8). The fourth decimal-place digit, 6, is greater than 5 and increases the third decimal-place digit 8, to 9. Drop all digits that follow.

$$0.63861 \approx 0.639$$

—

Example 2 Round 3.0746 to 2 decimal places.

Locate the digit in the second decimal place (7). The third decimal-place digit 4 is less than 5 and does not change the value of the second decimal-place digit 7. Drop all digits that follow.

$$3.0746 \approx 3.07$$

—

MATH REVIEW 12 Adding Decimal Fractions

- To add decimal fractions, arrange the numbers so that the decimal points are directly under each other. The decimal point of a whole number is directly to the right of the last digit. Add each column as with whole numbers. Place the decimal point in the sum directly under the other decimal points.

Example Add: $7.65 + 208.062 + 0.009 + 36 + 5.1037$

Arrange the numbers so that the decimal points are directly under each other.

Add zeros so that all numbers have the same number of places to the right of the decimal point.

Add each column of numbers.

Place the decimal point in the sum directly under the other decimal points.

$$\begin{array}{r} 7.6500 \\ 208.0620 \\ 0.0090 \\ 36.0000 \\ + 5.1037 \\ \hline 256.8247 \end{array}$$

MATH REVIEW 13 Subtracting Decimal Fractions

- To subtract decimal fractions, arrange the numbers so that the decimal points are directly under each other. Subtract each column as with whole numbers. Place the decimal point in the difference directly under the other decimal points.

Example Subtract: $87.4 - 42.125$

Arrange the numbers so that the decimal points are directly under each other. Add zeros so that the numbers have the same number of places to the right of the decimal point.

Subtract each column of numbers.

Place the decimal point in the difference directly under the other decimal points.

$$\begin{array}{r} 87.400 \\ - 42.125 \\ \hline 45.275 \end{array}$$

MATH REVIEW 14 Multiplying Decimal Fractions

- To multiply decimal fractions, multiply using the same procedure as with whole numbers. Count the number of decimal places in both the multiplier and the multiplicand. Begin counting from the last digit on the right of the product and place the decimal point the same number of places as there are in both the multiplicand and the multiplier.

Example Multiply: 50.216×1.73

Multiply as with whole numbers.

Count the number of decimal places in the multiplier (2 places) and the multiplicand (3 places).

Beginning at the right of the product, place the decimal point the same number of places as there are in both the multiplicand and the multiplier (5 places).

$$\begin{array}{r}
 50.216 \quad \leftarrow \text{Multiplicand} \\
 \times 1.73 \quad \leftarrow \text{(3 places)} \\
 \hline
 150648 \quad \leftarrow \text{Multiplier} \\
 351512 \quad \leftarrow \text{(2 places)} \\
 \hline
 50216 \\
 \hline
 86.87368 \quad \leftarrow \text{(5 places)}
 \end{array}$$

- When multiplying certain decimal fractions, the product has a smaller number of digits than the number of decimal places required. For these products, add as many zeros to the left of the product as are necessary to give the required number of decimal places.

Example Multiply: 0.27×0.18

Multiply as with whole numbers.

The product must have 4 decimal places.

Add one zero to the left of the product.

$$\begin{array}{r}
 0.27 \text{ (2 places)} \\
 \times 0.18 \text{ (2 places)} \\
 \hline
 216 \\
 27 \\
 \hline
 0.0486 \text{ (4 places)}
 \end{array}$$

MATH REVIEW 15 Dividing Decimal Fractions

- To divide decimal fractions, use the same procedure as with whole numbers. Move the decimal point of the divisor as many places to the right as necessary to make the divisor a whole number. Move the decimal point of the dividend the same number of places to the right. Add zeros to the dividend if necessary. Place the decimal point in the answer directly above the decimal point in the dividend. Divide as with whole numbers. Zeros may be added to the dividend to find the number of decimal places required in the answer.

Example 1 Divide: $0.6150 \div 0.75$

Move the decimal point 2 places to the right in the divisor.

Move the decimal point 2 places in the dividend.

Place the decimal point in the answer directly above the decimal point in the dividend.

Divide as with whole numbers.

$$\begin{array}{r}
 0.82 \\
 \text{Divisor} \rightarrow 0.75 \overline{)0.6150} \leftarrow \text{Dividend} \\
 60 \\
 150 \\
 150 \\
 \hline
 0000
 \end{array}$$

Example 2 Divide: $10.7 \div 4.375$. Round the answer to 3 decimal places.

Move the decimal point 3 places to the right in the divisor.

Move the decimal point 3 places in the dividend, adding 2 zeros.

Place the decimal point in the answer directly above the decimal point in the dividend.

Add 4 zeros to the dividend. One more zero is added than the number of decimal places required in the answer.

Divide as with whole numbers.

$$\begin{array}{r}
 2.4457 \approx 2.446 \\
 4375 \overline{)10700.0000} \\
 8750 \\
 19500 \\
 17500 \\
 20000 \\
 17500 \\
 2500 \\
 21875 \\
 31250 \\
 30625 \\
 \hline
 625
 \end{array}$$

MATH REVIEW 16 Expressing Common Fractions as Decimal Fractions

- A common fraction is an indicated division. A common fraction is expressed as a decimal fraction by dividing the numerator by the denominator.

Example Express $\frac{5}{8}$ as a decimal fraction.

Write $\frac{5}{8}$ as an indicated division.

Place a decimal point after the 5 and add zeros to the right of the decimal point.

Place the decimal point for the answer directly above the decimal point in the dividend.

Divide.

$$\begin{array}{r} 8 \overline{)5} \\ 8 \overline{)5.000} \\ 8 \overline{)5.000} \\ \underline{0.625} \\ 8 \overline{)5.000} \end{array}$$

- A common fraction which will not divide evenly is expressed as a repeating decimal.

Example Express $\frac{1}{3}$ as a decimal fraction.

Write $\frac{1}{3}$ as an indicated division.

Place a decimal point after the 1 and add zeros to the right of the decimal point. Place the decimal point for the answer directly above the decimal point in the dividend.

Divide.

$$\begin{array}{r} 3 \overline{)1} \\ 3 \overline{)1.0000} \\ 3 \overline{)1.0000} \\ \underline{0.3333} \\ 3 \overline{)1.0000} \end{array}$$

MATH REVIEW 17 Expressing Decimal Fractions as Common Fractions

- To express a decimal fraction as a common fraction, write the number after the decimal point as the numerator of a common fraction. Write the denominator as 1 followed by as many zeros as there are digits to the right of the decimal point. Express the common fraction in lowest terms.

Example 1 Express 0.9 as a common fraction.

Write 9 as the numerator.

Write the denominator as 1 followed by 1 zero. The denominator is 10.

$$\frac{9}{10}$$

Example 2 Express 0.125 as a common fraction.

Write 125 as the numerator.

Write the denominator as 1 followed by 3 zeros. The denominator is 1,000.

Express the fraction in lowest terms.

$$\frac{125}{1000} = \frac{1}{8}$$

MATH REVIEW 18 Expressing Inches as Feet and Inches

- There are 12 inches in 1 foot.
- To express inches as feet and inches, divide the given length in inches by 12 to obtain the number of whole feet. The remainder is the number of inches in addition to the number of whole feet. The answer is the number of whole feet plus the remainder in inches.

Example 1 Express $176\frac{7}{16}$ inches as feet and inches.

Divide $176\frac{7}{16}$ inches by 12.

There are 14 feet plus a remainder of $8\frac{7}{16}$ inches.

Example 2 Express 54.2 inches as feet and inches.

Divide 54.2 inches by 12.

There are 4 feet plus a remainder of 6.2 inches.

$$\begin{array}{r} 14 \text{ (feet)} \\ 12 \overline{)176\frac{7}{16}} \\ \underline{12} \\ 56 \\ \underline{48} \\ 8\frac{7}{16} \leftarrow \text{Remainder} \\ \text{(feet)} \end{array}$$

$$14' - 8\frac{7}{16}''$$

$$\begin{array}{r} 4 \text{ (feet)} \\ 12 \overline{)54.2} \\ \underline{48} \\ 6.2 \leftarrow \text{Remainder} \\ \text{(inches)} \end{array}$$

4 feet 6.2 inches

MATH REVIEW 19 Expressing Feet and Inches as Inches

- There are 12 inches in 1 foot.
- To express feet and inches as inches, multiply the number of feet in the given length by 12. To this product, add the number of inches in the given length.

Example Express 7 feet $9\frac{3}{4}$ inches as inches.

Multiply 7 feet by 12. There are 84 inches in 7 feet.

Add $9\frac{3}{4}$ inches to 84 inches.

$$\begin{aligned} 7 \times 12 &= 84 \\ 7 \text{ feet} &= 84 \text{ inches} \\ 84 \text{ inches} + 9\frac{3}{4} \text{ inches} &= \\ 93\frac{3}{4} \text{ inches} \end{aligned}$$

MATH REVIEW 20 Expressing Inches as Decimal Fractions of a Foot

- An inch is $\frac{1}{12}$ of a foot. To express whole inches as a decimal part of a foot, divide the number of inches by 12.

Example Express 7 inches as a decimal fraction of a foot.
Divide 7 by 12.

$$\begin{aligned} 7 \div 12 &= 0.58 \\ 0.58 \text{ feet} \end{aligned}$$

- To express a common fraction of an inch as a decimal fraction of a foot, express the common fraction as a decimal, and then divide the decimal by 12.

Example 1 Express $\frac{3}{4}$ inch as a decimal fraction of a foot. Expresses $\frac{3}{4}$ a decimal. Divide the decimal by 12.

$$3 \div 4 = 0.75$$

$$0.75 \div 12 = 0.06$$

0.06 feet

Example 2 Express $4\frac{3}{4}$ inches as a decimal fraction of a foot.

Express $4\frac{3}{4}$ as a decimal.

$$4 + \frac{3}{4} = 4 + 0.75 = 4.75$$

$$4.75 \div 12 = 0.39$$

0.39 feet

Divide the decimal inches by 12.

MATH REVIEW 21 Expressing Decimal Fractions of a Foot as Inches

- To express a decimal part of a foot as decimal inches, multiply by 12.

Example: Express 0.62 foot as inches. Multiply 0.62 by 12.

$$0.62 \times 12 = 7.44$$

7.44 inches

- To express a decimal fraction of an inch as a common fraction, see Math Review 17.

MATH REVIEW 22 Area Measure

- A surface is measured by determining the number of surface units contained in it. A surface is two-dimensional. It has length and width but no thickness. Both length and width must be expressed in the same unit of measure. Area is expressed in square units. For example, 5 feet \times 8 feet equals 40 square feet.

- *Equivalent Units of Area Measure:*

$$1 \text{ square foot (sq ft)} = 12 \text{ inches} \times 12 \text{ inches} = 144 \text{ square inches (sq in)}$$

$$1 \text{ square yard (sq yd)} = 3 \text{ feet} \times 3 \text{ feet} = 9 \text{ square feet (sq ft)}$$

- To express a given unit of area as a larger unit of area, divide the given area by the number of square units contained in one of the larger units.

Example 1 Express 648 square inches as square feet. Since 144 sq in = 1 sq ft, divide 648 by 144.

$$648 \div 144 = 4.5$$

648 square inches = 4.5 square feet

Example 2 Express 28.8 square feet as square yards. Since 9 sq ft = 1 sq yd, divide 28.8 by 9.

$$28.8 \div 9 = 3.2$$

28.8 square feet = 3.2 square yards

- To express a given unit of area as a smaller unit of area, multiply the given area by the number of square units contained in one of the larger units.

Example 1 Express 7.5 square feet as square inches.
 Since 144 sq in = 1 sq ft, multiply 7.5 by 144.

$$7.5 \times 144 = 1080$$

$$23 \text{ square yards} = 207 \text{ square feet}$$

Example 2 Express 23 square yards as square feet.
 Since 9 sq ft = 1 sq yd, multiply 23 by 9.

$$23 \times 9 = 207$$

$$23 \text{ square yards} = 207 \text{ square feet}$$

○ *Computing Areas of Common Geometric Figures:*

1. **Rectangle** A rectangle is a four-sided plane figure with four right (90°) angles.


The area of a rectangle is equal to the product of its length and its width. Area = length \times width ($A = l \times w$)

Example Find the area of a rectangle 24 feet long and 13 feet wide.

$$A = l \times w$$

$$A = 24 \text{ ft} \times 13 \text{ ft}$$

$$A = 312 \text{ square feet}$$



2. **Triangle** A triangle is a plane figure with three sides and three-angles. The area of a triangle is equal to one-half the product of its base and altitude.


$$A = \frac{1}{2} \text{base} \times \text{altitude} (A = b \times a)$$

Example Find the area of a triangle with a base of 16 feet and an altitude of 12 feet.

$$A = \frac{1}{2} b \times a$$

$$A = \frac{1}{2} \times 16 \text{ ft} \times 12 \text{ ft}$$

$$A = 96 \text{ square feet}$$



3. **Circle** The area of a circle is equal to π times the square of its radius. Area = $\pi \times \text{radius}^2$ ($A = \pi \times r^2$)
 Note: π (pronounced "pi") is approximately equal to 3.14.
 Radius squared (r^2) means $r \times r$.


Example Find the area of a circle with a 15-inch radius.

$$A = \pi \times r^2$$

$$A = 3.14 \times (15 \text{ in})^2$$

$$A = 3.14 \times 225 \text{ sq in}$$

$$A = 706.5 \text{ square inches}$$



MATH REVIEW 23 Volume Measure

- A solid is measured by determining the number of cubic units contained in it. A solid is three-dimensional; it has length, width, and thickness or height. Length, width, and thickness must be expressed in the same unit of measure. Volume is expressed in cubic units. For example, 3 feet \times 5 feet \times 10 feet = 150 cubic feet.

○ *Equivalent Units of Volume Measure:*

$$1 \text{ cubic foot (cu ft)} = 12 \text{ in} \times 12 \text{ in} \times 12 \text{ in} = 1728 \text{ cubic inches (cu in)}$$

$$1 \text{ cubic yard (cu yd)} = 3 \text{ ft} \times 3 \text{ ft} \times 3 \text{ ft} = 27 \text{ cubic feet (cu ft)}$$

- To express a given unit of volume as a larger unit of volume, divide the given volume by the number of cubic units contained in one of the larger units.

Example 1 Express 6,048 cubic inches as cubic feet
Since $1728 \text{ cu in} = 1 \text{ cu ft}$, divide 6048 by 1728.

$$6048 \div 1728 = 3.5$$

$$6048 \text{ cubic inches} = 3.5 \text{ cubic feet}$$

Example 2 Express 167.4 cubic feet as cubic yards.
Since $27 \text{ cu ft} = 1 \text{ cu yd}$, divide 167.4 by 27.

$$167.4 \div 27 = 6.2$$

$$167.4 \text{ cubic feet} = 6.2 \text{ yards}$$

- To express a given unit of volume as a smaller unit of volume, multiply the given volume by the number of cubic units contained in one of the larger units.

Example 1 Express 1.6 cubic feet as cubic inches.
Since $1728 \text{ cu in} = 1 \text{ cu ft}$, divide 1.6 by 1728.

$$1.6 \times 1728 = 2764.8$$

$$1.6 \text{ cubic feet} = 2764.8 \text{ cubic inches}$$

Example 2 Express 8.1 cubic yards as cubic feet.
Since $27 \text{ cu ft} = 1 \text{ cu yd}$, divide 8.1 by 27.

$$8.1 \times 27 = 218.7$$

$$8.1 \text{ cubic yards} = 218.7 \text{ cubic feet}$$

○ *Computing Volumes of Common Solids*

- A prism is a solid that has two identical faces called bases and parallel lateral edges. In a right prism, the lateral edges are perpendicular (at 90°) to the bases. The altitude or height (h) of a prism is the perpendicular distance between its two bases. Prisms are named according to the shapes of their bases.

- The volume of any prism is equal to the product of the area of its base and altitude or height.

$$\text{Volume} = \text{area of base} \times \text{altitude} \quad (V = A_B \times h)$$

○ *Right Rectangular Prism:*

A right rectangular prism has rectangular bases.

$$\text{Volume} = \text{area of base} \times \text{altitude}$$

$$V = A_B \times h$$

Example Find the volume of a rectangular prism with a base length of 20 feet, a base width of 14 feet, and a height (altitude) of 8 feet.


$$V = A_B \times h$$

Compute the area of the base (A_B):

$$\text{Area of base} = \text{length} \times \text{width}$$

$$A_B = 20 \text{ ft} \times 14 \text{ ft}$$

$$A_B = 280 \text{ sq ft}$$



Compute the volume of the prism:

$$V = A_B \times h$$

$$V = 280 \text{ sq ft} \times 8 \text{ ft}$$

$$V = 2,240 \text{ cu ft}$$

○ **Right Triangular Prism:**

A right triangular prism has triangular bases.

Volume = area of base \times altitude

$$V = A_B \times h$$

Example Find the volume of a triangular prism in which the base of the triangle is 5 feet, the altitude of the triangle is 3 feet, and the altitude (height) of the prism is 4 feet. Refer to the accompanying figure.

Volume = area of base \times altitude

$$V = A_B \times h$$

Compute the area of the base:

$$\text{Area of base} = \frac{1}{2} \text{base of triangle} \times \text{altitude of triangle}$$

$$A_B = \frac{1}{2} b \times a$$

$$A_B = \frac{1}{2} \times 5 \text{ ft} \times 3 \text{ ft}$$



$$A_B = 7.5 \text{ sq ft}$$

Compute the volume of the prism:

$$V = A_B \times h$$

$$V = 7.5 \text{ sq ft} \times 4 \text{ ft}$$

$$V = 30 \text{ cubic feet}$$



○ **Right Circular Cylinder:**

A right circular cylinder has circular bases.

Volume = area of base \times altitude

$$V = A_B \times h$$

Example Find the volume of a circular cylinder 1 foot in diameter and 10 feet high.

Note: Radius = $\frac{1}{2}$ Diameter; Radius = $1 \times 1 \text{ ft} = 0.5 \text{ ft}$.

$$V = A_B \times h$$

Compute the area of the base:

Area of base = $\pi \times$ radius squared

$$A_B = 3.14 \times (0.5)^2$$

$$A_B = 3.14 \times 0.5 \text{ ft} \times 0.5 \text{ ft}$$

$$A_B = 3.14 \times 0.25 \text{ sq ft}$$


$$A_B = 0.785 \text{ sq ft}$$

Compute the volume of the cylinder:

$$V = A_B \times h$$

$$V = 0.785 \text{ sq ft} \times 10 \text{ ft}$$

$$V = 7.85 \text{ cubic feet}$$



MATH REVIEW 24 Finding an Unknown Side of a Right Triangle, Given Two Sides

- If one of the angles of a triangle is a right (90°) angle, the figure is called a *right triangle*. The side opposite the right angle is called the *hypotenuse*. In the figure shown, c is opposite the right angle; c is the hypotenuse.
- In a right triangle, the square of the hypotenuse is equal to the sum of the squares of the other two sides:


$$c^2 = a^2 + b^2$$

If any two sides of a right triangle are known, the length of the third side can be determined by one of the following formulas:

$$c = \sqrt{a^2 + b^2}$$

$$a = \sqrt{c^2 - b^2}$$

$$b = \sqrt{c^2 - a^2}$$



Example 1 In the right triangle shown, $a = 6$ ft, $b = 8$ ft, find c .


$$c = \sqrt{a^2 + b^2}$$

$$c = \sqrt{6^2 + 8^2}$$

$$c = \sqrt{36 + 64}$$

$$c = \sqrt{100}$$

$$c = 10 \text{ feet}$$



Example 2 In the right triangle shown, $c = 30$ ft, $b = 20$ ft, find a .


$$a = \sqrt{c^2 - b^2}$$

$$a = \sqrt{30^2 - 20^2}$$

$$a = \sqrt{900 - 400}$$

$$a = \sqrt{500}$$

$$a = 22.36 \text{ feet (to two decimal places)}$$



Example 3 In the right triangle shown, $c = 18$ ft, $a = 6$ ft, find b .


$$b = \sqrt{c^2 - a^2}$$

$$b = \sqrt{18^2 - 6^2}$$

$$b = \sqrt{324 - 36}$$


















$$b = \sqrt{288}$$

$$b = 16.97 \text{ feet (to two decimal places)}$$



Appendix C












MATERIAL SYMBOLS IN SECTIONS

EARTH		STRUCTURAL STEEL	
ROCK		REINFORCING BARS	
GRAVEL OR CRUSHED STONE		GENERAL METAL	
CONCRETE		BATT INSULATION	
CONCRETE BLOCK		RIGID INSULATION	
FACE BRICK OR COMMON BRICK		PLASTER OR GYPSUM BOARD	
FIRE BRICK		THIN SHEET MATERIALS (PLASTIC FILM, SHEET METAL, PAPER, ETC.)	
ROUGH WOOD-CONTINUOUS			
WOOD BLOCKING			
FINISH WOOD			















Appendix D

PLUMBING SYMBOLS

PIPING



























DRAIN OR WASTE ABOVE GROUND	
DRAIN OR WASTE BELOW GROUND	
VENT	
COLD WATER	
HOT WATER	
HOT WATER HEAT SUPPLY	
HOT WATER HEAT RETURN	
GAS	
PIPE TURNING DOWN OR AWAY	
PIPE TURNING UP OR TOWARD	
BREAK - PIPE CONTINUES	

FITTINGS

	SOLDERED	SCREWED
TEE		
WYE		
ELBOW - 90°		
ELBOW - 45°		
CAP		
UNION CLEANOUT		
STOP VALVE		

Appendix E

ELECTRICAL SYMBOLS

CEILING FIXTURE		TELEPHONE	
CEILING FIXTURE WITH PULL SWITCH		INTERCOM	
WALL MOUNTED FIXTURE		TELEVISION ANTENNA	
RECESSED CEILING FIXTURE — OUTLINE SHOWS SHAPE		SMOKE DETECTOR	
FLOURESCENT FIXTURE		DISTRIBUTION PANEL	
FAN OUTLET		JUNCTION BOX	
CONVENIENCE DUPLEX OUTLET		SINGLE-POLE SWITCH	
SPLIT WIRED DUPLEX OUTLET		THREE-WAY SWITCH	
WEATHERPROOF OUTLET		SWITCH WITH PILOT LIGHT	
OUTLET WITH GROUND FAULT INTERRUPTER		WEATHERPROOF SWITCH	
SPECIAL-EQUIPMENT OUTLET		SWITCH WIRING	
RANGE OUTLET			
PUSH BUTTON			
CHIME			
TRANSFORMER			



Appendix F

COMMON ABBREVIATIONS

Note: These common abbreviations can appear on construction drawings and like documentation with or without periods (e.g., AC or A.C.).

AB—anchor bolt

AC—air conditioning

AL or **ALUM**—aluminum

BA—bathroom

BLDG—building

BLK—block

BLKG—blocking

BM—beam

BOTT—bottom

BPL—base plate

BR—bedroom

BRM—broom closet

BSMT—basement

CAB—cabinet

CL—centerline

CLNG or **CLG**—ceiling

CMU—concrete masonry unit
(concrete block)

CNTR—center or counter

COL—column

COMP—composition

CONC—concrete

CONST—construction

CONT—continuous

CORRUG—corrugated


CRNRS—corners

CU—copper

d—penny (nail size)

DBL—double

DET—detail

DIA or —diameter

DIM—dimension

DN—down

DO—ditto

DP—deep or depth

DR—door

DW—dishwasher

ELEC—electric

ELEV—elevation

EQ—equal

EXP—exposed or expansion

EXT—exterior

FG—fuel gas

FIN—finish

FL or **FLR**—floor

FOUND or **FDN**—foundation

FP—fireplace

FT—foot or feet

FTG—footing

GAR—garage

GFCI—ground fault circuit
interrupter

GI—galvanized iron

GL—glass

GRD—grade

GYPBD—gypsum board

HC—hollow core door

HCW—hollow core wood

HDR—header

HM—hollow metal

HORIZ—horizontal

HT or **HGT**—height

HW—hot water

HWM—high water mark

IN—inch or inches

INSUL—insulation

INT—interior

JSTS—joists

JT—joint

LAV—lavatory

LH—left hand

LIN—linen closet

LT—light

MANUF—manufacturer

MAS—masonry

MATL—material

MAX—maximum

MIN—minimum

MTL—metal

NAT—natural

N/F—now or formerly

NIC—not in contract

o/—overhead or over

OC—on centers

OH Door—overhead door

OSB—Oriented strand board

PERF—perforated

PL—plate

PLYWD—plywood

PT—pressure-treated lumber

R—risers

REF—refrigerator

REINF—reinforcement

REQ—requirement

RH—right hand

RM—room

ROB—run of bank (gravel)

ROW—right of way

SCRND—screened

SHT—sheet

SHTG—sheathing


SHWR—shower

SIM—similar

SL—sliding

S&P—shelf and pole

SPEC—specifications

SQ or —square

STD—standard

STL—steel

STY—story

T&G—tongue and groove

THK—thick

T'HOLD—threshold

TYP—typical

VB—vapor barrier

w/—with

WARD—wardrobe

WC—water closet

WD—wood

WDW—window

WH—water heater

WI—wrought iron



Glossary

A

Addendum—A change or modification to the bid documents, plans, and specifications that is made prior to the contractor's bid date

Aggregate—Hard materials such as sand and crushed stone used to make concrete

Ampere (amp)—Unit of measure of electric current

Anchor Bolt—A bolt placed in the surface of concrete for attaching wood framing members

Apron—Concrete slab at the approach to a garage door—also the wood trim below a window stool

Architect's Scale—A flat or triangular scale used to measure scale drawings

Ash Dump—A small metal door in the bottom of a fireplace

Awning Window—A window that is hinged near the top so the bottom opens outward

B

Backfill—Earth placed against a building wall after the foundation is in place

Backsplash—The raised lip on the back edge of a countertop to prevent water from running down the backs of the cabinets

Balloon Framing—Type of construction in which the studs are continuous from the sill to the top

of the wall—upper floor joists are supported by a let-in ribbon

Balusters—Vertical pieces that support a handrail

Balustrade—The complete assembly of railings, balusters, and newel posts around a stair or balcony

Batt Insulation—Flexible, blanket-like pieces, usually of fiber-glass, used for thermal or sound insulation

Batten—Narrow strip of wood used to cover joints between boards of sheet materials

Batter Boards—An arrangement of stakes and horizontal pieces used to attach lines for laying out a building

Beam—Any major horizontal structural member

Beam Pocket—A recessed area to hold the end of a beam in a concrete or masonry wall

Bird's Mouth—A notch cut in a rafter to fit around the top plate of the wall. The bird's mouth consists of a level cut that rests on top of the wall plate and a plumb cut that fits against the vertical surface of the wall.

Board Foot—144 cubic inches of wood or the amount contained in a piece measuring 12" × 12" × 1"

Bottom Chord—The bottom horizontal member in a truss

Box Sill—The header joist nailed across the ends of floor joists at the sill

Branch Circuit—The electrical circuit that carries current from the distribution panel to the various parts of the building

British Thermal Unit (BTU)—The amount of heat required to raise the temperature of 1 pound of water 1° Fahrenheit

Building Lines—The outside edge of the exterior walls of a building

C

Casement Window—A window that is hinged at one side so the opposite side opens outward

Casing—The trim around a door or window

Centerline—An actual or imaginary line through the exact center of any object

Change Order—A change or modification to the contract documents, plans, and specifications that is made after the contract has been awarded to the selected trade contractor

Cleanout—A pipe fitting with a removable plug that allows for cleaning the run of piping in which it is installed, or an access door at the bottom of a chimney

Collar Beam—Horizontal members that tie opposing rafters together, usually installed about halfway up the rafters

Collar Ties—A horizontal board between two opposing rafters, usually about one-third the vertical height of the roof from peak. Collar ties strengthen the roof frame and help prevent the rafters from forcing the walls outward.

Column—A metal post to support an object above

Common Rafter—A rafter extending from the top of the wall to the ridge

Concrete—Building material consisting of fine and coarse aggregates bonded together by Portland cement

Conductor—Electrical wire—a cable may contain several conductors

Contour Lines—Lines on a topographic map or site plan to describe the contour of the land

Contract—Any agreement in writing for one party to perform certain work and the other party to pay for the work

Convenience Outlet—Electrical outlet provided for convenient use of lamps, appliances, and other electrical equipment

Cornice—The construction that encloses the ends of the rafters at the top of the wall

Cornice Return—The construction where the level cornice meets the sloping rake cornice

Course—A single row of building units such as concrete blocks or shingles

Cove Mold—Concave molding used to trim an inside corner

CSI Format—The standard format for specifications developed by the Construction Specifications Institute.

D

Damper—A door installed in the throat of a fireplace to regulate the draft

Dampproofing—Vapor barrier or coating on foundation walls or under

concrete slabs to prevent moisture from entering the house

Datum—A reference point from which elevations are measured

Delivery Sheet (Trusses)—A summary sheet included with a packet of truss drawings to show how many of each type of truss is required

Detail—A drawing showing special information about a particular part of the construction—details are usually drawn to a larger scale than other drawings and are sometimes section views

Dormer—A raised section in a roof to provide extra headroom below

Double-hung Window—A window consisting of two sashes that slide up and down past one another

Drip Cap—A wood ledge over wall openings to prevent water from running back under the frame or trim around the opening

Drip Edge—Metal trim installed at the edge of a roof to stop water from running back under the edge of the roof deck

Drywall—Interior wall construction using gypsum wallboard

E

Elevation—A drawing that shows vertical dimensions—it may also be the height of a point, usually in feet, above sea level

F

Fascia—The part of a cornice that covers the ends of the rafters

Firestop—Blocking or noncombustible material between wall studs to prevent vertical draft and flame spread

Flashing—Sheet metal used to cover openings and joints in walls and roofs

Float—To level concrete before it begins to cure—floating is done with a tool called a *float*

Floor Plan—A drawing showing the arrangement of rooms, the locations of windows and doors, and complete dimensions—a floor plan is actually a horizontal section through the entire building

Flue—The opening inside a chimney—the flue is usually formed by a terra cotta flue liner

Flush Door—A door having flat surfaces

Footing—The concrete base upon which the foundation walls are built

Footing Drain—(also called *perimeter drain*) An underground drain pipe around the footings to carry groundwater away from the building

Frieze—A horizontal board beneath the cornice and against the wall above the siding

Frostline—The maximum depth to which frost penetrates the earth

Furring—Narrow strips of wood attached to a surface for the purpose of creating a plumb or level surface for attaching the wall, ceiling, or floor surface

G

Gable—The triangular area between the roof and the top plate walls at the ends of a gable roof

Gable Studs—The studs placed between the end rafters and the top plates of the end walls

Gauge—A standard unit of measurement for the diameter of wire or the thickness of sheet metal

Girder—A beam that supports floor joists

Grout—A thin mixture of high-strength concrete or mortar

Gusset—A reinforcing piece of metal or plywood fastened to a truss where the members meet.

Gypsum Wallboard—Drywall material made of gypsum encased in paper to form boards

H

Header—A joist fastened across the ends of regular joists in an opening, or the framing member above a window or door opening

Hearth—Concrete or masonry apron in front of a fireplace

Hip—Outside corner formed by intersecting roofs

Hip Rafter—The rafter extending from the corner of a building to the ridge at a hip

Hopper—A type of window that is hinged at the bottom and opens inward at the top.

Hose Bibb—An outside faucet to which a hose can be attached

I

I-joist—An engineered wood joist with a vertical web of plywood or OSB and solid wood upper and lower chords

Insulated Glazing—Two or more pieces of glass in a single sash with an air space between them for the purpose of insulation

Invert Elevation—The elevation at the lowest point inside a pipe

Isometric Drawing—A kind of drawing in which horizontal lines are 30° from true horizontal and vertical lines are vertical

J

Jack Rafter—A rafter between the outside wall and a hip rafter or the ridge and a valley rafter

Jamb—Side members of a door or window frame

Joists—Horizontal framing members that support a floor or ceiling

L

Lintel—Steel or concrete member that spans a clear opening—usually found over doors, windows, and fire-place openings

M

Masonry Cement—Cement that is specially prepared for making mortar

Measuring Line—An imaginary line running the length of a rafter and passing through the deepest part of the bird's mouth. This is the line from which all rafter measurements are made.

Mil—A unit of measure for the thickness of very thin sheets—1 mil equals .001"

Miter—A 45° cut so that two pieces will form a 90° corner

Mortar—Cement and aggregate mixture for bonding masonry units together

Mullion—The vertical piece between two windows that are installed side by side—window units that include a mullion are called *mullion windows*

Muntins—Small vertical and horizontal strips that separate the individual panes of glass in a window sash

N

Nailer—A piece of wood used in any of several places to provide a nailing surface for other framing members

Nominal Size—The size by which a material is specified—the actual size is often slightly smaller

Nosing—The portion of a stair tread that projects beyond the riser

O

Oblique Drawing—A drawing type in which one side (usually the one with the most detail) is drawn in proportion as though it is flat against the paper. Other sides are shown with parallel lines to show depth.

Orthographic Projection—A method of drawing that shows separate views of an object

Overhang—The horizontal distance covered by a roof outside the walls of the structure.

P

Panel Door—A door made up of panels held in place by rails and stiles

Penny Size—The length of nails

Perimeter Drain—(See *Footing Drain*)

Pilaster—A masonry or concrete pier built as an integral part of a wall

Pitch—Refers to the steepness of a roof—the pitch is written as a fraction with the rise over the span

Plan View—A drawing that shows the layout of an object as viewed from above

Plate—The horizontal framing members at the top and bottom of the wall studs

Platform Framing—(also called *Western framing*) A method of framing in which each level is framed separately—the subfloor is laid for each floor before the walls above it are formed

Plenum—A chamber within a forced-air heating system that is pressurized with warm air

Plumb—Truly vertical or true according to a plumb bob

Ply (trusses)—If trusses are plied, they are joined together face-to-face to make a stronger unit

Portland Cement—Finely powdered limestone material used to bond the aggregates together in concrete and mortar

Potable Water—Water that is safe for drinking

R

R value—The ability of a material to resist the flow of heat

Rafter—The framing members in a roof

Rail—Also the horizontal members in a balustrade, such as the railing around a stairway

Rake—The sloping cornice at the end of a gable roof

Resilient Flooring—Vinyl, vinyl-asbestos, and other man-made floor coverings that are flexible yet produce a smooth surface

Ridge Board—The framing member between the tops of rafters that runs the length of the ridge of a roof

Rise—The vertical dimension of a roof or stair

Riser—The vertical dimension of one step in a stair—the board enclosing the space between two treads is called a riser

Rowlock—Position of bricks in which the bricks are laid on edge

Run—The horizontal distance covered by an inclined surface such as a rafter or stair

S

Sash—The frame holding the glass in a window

Saturated Felt—Paper-like felt that has been treated with asphalt to make it water resistant

Screed—A straight board used to level concrete immediately after it is placed

Section View—A drawing showing what would be seen by cutting through a building or part

Setback—The distance from a street or front property line to the front of a building

Sheathing—The rough exterior covering over the framing members of a building

Shim—Thin material, typically wood shingle, used to adjust a small space

Sill—The framing member in contact with a masonry or concrete foundation

Sill Sealer—Compressible material used under the sill to seal any gaps

Site Constructed—Built on the job

Site Plan—The drawing that shows the boundaries of the building, its location, and site utilities

Sliding Window—A window with two or more sashes that slide horizontally past one another

Slope—The steepness of a roof, usually indicated in inches of rise per foot of run.

Soffit—The bottom surface of any part of a building, such as the underside of a cornice or lowered portion of a ceiling over wall cabinets

Soldier—Brick position in which the bricks are stood on end

Span—The horizontal dimension between vertical supports—the span of a beam is the distance between the posts that support it

Specifications—Specific written instructions for materials to be used and methods of construction or application

Square—The amount of siding or roofing materials required to cover 100 square feet

Stack—The main vertical pipe into which plumbing fixtures drain

Stair Carriage—The supporting framework under a stair

Stile—The vertical members in a sash, door, or other panel construction

Stool—Trim piece that forms the finished window sill

Stop—Molding that stops a door from swinging through the opening as it is closed—also used to hold the sash in place in a window frame

Stud—Vertical framing member in a wall

Subfloor—The first layer of rough flooring applied to the floor joists

Sweat—Method of soldering used in plumbing

T

Tail—The portion of a truss top chord or a rafter that extends beyond the walls of the structure.

Termite Shield—Sheet metal shield installed at the top of a foundation to prevent termites from entering the wood superstructure

Thermal-break Window—Window with a metal frame that has the interior and exterior separated by a material with a higher R value than the metal itself

Thermostat—An electrical switch that is activated by changes in temperature

Top Chord—The top horizontal or sloped member of a truss

Trap—A plumbing fitting that holds enough water to prevent sewer gas from entering the building

Tread—The surface of a step in stair construction

Trimmers—The double framing members at the sides of an opening

Truss—A manufactured assembly used to support a load over a long span

Truss Detail—An engineering drawing giving detailed specification for the manufacture of one particular truss; a truss drawing packet will usually include a truss detail for each type of truss to be used

Truss Drawings—Any of several types of drawings provided by an engineer to give detailed information about the construction and placement of trusses

Truss Layout Plan—A plan drawing giving detailed information about where each truss is to be placed, including spacing between trusses

U

Underlayment—Any material installed over the subfloor to provide a smooth surface over which floor covering will be installed

V

Valley—The inside corner formed by intersecting roofs

Valley Rafter—The rafter extending from an inside corner in the walls to the ridge at a valley

Vapor Barrier—Sheet material used to prevent water vapor from passing through a building surface

Veneer—A thin covering; in masonry, a single wythe of finished masonry over a wall; in woodwork, a thin layer of wood

Vent Pipe—A pipe, usually through the roof, that allows atmospheric pressure into the drainage system

Vertical Contour Interval—The difference in elevation between adjacent contour lines on a topographic map or site plan

Volt—The unit of measurement for electrical force

W

Water Closet—A plumbing fixture commonly called a *toilet*

Watt—The unit of measurement of electrical power—1 watt is the amount of power from 1 ampere of current with 1 volt of force

Web—The bracing members of a truss between the top chord(s) and the bottom chord.

Weep Hole—A small hole through a masonry wall to allow water to pass

Western Framing—(See *Platform Framing*)

Wythe—A single thickness of masonry construction



Index

Page numbers followed by “f” indicate figure.

A

Abbreviations, electrical, 326, 328f
Air-conditioning. *See* Heating, ventilating, and air-conditioning (HVAC)
Air-handling equipment, 315, 320, 320f
Alphabet of lines, 19–24
 centerlines, 22, 22f
 construction drawings and, 19
 cutting-plane lines, 23, 24f
 dashed lines, 20, 20f, 21f
 dimension lines, 21–22, 21f, 22f
 extension lines, 21–22, 21f, 22f
 hidden lines, 20
 leaders, 22–23, 23f
 object lines, 19, 19f
 phantom lines, 20, 21f
American Welding Society, 244, 286
Anchor bolts, 86, 86f
Applied stop molding, 184
Apron, pitch of, 93
Architect, 3–4, 144, 342
Architect’s scale, reading, 15, 17, 17f
Architectural drawing sheets, 29
Arrow side, of reference line, 286, 290f
Ash dump, 212, 212f
Ash pit, 212
Asphalt roofing materials, 156
Attic ventilation, 175–176, 176f
Authority Having Jurisdiction (AHJ), 5

B

Backfilled excavation, 92
Balloon diagrams, 4
Balloon framing, 96, 98f
Balusters, 220
Balustrade, 220, 220f
Band joist, 100
Bar joists, 306, 307f
Base moldings, 229f–234f
Battens, 188, 189f
Batter boards, 66f, 67
Beam pockets, 88, 88f, 103f
Beams, 99
 collar, 156
 grade, 291
 joists, 109

 lintels, 304
 LVL (laminated veneer lumber), 111f, 120
 plywood box, 99
 steel, 87, 111
 wooden, 87
Bearing, for floor joists, 120
Bearing angle, 60, 60f
Bearing plate, 109–111, 110112f
Bird’s mouth, 142, 156
Blanket insulation, 224, 226f
Bolts, 286, 289f
Bond beam, 307, 310f
Bond patterns, 193, 194f
Bottom chord, 140
Bottom (sole) plate, 100
Boundary lines, 60–61
Box cornice, 170, 171f, 172f
 fascia, 170
 narrow, 170, 172f
 parts of, 171f
 sloping, 170, 171f
 soffit, 170
 wide, 170, 173f
Box sill, 116, 117f. *See also* Sill construction
Branch circuits, 339
Brick positions, 194f
Brown coat, 193
Builder’s level, 69
Building codes
 footings, 79
 model codes and, 5
 party walls, 262
 purpose of, 5–6
 state and local, 5
Building layout, 37–38
Building lines, 65–67, 65f
Building permit, 5
Building sewer, 71, 72–73
Bus ducts and wireway symbols, 328f–332f

C

Cabinets
 on drawings, 236–238, 236f, 237f, 238f
 elevations, 50, 51f, 236, 236f
 in floor plans, 37, 39
 letter/number designations for, 238f

 manufacturers’ literature on, 238
 shelves/valances/filler pieces/trim, 238
 typical designations for, 238f
Cabinet unit heaters, 313, 314f
Cantilevered framing, 123, 125f
Casing, 180
Cast iron plumbing materials, 73
Centerlines, 22, 22f
Ceramic tile, 227
Certificate of occupancy, 5
Chain dimensions, 21–22
Chase (for metal chimney), 214, 214f, 216f
Check rails, 182
Chimney, 213–214, 213f, 214f
Civil construction, 2, 3f
Cleanout door (fireplace), 212, 212f
Collar beams, 156. *See also* Collar ties
Collar ties, 156. *See also* Collar beams
Column footings, 81f, 291, 304
Column pads, 79–80, 81f
Columns, 109–112, 110f, 112f
Commercial construction, 2, 2f, 3f, 283–294, 286f
 architectural style, 285, 286f
 coordination of drawings, 296–303
 foundations, 288–291, 292f–294f
 indexes, 296, 297f–299f
 masonry reinforcement, 307
 material keying, 296, 299–300, 300f
 mental walk-through, 301–303
 metal floor joists, 117
 metal framing, 100–101, 104f
 reference symbols on drawings, 300–301, 301f
 shop fabrication, 287–288, 291f
 structural drawings, 304, 306
 structural grid coordinate, 301, 302f
 structural steel, 285–286, 287f, 288f, 289f
 welding symbols, 286, 290f–291f
Commercial electrical symbols, 328f–332f
Common rafters, 154–160
 finding length of, 158, 158f
 International Residential Code and, 154
 roof construction and, 154, 154f, 156, 156f
 roof covering and, 156, 158f

- roof openings, 159
- shed roof framing, 158–159, 159f
- Common wall 260, 261f
- Composite products, 198
- Concrete foundations, 84–86, 283
 - anchor bolts and, 86, 199
 - reinforced, 283
 - structural concrete and, 85
- Concrete slabs, 93–94
- Conduit, 327, 334
- Connected load schedule, 341
- Construction classifications, 2
- Construction industry, 1, 2, 19
- Contour lines, 62, 63f
 - interpolation and, 62
 - topographic, 62
 - vertical contour interval, 62
- Contract documents, 228, 342
- Contractor, 5–6, 79
- Copper plumbing, 73, 190
- Corner boards, 191, 191f
- Cornice returns, 173, 174f, 175–176, 175f
 - framing for, 175f
 - level box cornice and, 173
 - style of, 173, 174f
 - types of, 175f
- Cornices, 171–178
 - box, 170, 171f, 172f
 - close, 173, 174f
 - cornice returns, 173, 174f, 175–176, 175f
 - end (rake) rafters and, 170
 - open, 170, 173f
 - types of, 170, 173
 - ventilation, 175–176
- Cove molding, 220, 228
- Cripple studs, 136, 137f, 138f
- Cross section, 47, 217, 217f
- CSI, 338
- Cut (earth removal), 62
- Cutting-plane lines, 23, 23f

D

- Damper (fireplace), 213, 213f
- Dashed lines, 20, 20f, 21f, 44f
- Datum symbols, 81
- Dead loads, 269
- Dynamic loads, 269
- Decks, 197–200
 - anchoring, 199–200, 199f
 - composite materials, 198
 - on floor plan, 198, 198f
 - railings, 200, 200f
 - support, 197–199, 197f, 198f
 - typical construction of, 197f
- Delta Energy Center, 3f
- Depth, of rafters and joists, 154
- Design and construction team, 6, 6f
- Design process, 3–6, 4f
- Details
 - large scale, 50, 51f
 - orienting, 52, 53f

- Dimension lines, 21–22, 21f, 22f
- Dimensions, 38, 38f, 39f
 - on an elevation, 45f
 - cabinet, 238
 - chain, 21–22
 - column footing, 291
 - finding, 130–131, 131f
 - footing, 79
 - nominal, 27
 - of rough openings, 134, 134f, 136
- Do (ditto), 306
- Doors
 - construction, 182–183, 183f
 - details of, 184, 184f
 - dimensions of, 38
 - floor plans and, 37–38
 - flush, 183f
 - hollow core, 183
 - jamb detail (exterior), 184f
 - measurement of, 27f
 - molded, 183, 183f
 - panel, 182, 183f
 - pocket, 137, 137f
 - reading catalogs of, 184
 - schedules, 27, 134, 134f
 - symbols, 25, 25f, 27
- Double-hung window, 182
- Double top plate, 95, 96f
- Dowels, 291
- Drainage, 90, 92
 - septic system and, 74
- Drainage waste and vent system, 320–321, 322f
- Drain field, 73, 73f
- Drains
 - floor drains, 90, 93
 - footing drains, 90, 90f, 91f
 - pitch of, 71
 - plastic drain pipe, 90, 91f
 - sanitary drain, 321
 - storm drain, 308–309
- Drawing to scale, 15
- Drip cap molding, 190

E

- Earthquakes
 - forces created by, 269, 274, 275f
 - occurrences, 269
 - protection, 5, 86, 86f
- Elbows, 315f
- Electrical drawings, 324–343
 - distribution symbols, 328f–332f
 - lighting circuits, 325
 - numbering of, 29–30, 241
 - plan views, 324–326, 326f
 - power circuits, 324–325, 325f
 - riser diagrams, 333–334, 334f, 335f, 336f
 - schedules, 337–339, 339f, 340f, 341–342, 341f–342f
 - schematic diagrams, 334–336, 337f
 - single-line diagrams, 326–327, 333, 333f

- specifications, 342–343
- symbols, 328f–332f
- Electrical outlets, cabinets and, 236
- Electrical raceway installations, 94
- Electrical service, 74–75, 75f, 334f
 - overhead, 75, 75f
 - underground, 75, 75f
- Electrical symbols, 328f–332f
- Electricity, 74–75,
 - circuits, 324–327, 333–334, 336
 - electrical symbols on plans, , 325–326
- Elevation drawings (showing height), 41–45
 - information given on, 42, 44–45, 44f, 45f
 - orienting, 42, 42f, 43f
- Elevation reference symbol, 300–301, 301f
- Elevations (denoting vertical position), 62
 - defined, 62
 - interpolating, 62–63, 62f, 63f
- Engineers, 5, 35, 117, 288, 291, 342
- Engineer's scale, and architect's scale
 - compared, 15, 17
- Equipment schedule, 341
- Excavation, 67, 69, 69f, 76, 90
- Exhaust fan (EF), 315, 320
- Expansion joints, 93, 265, 304
- Extension jamps, 182
- Extension lines, 21, 21f
- Exterior wall coverings, 188–195
 - corner and edge treatment, 191–192
 - corner boards, 191, 191f
 - drip caps and flashing, 190–191, 190f, 191f
 - exposure, 188, 189f
 - fiber cement siding, 189–190, 189f
 - horizontal siding, 188, 188f, 189f, 191
 - masonry veneer, 193, 193f
 - metal and plastic siding, 192, 192f
 - stucco, 192–193, 192f, 193f
 - wood siding, 188, 188f, 189f

F

- Fabrication drawings, 287. *See also* Shop drawings
- Fan coil units (FCU), 313
- Fascia, 170
- Fiber cement siding, 189–190, 189f
- Field weld symbol, 288, 291f
- Fillet weld, 286
- Financing, 6
- Finished grade, 62, 63f, 90, 203
- Fire alarm riser diagram, 333–334, 335f
- Fire damper, 320, 320f
- Fireplace drawings, 217, 217f, 218f
- Fireplaces, gas-burning, 214, 215, 215f, 216f
- Fireplaces, prefabricated metal, 214, 214f, 215f
- Fireplaces, wood-burning, 211–214
 - ash dump, 212, 212f
 - basic construction of, 211–214
 - chimney and, 213–214, 213f, 214f

- clay flue, 213
 - cleanout door, 212, 212f
 - damper, 213, 213f
 - drawings, 217, 217f, 218f
 - efficiency of, 214
 - firebox, 212–213, 212f
 - foundation, 212
 - hearth, 213
 - masonry, 212–213, 212f, 214
 - theory of operation of, 211–214
 - throat, 213, 213f
 - wythe, 212
 - zones, 211, 211f
 - Fire-rated construction, 262–263, 263f
 - Fire-resistant materials, 262–263
 - Firestops, 263, 265f
 - Fixture schedule, 337, 338, 338f
 - information shown on, 337–338
 - School Addition, 338, 338f
 - Flashing, 166, 188, 190
 - battens and, 188
 - drip caps and, 190–191, 190f, 191f
 - valley, 166
 - Z-flashing, 188
 - Floor/ceiling assemblies
 - Impact Isolation Class (IIC), 266, 267f
 - sound control in, 266
 - sound transmission classification, 266
 - Floor drain, 90, 91f, 93
 - Floor framing, 87f, 96, 109, 110f, 116–126
 - cantilevered, 123, 125f
 - double-line plan, 121f
 - floor joists, 117–119, 118f
 - for irregular-shaped house, 120f
 - joist-and-girder, 109, 110f
 - Lake House, 119–123, 121f, 124f
 - at openings, 120, 126f
 - sill construction, 116, 116f
 - Floor plans
 - building layout, 37–38
 - decks, 198, 198f
 - defined, 37
 - dimensions, 129
 - doors and windows in, 37, 39
 - features of, 39
 - keynote, 266, 267f
 - Lake House, 119–120, 124f, 128
 - scale, 15
 - as section view, 12
 - Floors
 - earthquakes and, 277
 - finished, 228
 - Foamed-in-place insulation, 224, 225f
 - Footing-and-wall-type foundation, 36
 - Footing drains, 90, 91f. *See also* Footings
 - Footings, 76–83
 - building codes for, 79
 - column pads, 79, 81f
 - depth of, 81–82, 82f
 - dimensions of, 79
 - drains, 90, 91f
 - elevations indicated, 81
 - footing schedule, 294f
 - reinforcement, 81, 81f
 - slab-on-grade, 76, 76f, 77f
 - spread footings, 77–79, 78f, 79f, 80f
 - stepped footings, 82, 82f
 - Foundation
 - for commercial buildings, 304
 - for commercial construction, 288, 291
 - detail, 293f
 - dimensions, 37, 79, 84f
 - fireplace, 212
 - footing-and-wall-type, 36
 - laying out, 84–86, 84f, 85f, 86f
 - materials, 85
 - permanent wood, 88, 88f
 - pile, 291
 - preventing seepage in, 92
 - section through, 85f
 - sill construction and, 116
 - slab-on-grade, 36, 36f, 76, 76f
 - special features, 87–88, 87f, 88f
 - walls, 84–89
 - Foundation Concrete, 274, 276f
 - Foundation plans, 36–37, 37f, 68f
 - detail, 47
 - dimensioning on, 84f
 - foundation layout, 304
 - Framing systems, 95–107
 - advanced framing, 101–102, 105f–106f
 - balloon, 96, 98f
 - metal framing, 100–101, 104f
 - platform framing, 95, 95f, 96f
 - post-and-beam, 98–100, 100f, 101f
 - timber fastenings, 102f
 - Frostline, 81
 - Furring, 227, 227f
- G**
- Gable ends, 153, 153f
 - Gable roof, 140
 - Gambrel roof, 140
 - Garages, 256, 277
 - Gas pipes, 74
 - General contractor, 5, 6
 - GFCI. *See* Ground-fault circuit interrupter (GFCI or GFI)
 - GFI. *See* Ground-fault circuit interrupter (GFCI or GFI)
 - Girders, 109, 110, 111, 304
 - Grade beams, 291
 - Grade line, 44, 90
 - Grading, 61–62, 208
 - Grass, 206
 - Grilles (ventilation), 315
 - Grinder pump, 71, 72f
 - Grout (foundation), 86
 - Grout (masonry reinforcement), 307
 - Gusset, 140, 141f
 - Gypsum wallboard, 226–227
- H**
- Handrail, for stairs, 220
 - Hardiplank, 189
 - Hash mark, 28
 - Haunch, 76, 77f
 - Haunched slab, 288
 - Header, 45, 100
 - Header, door and wall openings, 136
 - Head jamb
 - door, 182
 - window, 180
 - Heating, ventilating, and air-conditioning (HVAC), 312–322
 - air-handling equipment, 315, 320, 320f
 - heating piping, 315, 319f
 - plans, 312
 - symbols, 316f–319f
 - unit ventilators, 313, 313f, 314f
 - Heat sink, 94
 - Hidden line, 20
 - Hidden Valley, 240
 - High tide areas, 100
 - Hip jack rafters, 163, 163f, 166–167, 167f
 - Hip rafters, 161–163, 163f
 - Hip roof, 140
 - Hold-down straps, 86, 86f
 - Hollow core doors, 183
 - Hoover Dam, 3f
 - Housed stringers, 220, 220f
 - Housing starts, and economy, 2
 - Hurricane areas, 100
 - HVAC. *See* Heating, ventilating, and air-conditioning (HVAC)
- I**
- ICC. *See* International Code Council (ICC)
 - Ice dam, 175, 176f
 - I-joists, 117, 176
 - IIC. *See* Impact Isolation Class (IIC)
 - Impact Isolation Class (IIC), 266, 267f
 - Incandescent lamp designations, 339f
 - Industrial construction, 2, 3f, 117
 - Industrial electrical symbols, 328f–332f
 - Institutional electrical symbols, 328f–332f
 - Insulated doors, 183, 184
 - Insulating glass (for windows), 182
 - Insulation, 92–93, 92f, 224–226, 225f, 226f
 - batt, 224
 - blanket, 224, 226f
 - condensation and, 175
 - fiberglass, 23
 - fire-resistant fiberglass, 263
 - foamed-in-place, 225f
 - of foundation/concrete slab, 224
 - pouring insulation, 224
 - raised heel rafters and, 156
 - rigid boards, 225
 - rigid plastic foam, 92f

R-value of, 224
 sound, 263–266, 265f
 thermal, 85, 99, 224, 225f
 vapor barrier, 225
 Integral stop molding, 184
 Interior elevation symbols, 301, 301f
 Interior molding, 228
 International Building Code®, on stair risers, 221
 International Code Council (ICC), 5
 International Residential Code®, 5, 5f, 78, 79, 80f, 110, 154, 213
 footings, 78f, 79,
 girders and, 110
 roof construction, 154
 International Residential Code® for One- and Two-Family Dwellings, 5, 5f
 Interpolation, 62
 Inverted-T foundation, 288
 Invert elevation, 74, 74f, 321
 Isometric drawings, 8, 9f, 10f. *See also* Pictorial drawing

J

Jack rafters, 163, 166–168, 166f, 167f
 Joist-and-girder floor framing, 109, 110f
 Joist headers, 120, 122f
 Joists
 attaching to girders, 112f
 bar, 306, 307f
 ceiling, 156
 defined, 109
 floor, 117–119, 118f, 119f
 I-joists, 117, 118, 176
 metal floor, 118, 118f
 open-web steel, 306, 307f
 types of, 117

K

Keynotes, 264, 265f
 Kitchen elevations, 236f
 Kitchen equipment schedule, 339

L

Lake House
 bedroom, 120
 Construction Specifications Institute's MasterFormat (CSI format) for, 240, 241f
 floor framing, 119–123, 121f, 124f
 foundation plan, 85
 kitchen and dining room, 129f
 living room, 129f
 loft, 130f
 playroom, 129
 post-and-beam framing, 99
 wall dimensions, 131
 Laminated veneer lumber (LVL), 110, 111, 111f
 Lamp characteristic designations, 338, 339f, 340f

Landing (stair), 219, 222f
 Landscaping, 6, 67, 204, 208
 Laser level, 69
 Lath, for stucco, 192
 Lawns, 202, 204
 Leach lines, 73
 Left overhang (LOH), 144
 Let-in ribbon boards, 96
 Leveling instrument, 81
 Light fixtures, 325, 338
 Lighting circuits, 325
 Lighting symbols, 328f–332f
 Lintels
 defined, 304
 lintel schedule, 307, 308f
 loose steel categorization, 306–307
 masonry wall openings, 306
 Lite (glass), 179
 Live loads, 269
 Longitudinal sections, 47, 49f
 Lookouts, 170, 172f
 Louvered grille, 315
 L shaped stairs, 129, 221
 LVL. *See* Laminated veneer lumber (LVL)

M

Mansard roof, 140
Manual of Steel Construction (AISC), 286
 Masonry construction, 38, 39f, 306
 Masonry foundations, 69, 81, 84, 86
 Masonry opening, 27, 38, 88
 Masonry veneer, 38, 191, 193, 193f
 Master Format, 338
 Mast head, 75. *See also* Service head
 Material keying, 296, 299–300, 300f
 Material legend, 286
 Material symbols, 27, 28f
 Measuring line (roof), 142
 Mechanical drawings, 312
 air-handling equipment, 315, 320, 320f
 heating piping, 315
 HVAC, 312
 plumbing, 320–321, 322f
 symbols, 316f–319f
 unit ventilators, 313, 313f, 314f
 Mechanical symbols, 316f–319f
 Meetings rails, 182
 Mental walk-through, 301–303
 Metal fireplaces, prefabricated, 214, 214f
 Metal framing, 100–101, 104f, 137
 Metal siding, 192, 192f
 Metal tile roofs, 156
 Metal windows, 180
 Mils (measurement), 92
 Model codes, 5
 Molded doors, 183, 183f
 Mortar, in masonry joints, 86, 307, 309f
 Mortgage, 6
 Motor control schematic, 336, 337f
 Mullion, 182

Multiconductor feeders, 75
 Multifamily buildings, 256. *See also* Town house construction
 Multifamily construction, 253
 Multifamily dwellings, 256
 Municipal sewers, 71, 71f, 73–74
 Muntins, 179

N

Narrow box cornice, 170, 172f
 National Electrical Manufacturers Association (NEMA), 327, 341f
 Natural features, 61
 Natural grade, 62. *See also* Finished grade
 NEMA. *See* National Electrical Manufacturers Association (NEMA)
 NEMA specifications, 327
 Newel post, 220
 Nominal size, 88
 Nonmetallic-sheathed cable, 101–102, 104f, 117
 Nosing (stair), 219–220

O

Oblique drawings, 9, 10f
 Open cornice, 170, 173f
 Open stringers, 220–221, 220f
 Open-web steel joists, 306, 307f
 Oriented-strand board (OSB), 156
 Orthographic projection, 9–12, 10f
 OSB. *See* Oriented-strand board (OSB)
 Other side, of reference line, 286
 Overhang, 140, 144
 left. *See* Left overhang (LOH)
 right. *See* Right overhang (ROH)
 Overhead construction, shown in floor plans, 20, 39
 Overhead electrical service, 74–75, 75f

P

Panelboard symbols, 328f–332f
 Panel doors, 182, 183f
 Panel schedule, 339
 Panel strips mullion casings, 234f
 Partitions. *See* Walls and partitions
 Party wall, 262–263, 263f, 264f
 area-separation wall and, 258
 defined, 262, 263f
 fire-rated, 262, 264f
 fire-rated construction and, 262–263
 sound insulation and, 263, 265–266, 265f
 Paved areas, 203, 204f
 Percolation, 74
 Percolation test, 73
 Permanent wood foundations, 88, 88f
 Phantom lines, 20, 21f
 Pictorial drawing, 8, 9. *See also* Isometric drawings
 Piers, 109–110

Pilasters, 79
Piles, 291
Pipe columns, 109
Pitch
 of concrete slab, 92, 93, 93f
 of roof, 140, 144, 145f
 of sewers, 71, 91f
Planters, 203, 205f, 206f
Plantings, 204–205, 206f, 207f
Plan views, 11–12, 11f, 35–39
 building layout, 37–38
 in construction drawings, 11–12, 11f
 dimensions of, 38, 38f, 39f
 electrical drawings and, 324–326, 326f
 floor plans, 37
 foundation plans, 36–37, 36f, 37f
 lighting circuits and, 325
 site plans, 35–36, 35f
 of a two-flue chimney, 213–214, 213f
Plastic siding, 192, 192f
Platform framing, 95–96, 95f, 96f. *See also*
 Western framing
 balloon framing and, 98–99
 characteristics of, 95–96
Plumbing, 320–321, 322f
 drainage waste and vent system, 320–321
 isometric drawings of, 319f
 riser diagram, 321, 322f
 single-line isometric, 9f
 symbols, 30f, 316f–319f
Plumbing wall, 128, 129f
Pocket doors, 137
Pole structures, 100
Portland cement, 80, 86
Posts, metal or wooden, 109
Post tensioning, 274
Power equipment symbols, 328f–332f
Power riser diagram, 333, 334f. *See also*
 Riser diagrams
Prefabricated metal fireplaces, 214, 214f
Property line, 35, 60
 direction of, 60
 site plans and, 35

R

Rabbet joints, 188
Raceways, 94, 265, 324, 327
 electrical, 94
 sound transmission and, 265
Radius of an arc, 22, 22f
Rafters, 142, 154–159
 hip, 161–163, 162f, 163f
 jack, 166–168, 166f, 167f
 length of common, 158, 158f
 raised heel, 156
 rake, 170, 171f
 size and spacing of, 154, 155f
 as structural members in common frame
 roof, 154
 valley, 163–166, 164f, 165f

Rafter table, 158, 158f, 162f, 166–167
Rails
 door, 182
 meetings or check, 182
 window, 179
Rake rafters, 170, 171f
Rebars, 80, 80f
Receptacle outlet symbols, 328f–332f
Receptacle schedule, 341
Reference symbols, 300–301, 301f,
 328f–332f
Remote control station symbols,
 328f–332f
Residential Code, 5, 5f, 79, 80f, 110, 154,
 213
Residential construction, 2
 floor joists in, 117
 footings used in, 76
 girders used in, 110
 types of roofs used in, 140, 141f
Retaining walls, 202–203, 202f, 203f
Reversed plans, 256, 259f
Ridge board, 142, 154, 156f
Right overhang (ROH), 144
Rigid boards, 224
Rise, of stairs, 219
Riser (drainage), 92
Riser diagrams, 333–334
 fire alarm, 333–334, 335f
 power, 333, 334f
 special, 333
 telephone, 334, 336f
Risers (stair), 219, 220, 220f, 221
Roofs
 common rafters, 154–159
 construction of, 154, 156
 construction terms, 140–143, 143f
 coverings, 156
 earthquakes and, 277
 elements of, 154f
 fire-resistant materials, 262
 framing openings, 159
 framing plan, 156, 157f
 hip and valley framing, 161–168
 ridge boards and rafters, 142, 154–159,
 161–167
 spacing of rafters, 152, 155f
 trusses, 142, 144–151
 types of, 140, 141f
 ventilation, 175–176, 176f
 weather protection, 156
Room finishing
 floors, 228
 interior molding, 228, 229f–234f
 schedule, 228, 228f
 wall and ceiling covering, 226–228, 227f,
 228f
Rough opening, 134–136
Run (roof), 142
Run, of stairs, 219

S

Sanitary drain, 321
Sash (window), 179
Scale drawings, 15
Schematic wiring diagram, 334,
 336, 337f
School Addition
 fire alarm riser diagram for, 333, 335f
 fixture schedule, 338, 338f
 heating plans, 313
 panel schedule for, 339
 plumbing, 320–321
 structural steel, 286
 telephone riser diagram for, 336f
Scratch coat, of stucco, 192–193, 193f
Section views, 12, 23, 49, 50f
 cutting-plane lines, 23, 23f, 24f
 in elevation, 217, 218f
 orienting, 52, 53f
 symbols, 300–301, 301f
 transverse (cross section), 47, 49f
 typical wall, 30–31, 47, 49, 77f, 193f
Seismic considerations
 earthquake occurrences, 269
 forces created by earthquakes, 269, 274,
 275f
 soils conditions, 274
 structural drawings, 274–277
Seismic Design Category map, 269,
 270f–273f
Septic systems, 71f, 73–74, 73f
Service head, 75, 75f. *See also* Mast head
Settling, preventing, 76
Sewers
 building sewer, 71, 71f, 72–73
 drains, 71
 municipal, 73–74, 73f
 uphill flow of, 71, 72f
Shear forces, 276f, 277
Sheathing, 52, 96
 board, 52
 gypsum-based structural, 52
 horizontal or diagonal boards as, 52
 magnesium oxide structural, 52
 Oriented-strand board (OSB) and, 52
 plywood, 52, 96
 wall, 192
Shed roof, 11f, 140, 159f
 framing, 158–159, 159f
 rake and, 170
Shed roof framing, 158–159, 159f
Sheetrock™, 226–227
Shingle panel molding, 171f, 172f
Shingles, 188, 191, 191f
Shop drawings, 287, 306. *See also*
 Fabrication drawings
Shrubs, 202, 204, 206, 206f
Side jams
 door, 182
 window, 180

- Siding
 exposure of, 188, 189f
 fiber cement, 189–190, 189f
 horizontal, 188, 188f, 191
 metal, 192, 192f
 plastic, 192, 192f
 vertical, 188, 189f
 wood, 188, 188f, 189f
- Sill (door), 182
 Sill (window), 180
 Sill construction, 116, 116f, 117f. *See also*
 Box sill
 Sill plate, 116, 116f
 Sill sealer, 116
- Site
 clearing, 61, 61f
 grading, 61–62, 63f, 208
 Site elevation, 44, 44f
 Site plans, 35–36, 35f, 74f, 202f, 204f, 257f
 building position, 36, 65
 Lake House, 204f
 paved areas on housing sites in, 203, 204f
 retaining walls on, 202f, 203f
 reversed, 256, 259f
 sewer drains on, 71, 72f
 utilities, 74f
 visualizing, 256–259
 Site utilities, 71–75
 building sewer, 72–73
 electrical service, 74–75, 75f
 municipal sewers, 73–74
 septic systems, 73–74, 73f, 74f
 sewer drains, 71, 71f, 72f
 utility piping other than sewers, 74, 74f
 6-8-10 method, 66, 66f
 Slab-on-grade construction, 77f
 Slab-on-grade footing, 76
 Slab-on-grade foundation, 36, 36f, 76, 76f
 Slater's felt, 156
 Slope
 contour lines and, 62
 hip roof, 140
 of roof, 140–141, 142f, 156
 stepped footings and, 82
 Sloped sites, stepped footings and, 82
 Sloping box cornice, 170, 171f
 Smoke shelf, 213, 213f
 Soffit, 170, 171f, 173f
 Soils conditions, and seismic design, 274
 Sole plate, 95
 Solid wood header, 136f
 Sound insulation, 263–266, 265f
 Sound transmission classification (STC),
 263–266, 265f
 Span, of roof, 140, 144
 Special riser diagram, 333
 Spiral stairs, 221
 Spot elevations, 62, 62f, 69f
 Spread footings, 77–79, 78f, 79f, 288
 Stair cove, 220
 Stairs, 219–223
 basic parts of, 219–220, 219f, 220f
 calculating risers and treads, 221, 222f, 223f
 cove, 220
 trim and balustrade, 220, 220f
 types of, 220–221, 220f, 223f
 STC. *See* Sound transmission classification
 (STC)
 Stepped footings, 82, 82f
 Stiles, 179, 179f, 182
 Stock plans, 6, 6f
 Stop molding, 180
 Storm drain, 321
 Straight stairs, 221
 Stringers, 219, 220–221
 housed, 220, 220f
 open, 220, 220f
 Structural drawings, commercial buildings,
 304
 Structural grid coordinate, 301, 302f
 Structural steel, 285–286
 framing, 304, 306–307, 306f
 Structural steel framing, 304, 306–307,
 306f
 Studs, 38, 95
 in balloon framing, 96
 cripple, 136, 137f, 138f
 door and window framing and, 136–137,
 136f, 137f
 firestops and, 263, 265f
 in platform framing, 95, 95f
 roof framing and, 151
 sound insulation and, 265
 wracking, 96
 Stud wall construction, 136
 Subcontractors, 6, 312
 Subfloor, 128, 228
 Superstructure, 86, 86f, 288
 Switchboard symbols, 328f–332f
 Switches, on circuits, 338
 Symbols, 25–33
 abbreviations, 31
 door and window, 25, 25f, 26f, 27, 27f
 electrical and mechanical, 27–29, 29f
 elevation reference, 301f
 material, 27, 28f
 plumbing, 30f, 316f–319f
 reference marks, 29–31, 31f, 32f
 section view, 300–301, 301f
 welding, 286, 289f, 290f
- T**
 Tail (roof), 140
 Target rod, for leveling instrument, 69, 69f
 Telephone riser diagram, 334, 336f. *See also*
 Riser diagrams
 Termite areas, and metal framing, 116, 117f
 Termite shield, 116, 117f
 Terra-cotta roof tiles, 156
 Thermal-break windows, 180
 Thermal insulation, 224–226, 225f
 Timber fastenings, 102f
 TJIs. *See* I-joists
 Top chord, 140, 141f
 Top plate, 95–96, 96f
 Transom bar, 182
 Transverse section, 47, 49f
 Treads (stair), 221, 222f, 223f
 Trees, 61, 61f, 202, 204–205, 204f, 206f
 Tripod, for leveling instrument, 69
 Trusses, 142, 144–153
 delivery sheet, 144, 147f
 engineering drawings, 144–152, 145f,
 146f, 147f, 148f
 gable ends, 153, 153f
 information on drawings, 144,
 145f, 146f
 truss detail, 149, 151f
 truss layout plan, 146, 148f
 Typical wall sections, 30–31, 32f, 47, 77f
- U**
 Underlayment, 228
 Unit rise, 140–141, 142f
 Unit ventilators, 313, 313f, 314f
 Urban Courts
 first phase of, 256
 housing units, 258f
 photos, 257–259
 reversed plan, 256, 259f
 site plan for, 257f
 structural drawings for, 274–277, 276f
 walls, 277, 277f
 U shaped stairs, 221, 221f
 Utility installations, 71
 Utility systems coordination, 94
- V**
 Valley jack rafters, 162f, 166
 Valley rafters, 163–166, 164f, 165f
 Vapor barriers, 92
 Veneer, 110
 brick, 85
 masonry, 193, 193f, 194f
 Ventilation, cornices and, 175–176. *See also*
 Heating, ventilating, and air-
 conditioning (HVAC)
 Vent pipe, 321
 Vertical contour interval, 62
 VOCs (Volatile Organic Compounds),
 245
 Volts, 338
- W**
 Wallboard
 fire-rated, 262, 263
 gypsum, 226–227, 262
 Walls and partitions, 128–131
 earthquakes, 277
 finding dimensions, 130–131,
 130f, 131f

- framing openings in, 136–137, 136f, 137f
 - rough opening dimensions, 134, 134f, 135f, 136
 - visualizing layout of, 128–130, 129f, 130f
 - Warm-air heating systems, 312. *See also* Heating, ventilating, and air-conditioning (HVAC)
 - Water supply pipes, 74, 74f
 - Weather stripping, on windows, 182
 - Web (roof), 140, 141f
 - Weep holes, 203
 - Welded wire fabric (WWF), 93, 93f
 - Welded wire fabric reinforcement, 93
 - Welded wire mesh (WWM), 93, 93f
 - Welding symbol, 286, 289f
 - Weld symbol, 286, 290f
 - Western framing, 95, 95f, 96f. *See also* Platform framing
 - Wide box cornice, 170, 172f
 - Windows
 - construction, 179–182
 - details of, 180–182, 180f, 181f, 182f
 - dimensions of, 38, 38f, 39f
 - in foundation, 1
 - framing, 136
 - hinged, 27
 - metal, 180
 - parts of, 179–180, 179f, 181f
 - reading catalogs of, 184, 185f
 - sash, 12f, 179
 - symbols, 25–27, 26f
 - thermal-break, 180
 - wood, 179–180
 - Wiring symbols, 28, 328f–332f. *See also* Electrical drawings
 - Wood drip cap molding, 190
 - Wood shingles, 156, 188
 - Wood siding, 188, 188f, 189f
 - Wracking, 96, 98f, 99f
 - WWF. *See* Welded wire fabric (WWF)
 - WWM. *See* Welded wire mesh (WWM)
- Z**
- Z flashing, 188
 - Zoning laws, 5

Understanding Construction Drawings, Seventh Edition


Take a few minutes now to assemble your drawing set, so that you will be able to locate specific sheets more easily as you need them. To assemble the set, unfold all of the sheets and lay them on a table with the drawing numbers listed below under FRONT showing in the lower right corner. With sheets stacked FRONT side up, if you fold back the top right corner you will see the drawing number listed under BACK. With the drawings FRONT side up and in the below order, use a heavy-duty stapler to staple them along the left end. Use at least 5 staples. With the drawings properly stapled, you can easily view all of the drawings for the Two-Unit Apartment, the Lake House and Urban Courts from the FRONT. The drawings for the School will be in order when you flip the drawings set over, keeping the bound (stapled) edge on the left. The assembled drawing set can be rolled for storage or for carrying.

Key to abbreviations used in the list below


2U = Two-Unit apartment building
LH = Lake House
UC = Urban Courts
S = School

SHEET	FRONT	BACK
1	2U/1	S/E-7
2	2U/2	S/E-2
3	LH/1	S/E-1
4	LH/2	S/H-1
5	LH/3	S/P-1
6	LH/4	S/S203
7	LH/5	S/S202
8	LH/6	S/S201
9	LH/7	S/S200
10	UC/A1.0	S/S101
11	UC/A3.1	S/S100
12	UC/A3.2	S/A610
13	UC/A3.3	S/A520
14	UC/A3.4	S/A504
15	UC/A5.010	S/A503
16	UC/A5.011	S/A502
17	UC/A5.4	S/A501
18	UC/FP1	S/A301
19	UC/S7.1	S/A201
20	UC/S7.2	S/A102
21	UC/SD1	S/A101
22	UC/SD3	S/A001


DATE	09/01/11
FLOOR PLAN, ELEVATIONS & SECTION	
REVISION	2 GENERAL UPDATE
1	RF-1634E
NO.	TYB
DRAWN BY	
FILE:	APARTMENT 2011
SCALE:	AS SHOWN
DATE:	MARCH 1, 2011
SHEET 1 OF 2	




FLOOR PLAN (SEE HEADER SCHEDULE (SHT. 2))
 SCALE: 1/4" = 1'-0"




FRONT ELEVATION
 SCALE: 1/4" = 1'-0"




REAR ELEVATION
 SCALE: 1/4" = 1'-0"





SITE PLAN
 SCALE: 1" = 20'



TYPICAL SECTION
 SCALE: 1/4" = 1'-0"



LEFT SIDE ELEVATION
 SCALE: 1/4" = 1'-0"



SECOND FLOOR REFLECTED CEILING PLAN Δ E-16
1/8" = 1'-0"

FIRST FLOOR REFLECTED CEILING PLAN Δ E-15
1/8" = 1'-0"

No	REVISIONS/SUBMISSIONS	Date
CWCG CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C. 120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305		
ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL SED# 01-02-01-04-0-004-006		
Drawing Title DETAILS: SCHEDULES		
Seal	Designed WBF	Project No. 9-4036.00
	Drawn NFB	Scale NONE
	Checked WBF	Reviewed WBF
	Date 11-1-94	

PANEL	CIRCUIT	DESCRIPTION OF LOAD	LOAD	VOLTS	POLES	TRIP	PANEL	CIRCUIT	DESCRIPTION OF LOAD	LOAD	VOLTS	POLES	TRIP
L10	1	NORTHWEST CLASSROOM LIGHTING	1647	120	1	20	1G	1	LIBRARY COMPUTER OUTLETS	200	120	1	20
	2	SOUTHWEST CLASSROOM LIGHTING	1847	120	1	20		2	LIBRARY COMPUTER OUTLETS	200	120	1	20
	3	ELEVATOR, MACH. RM., CORRIDOR & JAN. CLOS.	1847	120	1	20		3	LIBRARY COMPUTER OUTLETS	200	120	1	20
	4	TEACHERS & SOUTH ENTRY LIGHTING	854	120	1	20		4	LIBRARY COMPUTER OUTLETS	200	120	1	20
	5	TEACHERS & SOUTH ENTRY LIGHTING	967	120	1	20		5	LIBRARY COMPUTER OUTLETS	200	120	1	20
	6	OUTDOOR RECEPIS.	360	120	1	20		6	LIBRARY COMPUTER OUTLETS	200	120	1	20
	7	OUTDOOR RECEPIS.	360	120	1	20		7	LIBRARY COMPUTER OUTLETS	200	120	1	20
	8	OUTDOOR RECEPIS.	360	120	1	20		8	LIBRARY COMPUTER OUTLETS	200	120	1	20
	9	OUTDOOR RECEPIS.	360	120	1	20		9	LIBRARY COMPUTER OUTLETS	200	120	1	20
	10	OUTDOOR RECEPIS.	360	120	1	20		10	LIBRARY COMPUTER OUTLETS	200	120	1	20
	11	OUTDOOR RECEPIS.	360	120	1	20		11	LIBRARY COMPUTER OUTLETS	200	120	1	20
	12	OUTDOOR RECEPIS.	360	120	1	20		12	LIBRARY COMPUTER OUTLETS	200	120	1	20
	13	OUTDOOR RECEPIS.	360	120	1	20		13	LIBRARY COMPUTER OUTLETS	200	120	1	20
	14	OUTDOOR RECEPIS.	360	120	1	20		14	LIBRARY COMPUTER OUTLETS	200	120	1	20
	15	OUTDOOR RECEPIS.	360	120	1	20		15	LIBRARY COMPUTER OUTLETS	200	120	1	20
	16	OUTDOOR RECEPIS.	360	120	1	20		16	LIBRARY COMPUTER OUTLETS	200	120	1	20
	17	OUTDOOR RECEPIS.	360	120	1	20		17	LIBRARY COMPUTER OUTLETS	200	120	1	20
	18	OUTDOOR RECEPIS.	360	120	1	20		18	LIBRARY COMPUTER OUTLETS	200	120	1	20
	19	OUTDOOR RECEPIS.	360	120	1	20		19	LIBRARY COMPUTER OUTLETS	200	120	1	20
	20	OUTDOOR RECEPIS.	360	120	1	20		20	LIBRARY COMPUTER OUTLETS	200	120	1	20
	21	OUTDOOR RECEPIS.	360	120	1	20		21	LIBRARY COMPUTER OUTLETS	200	120	1	20
	22	OUTDOOR RECEPIS.	360	120	1	20		22	LIBRARY COMPUTER OUTLETS	200	120	1	20
	23	OUTDOOR RECEPIS.	360	120	1	20		23	LIBRARY COMPUTER OUTLETS	200	120	1	20
	24	OUTDOOR RECEPIS.	360	120	1	20		24	LIBRARY COMPUTER OUTLETS	200	120	1	20
	25	OUTDOOR RECEPIS.	360	120	1	20		25	LIBRARY COMPUTER OUTLETS	200	120	1	20
	26	OUTDOOR RECEPIS.	360	120	1	20		26	LIBRARY COMPUTER OUTLETS	200	120	1	20
	27	OUTDOOR RECEPIS.	360	120	1	20		27	LIBRARY COMPUTER OUTLETS	200	120	1	20
	28	OUTDOOR RECEPIS.	360	120	1	20		28	LIBRARY COMPUTER OUTLETS	200	120	1	20
L11	1	NORTHWEST CLASSROOM LIGHTING	1647	120	1	20		1	LIBRARY COMPUTER OUTLETS	200	120	1	20
	2	SOUTHWEST CLASSROOM LIGHTING	1847	120	1	20		2	LIBRARY COMPUTER OUTLETS	200	120	1	20
	3	ELEVATOR, MACH. RM., CORRIDOR & JAN. CLOS.	1847	120	1	20		3	LIBRARY COMPUTER OUTLETS	200	120	1	20
	4	TEACHERS & TOILET LIGHTING	784	120	1	20		4	LIBRARY COMPUTER OUTLETS	200	120	1	20
	5	TEACHERS, STORAGE & TOILET LIGHTING	784	120	1	20		5	LIBRARY COMPUTER OUTLETS	200	120	1	20
	6	OUTDOOR RECEPIS.	360	120	1	20		6	LIBRARY COMPUTER OUTLETS	200	120	1	20
	7	OUTDOOR RECEPIS.	360	120	1	20		7	LIBRARY COMPUTER OUTLETS	200	120	1	20
	8	OUTDOOR RECEPIS.	360	120	1	20		8	LIBRARY COMPUTER OUTLETS	200	120	1	20
	9	OUTDOOR RECEPIS.	360	120	1	20		9	LIBRARY COMPUTER OUTLETS	200	120	1	20
	10	OUTDOOR RECEPIS.	360	120	1	20		10	LIBRARY COMPUTER OUTLETS	200	120	1	20
	11	OUTDOOR RECEPIS.	360	120	1	20		11	LIBRARY COMPUTER OUTLETS	200	120	1	20
	12	OUTDOOR RECEPIS.	360	120	1	20		12	LIBRARY COMPUTER OUTLETS	200	120	1	20
	13	OUTDOOR RECEPIS.	360	120	1	20		13	LIBRARY COMPUTER OUTLETS	200	120	1	20
	14	OUTDOOR RECEPIS.	360	120	1	20		14	LIBRARY COMPUTER OUTLETS	200	120	1	20
	15	OUTDOOR RECEPIS.	360	120	1	20		15	LIBRARY COMPUTER OUTLETS	200	120	1	20
	16	OUTDOOR RECEPIS.	360	120	1	20		16	LIBRARY COMPUTER OUTLETS	200	120	1	20
	17	OUTDOOR RECEPIS.	360	120	1	20		17	LIBRARY COMPUTER OUTLETS	200	120	1	20
	18	OUTDOOR RECEPIS.	360	120	1	20		18	LIBRARY COMPUTER OUTLETS	200	120	1	20
	19	OUTDOOR RECEPIS.	360	120	1	20		19	LIBRARY COMPUTER OUTLETS	200	120	1	20
	20	OUTDOOR RECEPIS.	360	120	1	20		20	LIBRARY COMPUTER OUTLETS	200	120	1	20
	21	OUTDOOR RECEPIS.	360	120	1	20		21	LIBRARY COMPUTER OUTLETS	200	120	1	20
	22	OUTDOOR RECEPIS.	360	120	1	20		22	LIBRARY COMPUTER OUTLETS	200	120	1	20
	23	OUTDOOR RECEPIS.	360	120	1	20		23	LIBRARY COMPUTER OUTLETS	200	120	1	20
	24	OUTDOOR RECEPIS.	360	120	1	20		24	LIBRARY COMPUTER OUTLETS	200	120	1	20
	25	OUTDOOR RECEPIS.	360	120	1	20		25	LIBRARY COMPUTER OUTLETS	200	120	1	20
	26	OUTDOOR RECEPIS.	360	120	1	20		26	LIBRARY COMPUTER OUTLETS	200	120	1	20
	27	OUTDOOR RECEPIS.	360	120	1	20		27	LIBRARY COMPUTER OUTLETS	200	120	1	20
	28	OUTDOOR RECEPIS.	360	120	1	20		28	LIBRARY COMPUTER OUTLETS	200	120	1	20

EXPLANATION OF MOTOR CONTROL SCHEDULE C-7			
PANEL	LOCATION	BRANCH BUS	REMARKS
L 9A	MECHANICAL	208/3/60 100 100	14
L 10	NEW 102	208/3/60 100 MLO	8 42 ①
L 11	NEW 202	208/3/60 100 MLO	8 42
1G	COMPUTER LAB	208/3/60 100 MLO	38/4

SCHEDULE OF PANELS A-7			
PANEL	LOCATION	BRANCH BUS	REMARKS
20*	20A GFI C/B		
①	SUBFEED LUGS		
②	ISOLATE GROUND BUSS, OVERSIZED NEUTRAL BUSS - MINIMUM 200A		

MOTOR CONTROL SCHEDULE G-7
NONE


EXPLANATION OF MOTOR CONTROL SCHEDULE C-7
NONE

SCHEDULE OF PANELS A-7
NONE

MOTOR CONTROL SCHEDULE G-7
NONE


EXPLANATION OF MOTOR CONTROL SCHEDULE C-7
NONE

SCHEDULE OF PANELS A-7
NONE



EXTERIOR WALL SECTION (TYPICAL)

SCALE: 1/2" = 1'-0"




DOOR TYPES

NTS.


WINDOW SCHEDULE (ALL WINDOWS COMPLETE W/SCREEN)

TAG	SIZE	TYPE	GLASS	COMMENT
A	8'-0" x 4'-0"	SLIDING	1" INSUL.	FIXED CTR.
B	2'-0" x 4'-0"	DH	1" INSUL.	50 SF MIN. EGRESS WINDOW MIN. DIMS: 20" W. X 24" H.
C	5'-0" x 4'-0"	SLIDING	1" INSUL.	



ROOF FRAMING PLAN

SCALE: 1/8" = 1'-0"




KITCHEN ELEVATIONS

SCALE: 1/4" = 1'-0"

DOOR SCHEDULE: (ALL UNITS PREHUNG / PREFIT COMPLETE W/HARDWARE)

TAG	LOCATION	SIZE	THK.	DOOR MAT'L	FRAME MAT'L	TYPE	GLASS	DOOR	W/STRIP / HOLD	COMMENT
1	ENTRY	3'-0" - 6'-0"	1 3/4"	HM	WD	A	5/8" INSUL	ENTRY	INTEGRAL	BIFOLD
2	CLOSET	2'-0" - 6'-0"	1 3/8"	HCU	WD	B				
3	BEDRM'S / BATHS	2'-6" - 6'-0"	1 3/8"	HCU	WD	B		PRIVACY		
4	CLOSET	2'-4" - 6'-0"	1 3/8"	HCU	WD	B		PASSAGE		
5	H.W. HTR.	1'-0" - 6'-0"	1 3/8"	HCU	WD	B		PASSAGE		
6	CLOSET	(2) 3'-0" - 6'-0"	1 3/8"	HCU	WD	B				SLIDING
7	CLOSET	(2) 2'-6" - 6'-0"	1 3/8"	HCU	WD	B				SLIDING
8	CLOSET	3'-0" - 6'-0"	1 3/8"	HCU	WD	B				BIFOLD
9	SLIDER	6'-0" - 6'-0"	1 3/4"	HM	WD	A	5/8" INSUL.	ENTRY	INTEGRAL	




INSULATED HEADER DETAIL

NTS.








DOOR FRAME TYPES

SCALE: 3/4" = 1'-0"



DETAIL (PLAN AT FIREWALL)

SCALE: 3/4" = 1'-0"



- CONSTRUCTION NOTES:**
- 1 AREA OF ASSISTANCE SIGN BY G.C., E.G. TO INSTALL AND WIRE TO EXIT LIGHT CKT.
 - 2 RELOCATE EXISTING EXIT SIGN AS INDICATED.
 - 3 REMOVE EXISTING DOOR HOLDER
 - 4 REMOVE CIRCUITRY FOR EXISTING BATTERY UNIT AT CEILING
 - 5 AREA OF ASSISTANCE PHONE LOCATE IN RECESSED WALL BOX WITH DOOR EQUIP. DOOR WITH SPRING CATCH, LABEL EMERGENCY PHONE TO SCHOOL OFFICE.
- △
- 6 L-10 TO MDP, 296 FEET, RUN IN CEILING WITH HEATING PIPING
 - 7 L-11 TO MDP, 317 FEET, RUN IN CEILING WITH HEATING PIPING
 - 8 ELEVATOR TO MDP, 352 FEET, RUN IN CEILING WITH HEATING PIPING
 - 9 INTERLOCKS FOR ELEVATOR & SPRINKLER SYSTEM

HAZAF
CONSULTANTS IN ENGINEERING
PO BOX 226, CLIFTON PARK, NY
12065

CWVG
CATALDO, WATERS and GRIFFITH
ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305


ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006

Drawing Title
FIRST & SECOND FLOOR PLAN; ADDITION UTILITIES


Designed	Project No.
Drawn	Scale
Checked	AS NOTED
Reviewed	Drawing No.
Date	11-11-94

E-2


ROBERT C. KURZON AIA ARCHITECTS 80 STATE STREET ALBANY, NEW YORK 12207	REVISION date	no.	1	SITE PLAN	GRANT LAKE CHENANGO COUNTY, VIRGINIA	by	scale	issue	no.	date
						chd.	rvsd.	no.	date	



SITE PLAN
1" = 20' - 0"




TILE FIELD DETAIL
1/2" = 1' - 0"






HAUNCH DETAIL
1/2" = 1' - 0"

FOUNDATION PLAN
1/4" = 1' - 0"



CONSTRUCTION NOTES:

- SEE CONTROL SCHEMATIC A-12 THIS SHEET.
- EQUIP ODD FIXTURES WITH ONE 2-LAMP AND ONE 1-LAMP BALLAST.
- SEE SCHEMATIC A-3 SHEET E-2.
- SEE SCHEMATIC A-6 SHEET E-2.
- SEE SCHEMATIC A-9 SHEET E-2.
- REMOVE EXISTING WALL-MOUNTED FIXTURE AND ASSOCIATED CIRCUITRY. MAINTAIN CIRCUITRY TO EXISTING FIXTURES, ETC. TO REMAIN.
- RELOCATE SWITCH FOR CORRIDOR LIGHTING. REMOVE SWITCH FOR EXTERIOR LIGHTS TO BE REMOVED.
- EXTEND CIRCUIT TO NEW LIGHTING FIXTURE AS INDICATED.
- REWIRE & REINSTALL EXISTING FIXTURE AS INDICATED.
- EMERGENCY LIGHTING BATTERY UNIT WITHOUT HEADS. WIRE AS INDICATED & PER MANUFACTURER'S RECOMMENDATIONS.
- EMERGENCY LIGHTING BATTERY UNIT WITH TWO (2) HEADS/ WIRE AS INDICATED & PER MANUF. REC. PROVIDE WIRE GUARD.
- REMOVE DUAL HEAD EMERGENCY LIGHT. WIRE TO BATTERY PACK PER MANUF. REC. AND AS INDICATED.
- RELOCATE EXISTING FIXTURE AS INDICATED (COBRA HEAD TYPE).
- WIRE TO TIME CLOCK. SEE A-6 SHEET E-2.



MARK	MAKE	MODEL	VOLTS	WATTS	LAMP NO./FIXT.	REMARKS
A	STONCO	VWXL110C	120	100	1	CAST GUARD.
FA	WILLIAMS	1222-RWKA125	120	183	3	SPLIT WIRE IN TANDEM PAIRS - WATAGE IS FOR 2 FIXTURES W/ TOTAL OF 3 2-LAMP BALLAST. ELECTRONIC BALLAST.
FA1	WILLIAMS	1222-RWKA125	120	92	3	ELECTRONIC BALLAST.
FB	WILLIAMS	2922-KA	120	61	2	ELECTRONIC BALLAST.
FC	KIRLIN	96617-45-46-61	120	36	2	HPF BALLAST
FC1	KIRLIN	96617-46-61-SM	120	36	2	HPF BALLAST SURFACE MOUNT; COLOR AS SELECTED
FD	WILLIAMS	8222	120	61	2	ELECTRONIC BALLAST.
FE	WILLIAMS	1262-RWKA125	120	84	4	ELECTRONIC BALLAST.
FF	TERON	E226-P-H	120	36	2	HPF BALLAST.
FG	WILLIAMS	2122-IM	120	61	2	ELECTRONIC BALLAST.
FH	WILLIAMS	EPG-R27RWKA-125	120	61	2	TO MATCH EXISTING.
M1	KIRLIN	SS-51277-24-43 (35W)-45-46-FR	120	40	1	HPF BALLAST.
M2	STONCO	PAR250LX	120	300	1	HPF BALLAST EQUIP WITH MOUNTING BRACKET ARM.
EXITS	LITHONIA	WILES SERIES	120	65	1	SEE SHEET E-2 FOR LOC. ARROWS & MOUNTING AS IND. EQUIP W/ BATTERY BACK-UP
EMERG. LGT. BATT. PACK REMOTE LAMP	EXIDE	E200	120/12	150	H1212	
	EXIDE	H1212	12	24	H1212	

MARK	MAKE	MODEL	VOLTS	WATTS	LAMP NO./FIXT.	REMARKS
A-10	NONE					
A-11	NONE					

CLASSROOM LIGHTING CONTROL SCHEMATIC A-12

LEVITON 6779 OR EQUIVALENT

WIRE ADDITIONAL SENSORS IN PARALLEL

TO OUTER LAMP IN ROW FIXTURES NEAR WINDOWS

TO INNER LAMP ALL ROWS

TO OUTER LAMP IN OTHER TWO ROWS FIXTURES

LOW VOLTAGE RACEWAY REC.

WALL SWITCHES

OUTLET BOX W/ COVER PLATE - TYPE PUNCHING AS DIRECTED.

FINISHED FLOOR

12" OR AS OTHERWISE INDICATED IN CLASSROOMS TO BE AT INDICATED HEIGHT.

SYMBOL LEGEND	A-4	2	3	4	5	6	7	8	9	10	11	12	13	14
EXISTING TO REMAIN														
EXISTING TO BE REMOVED														
NEW WORK														
DOWNLIGHT														
FLUORESCENT TRIPPER														
FLUORESCENT STRIP OR AS INDICATED														
WALL MOUNTED														
JUNCTION BOX														
TELEVISION OUTLET - SEE DETAIL														
SPECIAL OUTLET, SEE DETAIL														
DATA OUTLET, SEE DETAIL														
3-WAY SWITCH, MOUNT 48" AFF.														
SWITCH WITH MOTION SENSOR														
MOTION SENSOR														
RELAY MODULE														
UNSWITCHED CIRCUITRY														
SWITCHED CIRCUITRY														
HOME RUN, A-PANEL, B-CIRCUIT NO.														
NO. CONDUCTORS (EXCLUDING GROUND)														
TELEPHONE OUTLET, MOUNT 18" AFF.														
COUNTER MOUNTED TELEPHONE OUTLET, MOUNT 4" ABOVE COUNTER BACKSPASH														
WALL MOUNTED TELEPHONE OUTLET, MOUNT 48" A.F.F.														
INTERCOM PHONE														
CLOCK														

HA2F CONSULTANTS IN ENGINEERING
 12065 CUFION PARK, NY
 (518) 877-8566

CWGW CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
 120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT
 ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
 SED# 01-02-01-04-0-004-006

Project No. 94036.00
 Scale NONE
 Drawing No. E-1


DATE: TV; AND TELEPHONE OUTLET DETAIL A-11
 CLASSROOM LIGHTING CONTROL SCHEMATIC A-12
 FIXTURE SCHEDULE A-10
 NONE


NOT FOR CONSTRUCTION

by	app.
scale	issue
ckcd.	no.
rvsd.	date

no.	REVISION	date

ROBERT C. KURZON AIA
ARCHITECTS
80 STATE STREET
ALBANY, NEW YORK 12207







<p>CONSTRUCTION NOTES:</p> <ol style="list-style-type: none"> FROM FIRST FLOOR - CONNECT TO UNIT. SEE PIPING SCHEMATICS FOR FIT-UP. REFERS TO UNIT ON SECOND FLOOR. OFFSET FOR CLARITY. DROP DOWN IN METAL CHASE (BY G.C.) TO UNIT BELOW. RUN PIPING TO UNIT IN RADIATION ENCLOSURE. FINISH ON ENCLOSURE TO MATCH UNIT FINISH EXACTLY. RUN PIPING TO UNIT IN PIPE SPACE BEHIND BOOKCASES. PROVIDE ACCESS DOOR IN CHASE FOR ACCESS TO FIRE DAMPER. COORDINATE DUCT LOCATION WITH PLUMBING IN SAME CHASE. SEE DETAIL D-14 SHEET H-3. ADJUST GRILLE LOCATION TO AGREE WITH BLOCK COURSING. DROP DOWN BELOW BEAM IN CHASE. RISE UP TO ABOVE CEILING IN CLASSROOM. G.C. TO PROVIDE SOFFIT AREA TO CONCEAL PIPING. SEE DETAILS ON ARCH. DWGS. KEEP PIPING TIGHT TO WALLS. DROP DOWN AND RUN BELOW EXISTING BEAM. THEN DOWN IN WALL TO CLH. G.C. TO PROVIDE SOFFIT AREA TO CONCEAL PIPING. SEE DETAILS ON ARCH. DWGS. KEEP PIPING TIGHT TO WALLS. RUN PIPING THRU 6" X 12" HOLE IN BEAM AT 1/4 POINT BY G.C. SEE STRUCTURAL DWGS. RUN PIPING THRU 4" X 8" HOLE IN BEAM AT 1/4 POINT BY G.C. SEE STRUCTURAL DWGS. RUN PIPING THRU 5" X 15" HOLE IN BEAM AT 1/4 POINT. ADJACENT TO PLUMBING PIPING. COORDINATE. HOLE TO BE PROVIDED BY G.C. SEE STRUCTURAL DWGS. BOOKCASE BY H.C. LENGTH AS INDICATED. 		<p>HA2F CONSULTANTS IN ENGINEERING PO BOX 226, CLIFTON PARK, NY 12065</p>		<p>CWCG CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C. 120 ERE BOULEVARD, SCHENECTADY, N.Y. 12305</p>		<p>ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT JR./SR. HIGH SCHOOL SED# 01-02-01-04-0-004-006 Drawing Title FIRST & SECOND FLOOR PLAN - ADDITION SYMBOL LEGEND</p>		<p>Project No. 940536.00 Scale AS NOTED Drawn K.S. ALLEN Checked WDF Reviewed WDF Date 11-11-94</p>		<p>Project No. 940536.00 Scale AS NOTED Drawn K.S. ALLEN Checked WDF Reviewed WDF Date 11-11-94</p>			
<p>SECOND FLOOR PLAN 1/8" = 1'-0"</p>		<p>E-14 1/8" = 1'-0"</p>		<p>C-14 NONE</p>		<p>A-14 NONE</p>		<p>KEY PLAN NONE</p>		<p>A-11 NONE</p>		<p>11</p>	
<p>PIPING DETAIL NONE</p>		<p>E-7 1/8" = 1'-0"</p>		<p>A-7 1/2" = 1'-0"</p>		<p>A-3 1/15" = 1'-0"</p>		<p>SECTION 'A' NONE</p>		<p>8</p>		<p>10</p>	
<p>FIRST FLOOR PLAN 1/8" = 1'-0"</p>		<p>E-7 1/8" = 1'-0"</p>		<p>A-7 1/2" = 1'-0"</p>		<p>A-3 1/15" = 1'-0"</p>		<p>SECTION 'A' NONE</p>		<p>8</p>		<p>10</p>	
<p>PARTIAL FIRST FLOOR PLAN 1/15" = 1'-0"</p>		<p>E-7 1/8" = 1'-0"</p>		<p>A-7 1/2" = 1'-0"</p>		<p>A-3 1/15" = 1'-0"</p>		<p>SECTION 'A' NONE</p>		<p>8</p>		<p>10</p>	
<p>SYMBOL LEGEND</p> <ul style="list-style-type: none"> EXISTING TO REMAIN EXISTING TO BE REMOVED NEW WORK CALLOUT, TYPE AS NOTE SUPPLY REGISTER W/FLOW DIRECTION RETURN/EXHAUST REGISTER DUCTWORK - SIZE SHOWN IS DIMENSION "X" DUCT UP - SUPPLY DUCT DOWN - RETURN VOLUME DAMPER THERMOSTAT ACCESS DOOR EXT. WATER SUPPLY HOT WATER SUPPLY HWS - HOT WATER RETURN LWR - LOW PRESSURE STEAM VERTICAL FIRE DAMPER & ACCESS DOOR (VERTICAL DUCT) ACCESS DOOR (HORIZONTAL DUCT) FIRE RATED OPENING PROTECTIVE FURNISHED AS PART OF REGISTER OR GRILLE OR DAMPER. SEE SCHEDULES. 		<p>SYMBOL LEGEND</p> <ul style="list-style-type: none"> PUMP DISCHARGE LOW PRESSURE RETURN GLOBE VALVE BUTTERFLY VALVE BALL VALVE CHECK VALVE MOTORIZED CONTROL VALVE - 2-WAY MOTORIZED CONTROL VALVE - 3-WAY CAPPED PIPE TEE DOWN TEE UP ELBOW UP ELBOW DOWN ELBOW PLAN REDUCER ECCENTRIC REDUCER UNION AIR VENT TEMP. GAUGE PRESSURE GAUGE TEMPERATURE CONTROL FUNCTIONALITY RELATIONSHIP 		<p>KEY PLAN</p>		<p>KEY PLAN</p>		<p>KEY PLAN</p>		<p>KEY PLAN</p>		<p>KEY PLAN</p>	

no.	REVISION	date


by	scale	issue	date




WEST ELEVATION
 1/4" = 1'-0"



EAST ELEVATION
 1/4" = 1'-0"



NORTH ELEVATION
 1/4" = 1'-0"



SOUTH ELEVATION
 1/4" = 1'-0"

CONSTRUCTION NOTES:

① RUN THROUGH 5'X15' HOLE IN BEAM - SEE STRUCTURAL DRAWINGS.



HA2F
CONSULTANTS IN ENGINEERING
PO BOX 226, CLIFTON PARK, NY
12065


CWCG CATALDO, WATERS and GRIFFITH
ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION
FOR THE
BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT
JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006
Drawing Title

PARTIAL PLAN - ADDITION FIRST FLOOR & SECOND FLOOR


Seal	Designed WBF	Project No. 94036.00
	Drawn KSN/NFB	Scale AS NOTED
	Checked WBF	Reviewed WBF
	Date 11-11-94	Drawing No. P-1

NOT FOR CONSTRUCTION




SECOND FLOOR PLAN

E-14
1/8" = 1'-0"




KEY PLAN

A-14
NONE




FIRST FLOOR PLAN

E-7
1/8" = 1'-0"



DETAIL - PIPING

A-8
NONE




PARTIAL FIRST FLOOR PLAN

A-4
1/16" = 1'-0"


SYMBOL EXPLANATION

	DOMESTIC COLD WATER
	DOMESTIC HOT WATER
	DOMESTIC HOT WATER RETURN
	PIPLINE - TYPE AS NOTED
	GAS (NATURAL OR PROPANE AS NOTED)
	SANITARY VENT
	ABOVE GRADE SANITARY
	BELOW GRADE SANITARY
	ABOVE GRADE STORM WATER
	BELOW GRADE STORM WATER
	FLOOR DRAIN
	IN LINE CLEANOUT
	SANITARY WYE
	ROOF DRAIN
	VENT THRU ROOF
	ELBOW UP
	ELBOW DOWN
	TEE DOWN
	TEE UP
	PIPELINE STRAINER
	LAWN HYDRANT
	GATE VALVE
	DRAIN VALVE
	CHECK VALVE
	BLEEDING VALVE
	SOLENOID VALVE
	GAS COCK OR BALANCE VALVE
	PLUMBING RISER NO.
	CONSTRUCTION NOTE NO.


no.	REVISION	date




SECTION
 1/4" = 1'-0"




SECTION
 1/4" = 1'-0"



WALL SECTION (TYPICAL COMPOSITE)
 3/4" = 1'-0"




CORNER DETAIL (TYP)
 3/4" = 1'-0"



1 TYPICAL REINFORCING DETAILS FOR MASONRY WALLS
5203 N1:5

- NOTES:**
- WALL REINFORCING APPLIES TO ALL CMU WALLS, BOTH INTERIOR AND EXTERIOR.
 - WORK WITH DETAILS 45203 AND 5203 FOR ADDITIONAL REINFORCING INFORMATION.
 - MINIMUM WALL REINFORCING FOR EXTERIOR WALLS IS #4 @ 48" O.C. VERT.



- NOTES:**
- LOCATION OF BOND BEAM MAY BE POSITIONED DOWN ONE COURSE TO ALL AROUND BUILDING. REFER TO ARCH. DWGS AS01 & AS02

2 SECTION AT ENTRANCE
5203 SCALE: 3/4" = 1'-0"

- NOTES:**
- CONTRACTOR HAS OPTION TO USE ALTERNATE TOP SUPPORT CONNECTION DETAIL THAN THE VERTICAL SLIP CLIP WITH APPROVAL FROM ENGINEER.

3 PANEL SUPPORT SECTION
5203 SCALE: 3/4" = 1'-0"

- NOTES:**
- CONTRACTOR HAS OPTION TO USE ALTERNATE TOP SUPPORT CONNECTION DETAIL THAN THE VERTICAL SLIP CLIP WITH APPROVAL FROM ENGINEER.

RB Ryan-Biggs Associates, P.C.
 291 River Street
 Troy, New York 12180
 (518) 272-6266

CWGW CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
 120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
 SED# 01-02-01-04-0-004-006

MISCELLANEOUS STEEL DETAILS & MASONRY REINFORCING DETAILS

Designed	MCM	Project No.	01020401
Drawn	SJW	Scale	AS NOTED
Checked	MCM	Drawing No.	S203
Reviewed	CJZ		
Date	11-11-94		


NOT FOR CONSTRUCTION



KITCHEN ELEVATIONS

1/2" = 1' - 0"

SIZE	TYPE	GLASS	COMMENTS
A	3'-0" X 3'-0" THERMAL BREAK ALUMINUM	5/8" INSULATED	
B	3'-0" X 3'-0" D.O.	D.O.	
C	4'-0" X 4'-0" D.O.	D.O.	
D	4'-0" X 5'-0" D.O.	D.O.	
E	5'-0" X 5'-0" D.O.	D.O.	
F	6'-0" X 4'-0" D.O.	1" INSULATED	
G	6'-0" X 5'-0" D.O.	1" INSULATED	
H	6'-0" X 6'-8" D.O.	1" TEMP. INSUL.	SLIDING GLASS DOORS
J	3'-6" X 2'-6" D.O.	D.O.	ELEC. OPERATION





DOOR TYPES


NO SCALE

6/5

STAIR DETAIL
1/2" = 1' - 0"



7/5




RAILING & LADDER DETAIL

1/2" = 1' - 0"


4/5

WINDOW DETAIL

3/4" = 1' - 0"




4/5



3/5

DOOR FRAME TYPES

3/4" = 1' - 0"



2/5

HEAT SINK DETAIL

1/2" = 1' - 0"

app.	scale	issue	no.	date
by	scale	ckd.	no.	date
rsd.				

LAKE HOUSE
GRANT LAKE
CHENANGO COUNTY, VIRGINIA

SCHEDULES & DETAILS



5

ROBERT C. KURZON AIA
ARCHITECTS
80 STATE STREET
ALBANY, NEW YORK 12207



no.	REVISION	date

no.	REVISION	date

by	app.	no.	date
scale	issue		
chd.			
rvsd.			





NOTE:
 ALL LUMBER TO BE PRESSURE TREATED.




SCHEDULE OF DOORS


NO.	SIZE	THK.	DOOR MATL. TYPE	FRAME MATL. TYPE	GLASS	LOCKSET	COMMENTS
001	2'-8" X 6'-8"	1 3/8"	WD. C	WD. A		GLASSROOM	
002	2'-0" X 6'-8"	1 3/8"	WD. C	WD. A		PRIVACY	
003	PR. 2'-0" X 6'-8"	1 3/8"	WD. D	WD. A		PASSAGE RH. DUMMY TRIM L.H.	
101	3'-0" X 6'-8"	1 3/4"	HM. A	WD. A	1" INSL.	ENTRY	1'-8" SIDELIGHT
102	3'-0" X 6'-8"	1 3/4"	HM. B	WD. A		ENTRY	
103	PR. 2'-4" X 6'-8"	1 3/8"	WD. D	WD. B		NONE	PI-PASSING HDWARE
104	2'-6" X 6'-8"	1 3/8"	WD. C	WD. D		PRIVACY	
105	PR. 2'-6" X 6'-8"	1 3/8"	WD. D	WD. D		PASSAGE RH. DUMMY TRIM L.H.	
106	2'-0" X 6'-8"	1 3/8"	WD. C	WD. D		PRIVACY	
107	(4) 1'-0" X 6'-8"	1 3/8"	WD. E	WD. D		NONE	PI-FOLDING HDWARE
108	2'-0" X 6'-8"	1 3/8"	WD. C	WD. D		PRIVACY	
109	2'-0" X 6'-8"	1 3/8"	WD. C	WD. D		PRIVACY	
110	2'-6" X 6'-8"	1 3/8"	WD. C	WD. D		PRIVACY	
111	2'-0" X 6'-8"	1 3/8"	WD. C	WD. D		PASSAGE	
112	2'-6" X 6'-8"	1 3/8"	WD. C	WD. D		PRIVACY	




1 ROOF SECTION
SCALE: 3/4\"/>



3 SCHEMATIC STAIR FRAMING PLAN
SCALE: N.T.S.



4 EDGE DETAIL AT FIRE WALL
SCALE: 3/4\"/>



5 FOLDING PARTITION CONNECTION DETAIL
SCALE: 1 1/2\"/>

KEY PLAN

1" = 120' 0"

RB Ryan-Biggs Associates, P.C.
291 River Street
Troy, New York 12180
(518) 272-6266

CWGW CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006

ROOF FRAMING PLAN & DETAILS

Designed	MCM	Project No.	01020401
Drawn	BAM	Scale	AS NOTED
Checked	MCM	Drawing No.	S201
Reviewed	CJZ	Date	11-11-94

NOT FOR CONSTRUCTION


ROOF FRAMING PLAN

SCALE: 1/8" = 1'-0"

- NOTES:
1. TOP OF STEEL ELEV. = 23'-9" ABOVE REFERENCE TYPICAL UNLESS NOTED (±)
 2. R.D. INDICATES ROOF DRAIN FRAMING PLAN.
 3. SEE 1/5201 FOR ELEVATOR ROOF FRAMING PLAN.
 4. R.V. INDICATES ROOF VENT. PROVIDE 4x4x5/16 FRAME AROUND VENT. COORDINATE SIZE & LOCATION WITH MECHANICAL CONTRACTOR.


NOTE: BOND BEAM BLOCK TO BE CUT AS REQ'D TO MAINTAIN GAP.

NOTES: COORDINATE HOLES SIZE AND SPACING IN BOTTOM FLANGE WITH DOOR MANUFACTURER.




FIREPLACE PLAN
3/4" = 1'-0"

5/7




CORRUGATED ROOFING DETAIL
1/2" = 1'-0"

7/7




FIREPLACE SECTION
3/4" = 1'-0"

4/7




RIDGE DETAIL
1/2" = 1'-0"

6/7



ROOF DETAIL
1/2" = 1'-0"

1/7



SKYLIGHT DETAIL
3/8" = 1'-0"

2/7

by	app.	7
scale	issue	
chkd.	no.	
rvsd.	date	

LAKE HOUSE
GRANT LAKE
CHEMANGO COUNTY, VIRGINIA

DETAILS

ROBERT C. KURZON AIA
ARCHITECTS
80 STATE STREET
ALBANY, NEW YORK 12207

no.	REVISION	date

KEY PLAN

RYAN-BIGGS ASSOCIATES, P.C.
291 River Street
Troy, New York 12180
(518) 272-6266

CWGW
CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006

SECOND FLOOR FRAMING PLAN & DETAILS













Project No. 01020401
Scale AS NOTED
Drawing No. S200

Designed MCM
Drawn BAM
Checked MCM
Reviewed CJZ
Date 11-1-94

No. REVISIONS/SUBMISSIONS _____ Date _____

SEE LINTEL NOTES FOR ADDITIONAL INFORMATION

MARK	MATERIAL	TYPE	MAS. OPNG.	REMARKS
L1	WT8X13	I	SEE ARCH.	ATTACH ONE END TO COL. SEE 1/5200
L2	WT8X13	I	-	END BEARING BOTH ENDS CONTINUOUS W/CENTER SUPPORT ON T.S. 4X4
L3	WT8X13	I	-	AT ALL BELOW WINDOW UNIT VENTILATOR OPENINGS.
L4	WT4X9	I	-	LINTEL IN FIREWALL WELD BOT. FT. TO ANGLES.
L5	1/4"X9 1/2 CONT. BOT. FT.	I	-	IN EXIST. BLDG. WALL
L6	(2) 3/4"X4X5/16	JL	-	AT CAFETERIA HVAC UNIT WALL OPENINGS. COORDINATE WITH G-7/HS AND A103 (2 LOCATIONS)
L7	(3) 3/4"X4X5/16	JL	-	-




Northwest Land Park: Urban Courts

City of Sacramento, California

Symbol Legend

- FLOOR ELEVATION CHANGE
- KEYNOTE SYMBOL
- REVISION SYMBOL (CLOUD REVISION)
- INTERIOR ELEVATION ELEVATION IDENTIFICATION SHEET WHERE ELEVATION OCCURS



Graphic Legend

- SAND/MORTAR/PLASTER
- CONCRETE
- WOOD, FRAMING
- WOOD, BLOCKING
- WOOD, FINISH
- PLYWOOD
- 2x4 WALL, STANDARD CONSTRUCTION
- 2x6 WALL, STANDARD CONSTRUCTION
- 2x8 WALL, STANDARD CONSTRUCTION
- ARCH SOFFIT HEADER
- FLAT SOFFIT HEADER OR DROP CEILING
- BACKING FOR FIXTURE ATTACHMENT
- CONTINUOUS 1-HOUR WALL ASSEMBLY

Project Information

Proposed Use: Single Family Attached Duplex
 Occupancy: VB
 Building Type: R3 / U
 Fire Sprinklers: Required per CRC R313.2
 Code Compliance: See General Notes
 Stories: 4 (Table 503 and Section 504.2)
 Building Height: ±43'-10"


JD+A Team

JD+A Job Number: 14060
 Project Designer: SR, MH
 Project Manager: SS
 Project Team: SN, TL
 Checked By: SS

Area Tabulation

Floor Area: Unit A	
LIVING AREA:	553.00 FT.
SECOND FLOOR LIVING:	553.00 FT.
TOTAL LIVING AREA:	553.00 FT.
OTHER AREAS:	
GARAGE:	
COVERED BALCONY:	245.00 FT.
9" SLO. FT.	97.50 FT.
Floor Area: Unit B	
LIVING AREA:	128.50 FT.
800 FLOOR BERRY STAIRS:	131.50 FT.
SECOND FLOOR STAIRS:	131.50 FT.
THIRD FLOOR STAIRS:	21.50 FT.
FOURTH FLOOR LIVING:	685.00 FT.
TOTAL LIVING AREA:	2133.00 FT.
OTHER AREAS:	
GARAGE:	
24" SLO. FT.	224.50 FT.
8" SLO. FT.	8.50 FT.
ROOF DECK:	130.50 FT.

Vicinity Map



Location: Broadway and 5th Street
 Jurisdiction: City of Sacramento

Project Directory

Owner:
 NORTHWEST LAND PARK, LLC
 2555 3rd STREET, #113
 SACRAMENTO, CA 95818
CONTACT: KEVIN SMITH
 PHONE: 916.838.6651
 EMAIL: KMG@GURES@COMCAST.NET

Builder:
 BARDIS HOMES
 10630 MATHER BLVD
 MATHER, CA 95655
CONTACT: RACHEL BARDIS
 PHONE: 916.313.3061
 EMAIL: RACHEL@BARDISHOMES.COM

Architect:

JEFFREY DEMUIRE + ASSOCIATES
 5905 GRANITE LAKE DRIVE, SUITE 140
 GRANITE BAY, CA 95746
CONTACT: SHAWN SIDENER
 PHONE: 916.783.3700
 FAX: 916.783.3711
 EMAIL: SSIDENER@JDAARCH.COM

Structural Engineer:

O'CONNOR FREEMAN & ASSOCIATES, INC.
 225 30TH STREET, SUITE 201
 SACRAMENTO, CA 95816
CONTACT: KARL FREEMAN
 PHONE: 916.441.5721
 EMAIL: KFREEMAN@OFAINC.NET

Energy Consultant:

VALLEY DUCT TESTING
 2216 SIERRA MEADOWS DRIVE
 ROCKLIN, CA 95677
CONTACT: BEN WRIGHT
 PHONE: 916.624.2092
 EMAIL: BEN@VALLEYDUCTTESTING.COM

Mechanical Engineer:

DEAL MECHANICAL - (PREPARED BY VALLEY DUCT TESTING)
 2557 B ALBATROSS WAY
 SACRAMENTO, CA 95815
CONTACT: BOB DEAL
 PHONE: 916.927.4500
 EMAIL: DEAL@SBCCGLOBAL.NET

Fire Sprinkler:

FOOTHILL FIRE PROTECTION
 4000 ALVIS COURT
 ROCKLIN, CA 95677
CONTACT: DILLON GRAY
 PHONE: 916.633.3882
 EMAIL: DILLON@FFPROTECTION.COM

Sheet Index

Architectural	Structural	Energy Calculations	Mechanical	Fire Sprinklers
A1.0 COVER SHEET	SN.1 GENERAL STRUCTURAL NOTES & DETAILS	T24-0 MFR MANDATORY MEASURES	M-1.0 HVAC SCHEDULE AND DETAILS	FP-1 SITE PLAN & DETAILS
A1.1 CODE COMPLIANCE	SN.2 GENERAL STRUCTURAL NOTES & DETAILS	T24-1 2013 ENERGY COMPLIANCE - URBAN COURTS BLD 1 - UNIT A (WINDOW OPTION)	M-2.0 HVAC LAYOUT - URBAN COURTS BLD-1 PLAN A	FP-2 FIRE SPRINKLER PLAN
A1.2 PHASE 1 - 1-HOUR FIRE PROTECTION	SN.3 GENERAL STRUCTURAL NOTES & DETAILS	T24-1 2013 ENERGY COMPLIANCE - URBAN COURTS BLD 1 - UNIT B (WINDOW OPTION)	M-3.0 HVAC SCHEDULE AND DETAILS	
A2.1 DIMENSION CONTROL PLAN	SN.4 GENERAL STRUCTURAL NOTES & DETAILS	T24-1W 2013 ENERGY COMPLIANCE - URBAN COURTS BLD 1 - UNIT B (WINDOW OPTION)	M-4.0 HVAC LAYOUT - URBAN COURTS BLD-1 PLAN B	
A3.1 FIRST FLOOR PLAN	S7.1 FOUNDATION PLAN			
A3.2 SECOND FLOOR PLAN	S7.2 SECOND FLOOR FRAMING			
A3.3 THIRD FLOOR PLAN	S7.3 THIRD FLOOR/ROOF FRAMING			
A3.4 FOURTH FLOOR PLAN	S7.4 FOURTH FLOOR/ROOF FRAMING			
A4- INTERIOR ELEVATIONS	S7.5 ROOF FRAMING			
A5.010 EXTERIOR ELEVATIONS "A" (FRONT/REAR)	PTI STRUCTURAL DETAILS			
A5.012 ROOF PLAN "A"	SD1 STRUCTURAL DETAILS			
A5.050 EXTERIOR ELEVATIONS "A4" TRIM (FRONT/REAR)	SD2 STRUCTURAL DETAILS			
A5.051 EXTERIOR ELEVATIONS "A4" TRIM (RIGHT/LEFT)	SD3 STRUCTURAL DETAILS			
A5.052 ROOF PLAN "A4" TRIM	SWSB1 SIMPSON STRONGWALL FRAME DETAILS			
A5.4 BUILDING SECTIONS (ELEVATION "A")	SWSB2 SIMPSON STRONGWALL FRAME DETAILS			
A6.010 EXTERIOR ELEVATIONS "B" (FRONT/REAR)				
A6.011 EXTERIOR ELEVATIONS "B" (RIGHT/LEFT)				
A6.012 ROOF PLAN "B"				
A7.010 EXTERIOR ELEVATIONS "C" (FRONT/REAR)				
A7.011 EXTERIOR ELEVATIONS "C" (RIGHT/LEFT)				
A7.012 ROOF PLAN "C"				
A7.050 EXTERIOR ELEVATIONS "C4" TRIM (FRONT/REAR)				
A7.051 EXTERIOR ELEVATIONS "C4" TRIM (RIGHT/LEFT)				
A7.052 ROOF PLAN "C4" TRIM				
E.1 UTILITY PLAN, FIRST & SECOND FLOORS				
E.2 UTILITY PLAN, THIRD & FOURTH FLOORS				
AD1 EXTERIOR DETAILS - ROOF				
AD2 EXTERIOR DETAILS - SOFFIT & BRACES				
AD3 EXTERIOR DETAILS - WINDOWS				
AD4 EXTERIOR DETAILS - DOORS				
AD5 EXTERIOR DETAILS - MATERIAL				
AD6 DETAILS				
FP1 DETAILS - FIRE PROTECTION				

General Notes

- All work to conform to the following California Codes and Regulations:
 - 2013 California Building Code
 - 2013 California Residential Code Part 2.5
 - 2013 California Mechanical Code Part 4
 - 2013 California Energy Code Part 6
 - 2013 Building Energy Efficiency Standards
 - 2013 National Fire Protection Association 13D
- All grade elevations are to be field verified.
- Slopes between grade elevations shall be uniform.
- Refer to civil site plan for site drainage information. Surface water shall drain away from foundation walls. The grade shall fall a minimum of 6 inches within the first 10 feet (5%). (CRC R401.3)
 Exception: Where lot lines, walls, slopes, or other physical barriers prohibit 6 inches of fall within 10 feet, drains or swales shall be constructed to ensure drainage away from the structure. Impervious surfaces within 10 feet of the building foundation shall be sloped a minimum of 2% away from the building.
- Floor elevations are to top of concrete slab, or top of subfloor unless noted otherwise.
- Indicated dimensions take precedence. DO NOT SCALE THE DRAWINGS.
- All dimensions are to face of stud, face of concrete, centerline of window, and centerline of door or other opening unless noted otherwise.
- In the event certain features of the construction are not fully shown on the construction documents, then their construction shall be of the same character as for similar conditions that are shown.
- Contractor shall verify all dimensions and conditions shown on the drawings and notify the architect of any discrepancies. Provide and verify the size and location of the following: Required access doors, openings, turning, anchors, inserts and blocking required for accessories and mechanical, electrical equipment. Verify all rough-in dimensions for equipment provided in these plans or equipment by others.
- Contractor shall verify size, make and model number of all household appliances and plumbing fixtures prior to fabrication of cabinets to ensure proper fit and finish.
- Contractor shall verify all electrical, mechanical, telephone, fire alarm and security requirements before construction begins.
- Contractor shall coordinate the locations of lights, air supply diffusers and return air grilles, fire sprinkler heads, smoke/carbon monoxide detectors, cable and satellite tv, skylights and attic access panels before construction begins.
- Contractor shall assume sole & complete responsibility for job site conditions and comply with safety regulations and restrictions as required for worker and pedestrian protection during the course of construction of this project.

Abbreviations

A/C	Air Conditioning	FO	Finished Opening	REF	Refrigerator
ADJ	Adjacent	FR	Fireplace	REIN	Reinforced
AFCI	Arc-Fault Circuit Interrupt	FR	French Door	REQ	Required / Requirements
AFF	Above Finished Floor	FTG	Footing	RES	Re-sawn
BA	Bath	FX	Fixed	RM	Room
BLDG	Building	GA	Gauge	RO	Rough Opening
BLKG	Blocking	GALV	Galvanized	RWD	Redwood
BM	Beam	GB	Grab Bar	S & P	Shell & Pole
BP	Bypass	GFI	Ground Fault Interrupter	SC	Self Closure
BU	Built-Up	GRD	Grade	SCF	Square Feet
C	Carpet	G3F	Gross Square Footage	SGD	Sliding Glass Door
CAB	Cabinet	GYP	Gypsum	SH	Single Hung
CL	Centrifuge	HCP	Handicap	SHT	Sheet
CLG	Celling	HDR	Header	SHM	Similar
CLR	Clear	HDWR	Hardware	SL	Sliding
CMU	Concrete Masonry Unit	HE	High Efficacy	SLOP	Sloped
COMP	Composite	HR	Hour	SPEC	Specification
CONC	Concrete	HTG	Height	SQ FT	Square Feet/Foot
CONT	Continuous	HT	Heating	STD	Standard
CONTR	Contractor	HW	Hot Water	STOR	Storage
CR	Corrosion Resistant	INSUL	Insulation	STRUCT	Structural
CW	Cold Water	INT	Interior	T	Tie
D	Dimension	JB	Junction Box	T&G	Tongue and Groove
DM	Dimmer	KO	Knock-Out	TB	Towel Bar
DN	Down	KP	Kickplate	TC	Trash Compactor
DP	Damp Proof	LAU	Laundry	TEL	Telephone
DR	Door	LIN	Linon	TOC	Top Of Curb
DW	Dishwasher	MAX	Maximum	TOP	Top Of Plate
DWR	Drawer	MECH	Mechanical Cabinet	TOS	Top Of Slab
ELEC	Electrical	MECH	Mechanical	TP	Tissue Paper
ELEV	Elevation	MFR	Manufacturer	TR	Towel Ring
ENCL	Enclosed	MIN	Minimum	Typ	Typical
ENGR	Engineer	NSF	Net Square Footage	UNO	Unless Noted Otherwise
EQ	Equal	NIS	Not To Scale	UNLESS	Unless Otherwise Noted
EQUIP	Equipment	OA	Over All	V	Vinyl
EXIST	Existing	OC	On Center	VERT	Vertical
EXT	Exterior	OGD	Overlapped Garage Door	W	Washing Machine
FAU	Forced Air Unit	OPT	Option / Optional	W/	With
FRGL	Fiberglass	P/L	Property Line	W/O	Without
FDN	Foundation	PLY	Plate Line	WC	Water Closet
FE	Fire Extinguisher	PR	Pair	WD	Wood
FF	Face Frame	PT	Pressure Treated	WDW	Window
FEL	Finish Floor Line	PVC	Polyvinyl Chloride	WH	Water Heater
FG	Finish Grade	PWDR	Powder Room	WIC	Walk in Closet
FIN	Finish	RA	Return Air	WP	Water Proof
FL	Floor				

Northwest Land Park:
 Urban Courts
 City of Sacramento, California

Sheet Revisions	
#	DATE / COMMENT
	01.13.15 INITIAL PLAN CHECK SUBMITAL
A	02.03.15 PLAN REVIEW 1
A	02.11.15 OWNER MODIFICATIONS
A	03.03.15 PLAN REVIEW 2
A	04.13.15 CLARIFICATION
A	05.29.15 WINDOW MODIFICATIONS
A	06.30.15 FRAME WALK MODIFICATIONS

BUILDING 1
 Sheet Description:
 COVER SHEET

Sheet Number:

A1.0

- FOUNDATION NOTES:**
1. Bear all footings on compacted structural fill.
 2. Footings have been designed for a soil bearing pressure of 4500 psf. Bearing stratum for footings shall be verified in field by a licensed geotechnical engineer before casting concrete footings.
 3. Soil bearing surfaces previously accepted by geotechnical engineer, which are allowed to become saturated, frozen, or disturbed shall be reworked to satisfaction of geotechnical engineer.
 4. Do not place footings in water nor on frozen ground.
 5. Do not allow ground beneath footings to freeze.
 6. Center footings under walls, piers, or columns, unless noted otherwise.
 7. Reinforce all concrete elements (footings, walls, piers, slabs), reinforcement shown pertains to all typical conditions.
 8. Lap footing and horizontal wall reinforcement 24 diameters at splices.
 9. Provide corner bars in footings, the same size and number as continuous reinforcement, lapped 2 feet with main reinforcement.
 10. Extend reinforcement in wall footings between columns into column footings a minimum of 2 feet.
 11. Place transverse reinforcement in continuous footings where shown in bottom layer.
 12. Where required, step new footings up or down in ratio of two horizontal to one vertical to join existing footings.
 13. Cast stepped footings monolithically.
 14. Key and dowel concrete walls and piers into footings with details, its bottom side and top side as shown. Extend dowels to within 3 inches of bottom of footing. Terminate with A.C.I. Std. 90 degree hook. Lap 30 diameters with vertical reinforcement.
 15. Build concrete piers in concrete walls simultaneously with walls.
 16. Align all foundation wall construction joints with masonry wall control joints.
 17. Verify size and location of mechanical openings.
 18. Concrete walls shall attain a minimum strength of 70% fc before placing backfill against them.
 19. Concrete cover for reinforcement shall be as follows unless detailed otherwise:
 Footings poured against earth: 3"
 Surface exposed to weather or earth: 2"
 Bars larger than #5: 1 1/2"
 #5 bars or smaller: 3/4"
 Beams and piers: 1 1/2"
 20. Foundation Preparation: Refer to Specifications for Structural Excavation, Backfill & Compaction (Building Area).

- SLAB ON GRADE**
1. Do not extend reinforcement in slab on grade thru construction or control joints.
 2. Subgrades below slab on grade shall be reviewed and accepted by geotechnical engineer before concrete slab placement.
 3. See Architectural Drawings for exact locations and details of depressed slabs.
 4. Thicken slabs on grade under non-bearing masonry walls (6 inches thick or over) to 8 inches and reinforce as details.


RB Ryan-Biggs Associates, P.C.
 291 River Street
 Troy, New York 12180
 (518) 272-6266

CWVG CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
 120 ERE BOULEVARD, SCHENECTADY, N.Y. 12305


ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
 SED# 01-02-01-04-0-004-006

FOUNDATION DETAILS


No	REVISIONS/SUBMISSIONS	Date




1 SLAB SECTION
 SCALE: 3/4" = 1'-0"




2 SECTION AT DOOR
 SCALE: 3/4" = 1'-0"




3 TYPICAL THICKENED SLAB DETAIL
 SCALE: 3/4" = 1'-0"




4 SLAB OVERPOUR AT DOORS
 SCALE: 3/4" = 1'-0"




5 WALL CONTROL JOINT
 SCALE: 3/4" = 1'-0"




6 WALL CONSTRUCTION JOINT
 SCALE: 3/4" = 1'-0"




7 WALL JOINT SEALANT DETAIL
 SCALE: 1/2" = 1'-0"




8 TYPICAL FOOTING STEP
 SCALE: 1/2" = 1'-0"




9 INTERIOR FOOTING SECTION
 SCALE: 3/4" = 1'-0"




10 TYPICAL FOOTING SECTION
 SCALE: 3/4" = 1'-0"




11 RAMP SECTION
 SCALE: 1/4" = 1'-0"



12 RAMP SECTION
 SCALE: 1/2" = 1'-0"



13 TYPICAL WALL SECTION
 SCALE: 3/4" = 1'-0"



14 FOUNDATION WALL SECTION
 SCALE: 3/4" = 1'-0"

FOUNDATION DETAILS

Designated	Project No.
MCM	01020401
Drawn	Scale
SJW	AS NOTED
Checked	Drawing No.
MCM	S101
Reviewed	Date
CJZ	11-11-94


NOT FOR CONSTRUCTION

NOT FOR CONSTRUCTION

NOT FOR CONSTRUCTION

NOT FOR CONSTRUCTION

Unit Key:






Sheet Notes:

- ALL DIMENSIONS SHALL BE PROVIDED IN ALL CONCEALED SPACES (CRC SECTION 8301)
- ALL DIAGONAL WALLS TO BE 45 DEGREES (UNO)
- WINDOW HEAD HEIGHTS:
 - 1ST FLOOR = 4'-8" AFF (UNO)
 - 2ND FLOOR = 8'-0" AFF (UNO)
 - 3RD FLOOR = 8'-0" AFF (UNO)
 - 4TH FLOOR = 8'-0" AFF (UNO)
 - 5TH FLOOR = 8'-0" AFF (UNO)
- ALL DOORS TO BE CENTERED WITH ADJACENT WALLS OR DOOR JAMB TO BE FRAMED AT 3" UNLESS OTHERWISE DIMENSIONED.
- PROVIDE BACKING FOR ALL HARDWARE FIXTURES (TOWEL BARS, ETC.)
- REFER TO BASE FLOOR PLAN FOR INFORMATION NOT SHOWN ON PARTIAL FLOOR PLANS. HATCHED WALLS ON PARTIAL FLOOR PLANS INDICATE FRAMING CHANGES FROM BASE FLOOR PLAN.

Floor Plan Keynotes:

- DWELLING/GARAGE SEPARATION: ALL SURFACES SHALL BE PROTECTED WITH MINIMUM ONE (1) LAYER 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE. ALL HORIZONTAL SURFACES WITH HABITABLE SPACE ABOVE SHALL BE PROTECTED WITH MINIMUM ONE (1) LAYER 5/8" TYPE X GYPSUM BOARD APPLIED TO THE GARAGE SIDE. ALL VERTICAL SURFACES SHALL BE PROTECTED WITH MINIMUM ONE (1) LAYER 5/8" TYPE X GYPSUM BOARD OR NAILED THICKNESS OF PLYWOOD.
- CHANGING ROOMS: CHANGING ROOMS SHALL BE LOCATED IN THE GARAGE OR ATTACHED TO THE GARAGE. CHANGING ROOMS SHALL BE PROTECTED BY AN AUTOMATIC RESIDENTIAL FIRE SPRINKLER SYSTEM. DOOR OPENINGS BETWEEN THE HOUSE AND THE GARAGE NEED ONLY BE SELF-CLOSING AND SELF-LATCHING. (CRC SECTION R302.5.1 EXCEPTION)
- EMERGENCY ESCAPE AND RESCUE OPENINGS: EVERY SLEEPING ROOM SHALL HAVE AT LEAST ONE (1) OPERABLE EMERGENCY ESCAPE AND RESCUE OPENING. EMERGENCY OPENING SHALL HAVE THE BOTTOM OF THE CLEAR OPENING NOT GREATER THAN 44" MEASURED FROM THE FLOOR AND A MINIMUM NET CLEAR OPENING HEIGHT SHALL BE 20" AND THE MINIMUM NET CLEAR OPENING WIDTH SHALL BE 20". (CRC SECTION R310.1)
- TANKLESS WATER HEATER: SPEC PER ENERGY CALCULATIONS.
- EXTENTS OF EXTERIOR ADHERED STONE VENEER, HEIGHT AND WRAP-BACK AS NOTED ON ELEVATIONS.
- ATTIC ACCESS: PROVIDE A MINIMUM 22"x30" OPENING OR LARGE ENOUGH TO REMOVE THE LARGEST PIECE OF EQUIPMENT. (CRC SECTION R807.1 & CMC SECTION R94.10) LOCATION APPROXIMATE. COORDINATE IN FIELD WITH RUSS.
- A/C CONDENSER: PROVIDE MINIMUM 30"x30" CONCRETE PAD, MINIMUM 3" ABOVE GRADE. LOCATE PER FLOOR PLAN.
- TEMPERED SAFETY GLASS: PROVIDE TEMPERED GLASS AT HAZARDOUS LOCATIONS PER REQUIREMENTS. (CRC SECTION S338.4)
- DRYER: VENT DUCT SHALL BE OF METAL AND SHALL HAVE SMOOTH INTERIOR SURFACES. EXTENDING TO EXTERIOR WITH BACKDRAFT DAMPER. (CRC SECTION S504.3) SEE DETAIL 6/10/6
- WASHING MACHINE: PROVIDE PREFABRICATED CORROSION RESISTANT PAN UNDER WASHING MACHINE (LOCATED ON UPPER FLOOR). DRAIN TO EXTERIOR.
- UPPER CABINETS: WALL MOUNTED ABOVE 12" DEEP TYPICAL 24" DEEP ABOVE REFRIGERATOR.
- SHOWERS & TUB/SHOWER COMBINATIONS: FLOORS AND WALLS SHALL BE FINISHED WITH A NONABSORBENT SURFACE. SUCH WALL SURFACES SHALL EXTEND TO A HEIGHT OF NOT LESS THAN 6 FEET ABOVE THE FLOOR. (CRC SECTION R207.2)
- BACKERS AS A BASE FOR WALL TIE IN AND SHOWER AREAS AND WALL AND CEILING PANELS AREAS IN SHOWERS. (CRC SECTION R702.4.2) LOCATE SHOWER HEAD AT 4'-8" AFF.
- LOW WALL: PROVIDE WITH DOUBLE TOP PLATE. HEIGHT AT 4'-2" AFF (UNO)
- UNDERSLAB PROTECTION: PROVIDE 1/2" GYPSUM BOARD ON ALL WALLS UNDER STAIRS AND ALL STAIRS WITHIN ENCLOSED ACCESSIBLE SPACES. (CRC SECTION R302.7)
- STAIRWAYS: SHALL NOT BE LESS THAN 36" IN CLEAR WIDTH (AND HEADROOM SHALL NOT BE LESS THAN 6'-8" MAXIMUM CLEAR HEIGHT SHALL BE 7'-3 1/4" AND MINIMUM TREAD DEPTH SHALL BE 10". (CRC SECTION R311.7)
- HANDRAILS AND GUARDS WHERE THE TOP OF THE GUARD ALSO SERVES AS A HANDRAIL: HEIGHT SHALL BE NOT LESS THAN 34" AND NOT MORE THAN 38". AND CONTINUOUS FOR THE FULL LENGTH OF THE FLIGHT. (CRC SECTION R311.7.8) SEE DETAIL S/10/6
- GUARDS: SHALL BE NOT LESS THAN 42" IN HEIGHT AND RAIL DESIGN TO COMPLY WITH CODE. (CRC SECTION R312) SEE DETAIL 4/10/6
- COOKING APPLIANCES:
 - RANGE/HOOD, LIGHT, EXHAUST FAN ABOVE. FAN MIN 100 CFM FOR LOCAL EXHAUST VENTILATION (2013 BUILDING ENERGY EFFICIENCY STANDARDS)
 - 30" MICROWAVE IN CABINET.
- INTERIOR FLOOR SOFFIT: FRAME AT 8'-1" AFF (UNO)
- EXTERIOR SOFFIT OR ARCH: SEE EXTERIOR ELEVATIONS FOR DIMENSIONS.
- PANTRY LINEN: (S) SHELVES. EQUAL SPACING.
 - FRAMED WITH HINGED DOOR.
 - CABINET FACE FRAME OR SLIP-IN.
- DASHED LINE INDICATES OUTLINE OF FLOOR ABOVE. SOLID LINE INDICATES OUTLINE OF FLOOR BELOW.
- SHELVES: (S) SHELVES. EQUAL SPACING.
- WOOD DOOR: SEE AS NOTED.
- 1-HOUR FIRE WALL WITH UNPROTECTED OPENINGS: SEE DETAIL 8/1/1.
- 2-HOUR COMMON WALL: SEE DETAIL 9/1/1 AND SHALL COMPLY WITH CRC 302.4 REQUIREMENT FOR FIRE RATED PENETRATIONS
- 1-HOUR FIRE GARAGE WALL: SEE DETAIL 20/1/1.




Floor Area: Unit A	
LIVING AREA:	553 SQ. FT.
SECOND FLOOR LIVING:	553 SQ. FT.
TOTAL LIVING AREA:	553 SQ. FT.
OTHER AREAS:	
GARAGE:	256 SQ. FT.
COVERED BALCONY:	59 SQ. FT.
Floor Area: Unit B	
LIVING AREA:	129 SQ. FT.
FIRST FLOOR ENTRY STAIRS:	121 SQ. FT.
SECOND FLOOR STAIRS:	21 SQ. FT.
THIRD FLOOR STAIRS:	668 SQ. FT.
FOURTH FLOOR LIVING:	1150 SQ. FT.
TOTAL LIVING AREA:	226 SQ. FT.
OTHER AREAS:	8 SQ. FT.
GARAGE:	130 SQ. FT.
PORCH:	
ROOF DECK:	

Northwest Land Park:
Urban Courts



10430 MATHER BLVD
MATHER, CA 95655
916.366.9665



© 2014-2015 Jeffrey Denmure + Associates Architects
All rights reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Jeffrey Denmure + Associates Architects. This document is the property of Jeffrey Denmure + Associates Architects and is loaned to you for your use only. It is not to be distributed, copied, or otherwise used without the prior written permission of Jeffrey Denmure + Associates Architects.


JDA-A, Job Number: 14060

Sheet Revisions	
#	DATE: COMMENT
01	01.13.15 INITIAL PLAN CHECK SUBMITTAL
02	02.03.15 PLAN REVIEW 1
03	
04	05.29.15 WINDOW MODIFICATIONS
05	06.30.15 FRAME WALK MODIFICATIONS

BUILDING 1
Sheet Description:
FIRST FLOOR PLAN

Sheet Number:
A3.1

1 2 3 4 5 6 7 8 9 10 11 12 13 14



GENERAL NOTES

- All dimensions to, of, and in existing building shall be verified in field by contractor.
- Do not change size nor spacing of structural elements.
- Details shown are typical; similar details apply to similar conditions unless otherwise indicated.
- These Drawings do not include necessary components for construction safety.
- Brace building until all structural elements needed for stability are installed. These elements are as follows: (floor deck, roof deck, masonry walls).
- Designed per "New York State Uniform Fire Prevention and Building Code", as part of the International Building Code and Regulations of the State of New York including amendments through October 1992.
- Contractor shall determine exact location of existing utilities before commencing work. He shall be responsible for any damage to existing utilities which might be occasioned by his failure to exactly locate and preserve underground utilities.
- Contractor shall notify Engineer in writing of all proposed deviations or substitutions from dimensions, materials, or equipment shown on Drawings and make only those deviations, or substitutions acceptable to Engineer.

DESIGN DATA

1. Live Loads: 45 psf
Roof: (Drifted snow as per American Society of Civil Engineers Standards, ASCE 7-93).

Floors: Classrooms: 40 psf
Corridors and stairs: 100 psf

Wind Loads: Walls: 15 psf
Height above grade: 0 to 25' - 18 psf
25' to 40' - 19 psf

Dead Loads: 23 psf
Roof: 53 psf

Soil Pressure: Presumptive Soil Bearing Pressure: 4500 psf under spread footing, 4000 psf under continuous strip footings.

Foundation design based on recommendations included in "Geotechnical Evaluation, Proposed addition to B.K.W. High School, Berne, New York", F.E. 94-51, by F.A. Dente Engineering, P.C. dated July 1, 1994.

4. Seismic Loads: UBC 1984 Occupancy Category III, Zone 2A.

FOOTING SCHEDULE

MARK	SIZE	REINF.	REMARKS
F1	3'-0"x3'-0"x1'2"	(4) #5 BAR EA. WAY	
F2	4'-0"x4'-0"x1'2"	(5) #5 BAR EA. WAY	
F3	4'-6"x4'-6"x1'2"	(5) #5 SHORT BAR (7) #3 LONG BARS	OVER FOUR EXISTING BUILDING FOOTING (SIM. TO 14/10/1)
F4	3'-0"x4'-6"x2'4"		

PIER DETAILS

SCALE: 1" = 1'-0"

NOTES:

- PLACE PIERS MONOLITHICALLY WITH FDN. WALL.
- WORK WITH DWG. 5200 & 5201 FOR A.B. ORIENTATIONS.
- LOCATE TOP TIE 2" BELOW TIPPER AND PROVIDE ADDTL. TIES AS SHOWN IN 105/101

ELEVATOR PIT SECTION

SCALE: 1/2" = 1'-0"

NOTE: 1. PAINT BEDROCK MAY BE ENCOUNTERED AT PIT EXCAVATION. IF ENCOUNTERED REMOVE ROCK TO 2" BELOW FIG. BOTTOM AND FILL WITH COMPACTED STRUCTURAL FILL.

FOUNDATION PLAN

SCALE: 1/8" = 1'-0"

NOTES:

- TOP OF SLAB REFERENCE ELEV. = 99'-2" (10' ± BELOW EXISTING SLAB ELEVATION)
- TOP OF FTGS. NOTED (+ OR -) ARE FROM REF. ELEV. 99'-2" (1FF)
- PROVIDE WALL CONTROL OR CONSTRUCTION JOINTS AT LOCATIONS INDICATED BY C.I. SEE 5/5/101 & 6/5/101 ALIGN WITH MASONRY JOINTS.
- COORDINATE THICKENED SLAB LOCATIONS WITH ARCHITECTURAL DRAWINGS.
- AT LOWER FOOTING ELEVATIONS, BEDROCK MAY BE ENCOUNTERED. NOTIFY ENGINEER FOR REVIEW AND RECOMMENDATIONS
- COORDINATE SLAB RECESS LOCATIONS WITH ARCH DRAWINGS PROVIDE CAST-IN-PLACE EDGE FRAME AROUND PERIMETER AS SHOWN IN 1/5201.

KEY PLAN

1" = 120'-0"

Ryan-Biggs Associates, P.C.
291 River Street
Troy, New York 12180
(518) 272-6266

REVISIONS/SUBMISSIONS

No	REVISIONS/SUBMISSIONS	Date

CWCG
CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

FOUNDATION PLAN & NOTES

ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT


ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006

Project No. 01020401
Scale AS NOTED
Drawing No. S100

Designed MCM
Drawn BAM
Checked MCM
Reviewed CJZ
Date 11-1-94

NOT FOR CONSTRUCTION

Unit Key:






SECOND FLOOR

- Sheet Notes:**
- FIRE BLOCKING SHALL BE PROVIDED IN ALL CONCEALED SPACES (CRC SECTION R302.11).
 - ALL DIAGONAL WALLS TO BE 45 DEGREES (UNO).
 - MINIMUM CLEARANCE HEIGHTS:
 - 1ST FLOOR = 48" AFF (UNO)
 - 2ND FLOOR = 8'0" AFF (UNO)
 - 3RD FLOOR = 8'0" AFF (UNO)
 - 4TH FLOOR = 8'0" AFF (UNO)
 - DOOR HEIGHTS AS NOTED ON FLOOR PLANS.
 - ALL DOORS TO BE CENTERED WITH ADJACENT WALLS, OR DOOR FRAME TO BE CENTERED WITH ADJACENT WALLS (TOWEL BARS, ETC.).
 - PROVIDE BACKING FOR ALL HARDWARE FITURES (TOWEL BARS, ETC.).
 - REFER TO BASE FLOOR PLAN FOR INFORMATION NOT SHOWN ON PARTIAL FLOOR PLANS. HATCHED WALLS ON PARTIAL FLOOR PLANS INDICATE FRAMING CHANGES FROM BASE FLOOR PLAN.

Floor Plan Keynotes:

- DWELLING/GARAGE FIRE SEPARATION: ALL SURFACES SHALL BE PROTECTED BY 5/8" THICK GYPSUM BOARD OR 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE. ALL HORIZONTAL SURFACES WITH HABITABLE SPACE ABOVE SHALL BE PROTECTED WITH MINIMUM ONE (1) LAYER 5/8" TYPE X GYPSUM BOARD APPLIED TO THE GARAGE SIDE. (CRC SECTION R702.3.1) TABLE R702.3.1. WHEN SHEAR PLATEWOOD IS INSTALLED AT GARAGE OCCUPANCY SEPARATION LENGTHEN GYPSUM SCREW OR NAILS TO THICKNESS OF PLATEWOOD.
- OPENING PROTECTION: WHERE THE RESIDENCE AND PRIVATE GARAGE ARE PROTECTED BY AN AUTOMATIC REFRIDERABLE FIRE STOPPING SYSTEM, THE SYSTEM SHALL BE INSTALLED IN THE HOUSE AND THE GARAGE SEED ONLY BY SEE CLOSING AND SEE SLATCHING. (CRC SECTION R302.3.1 EXCEPTION)
- EMERGENCY ESCAPE AND RESCUE OPENINGS: EVERY SLEEPING ROOM SHALL HAVE AT LEAST ONE (1) OPERABLE EMERGENCY ESCAPE AND RESCUE OPENING. EMERGENCY OPENINGS SHALL HAVE THE BOTTOM OF THE CLEAR OPENING NOT GREATER THAN 44" MEASURED FROM THE FLOOR AND A MINIMUM NET CLEAR OPENING OF 5.7 SQUARE FEET. THE MINIMUM NET CLEAR OPENING HEIGHT SHALL BE 24" AND THE MINIMUM NET CLEAR OPENING WIDTH SHALL BE 20". (CRC SECTION R310.1)
- TANKLESS WATER HEATER: SPEC PER ENERGY CALCULATIONS.
- EXTENTS OF EXTERIOR ADHERED STONE VENEER HEIGHT AND WRAPBACK AS NOTED ON ELEVATIONS.
- AIRC ACCESS: PROVIDE A MINIMUM 22"x30" OPENING OR LARGE ENOUGH TO REMOVE THE LARGEST PIECE OF EQUIPMENT. (CRC SECTION R807.1 & CMC SECTION 904.10) LOCATION APPROXIMATE. COORDINATE IN FIELD WITH TRUSS.
- A/C CONDENSER: PROVIDE MINIMUM 30"x30" CONCRETE PAD, MINIMUM 3" ABOVE GRADE. LOCATE PER FLOOR PLAN.
- TEMPERED SAFETY GLASS: PROVIDE TEMPERED GLASS AT HAZARDOUS LOCATIONS PER REQUIREMENTS. (CRC SECTION R308.4)
- DRYER: VENT DUCT SHALL BE OF METAL AND SHALL HAVE SMOOTH INTERIOR SURFACES. EXTENDING TO EXTERIOR WITH BACKDRAFT DAMPER. (CMC SECTION 504.3) SEE DETAIL 6/A/D6
- WASHING MACHINE: PROVIDE PREFABRICATED CORROSION RESISTANT PAN UNDER WASHING MACHINE LOCATED ON UPPER FLOOR. DRAIN TO EXTERIOR.
- UPPER CABINETS: WALL MOUNTED ABOVE 12" DEEP TYPICAL. 24" DEEP ABOVE REFRIGERATOR.
- SHOWERS & TUB/SHOWER COMBINATIONS: FLOOR AND WALLS SHALL BE FINISHED WITH A NONABSORBANT SURFACE. SUCH WALL SURFACES SHALL EXTEND TO A HEIGHT OF NOT LESS THAN 6 FEET ABOVE THE FLOOR. (CRC SECTION R307.2) PROVIDE CHENIT, FIBER-CEMENT OR GLASS MAT GYPSUM BACKER AS A BASE FOR WALL TILE IN AND SHOWER AREAS. (CRC SECTION R302.4) LOCATE SHOWERHEAD AT 6'-0" AFF.
- LOW WALL: PROVIDE WITH DOUBLE TOP PLATE. HEIGHT AT 4'-2" AFF (UNO)
- UNDER-STAR PROTECTION: PROVIDE 1/2" GYPSUM BOARD ON ALL WALLS UNDER STAR SURFACE AND ANY SOFFITS WITHIN ENCLOSED ACCESSIBLE SPACES. (CRC SECTION R302.7)
- STAIRWAYS: SHALL NOT BE LESS THAN 36" IN CLEAR WIDTH (AND NOT HAVE A VERTICAL RISE OF MORE THAN 12"). MINIMUM HEADROOM SHALL NOT BE LESS THAN 6'-8". MAXIMUM RISEER HEIGHT SHALL BE 7'-8". AND MINIMUM HEAD DEPTH SHALL BE 10". (CRC SECTION R311.7)
- HANDRAILS AND GUARDS: WHERE THE TOP OF THE GUARD ALSO SERVES AS A HANDRAIL, HEIGHT SHALL BE NOT LESS THAN 36" TO 42" ABOVE FINISHED FLOOR SURFACE OR THE FULL LENGTH OF THE FLIGHT. (CRC SECTION R311.7.8) SEE DETAIL 5/A/06
- GUARDS SHALL BE NOT LESS THAN 42" IN HEIGHT AND 4"AIL DESIGN TO COMPLY WITH CODE. (CRC SECTION R312) SEE DETAIL 4/A/06
- COOKING APPLIANCE:
 - A. 30" RANGE/WOOD LIGHT EXHAUST FAN ABOVE FAN WITH 100 CFM FOR LOCAL EXHAUST VENTILATION (2013 BUILDING ENERGY EFFICIENCY STANDARDS)
 - B. 30" MICROWAVE IN CABINET.
- INTERIOR FLOOR SOFFIT: FRAME AT 8'-1" AFF (UNO)
- EXTERIOR SOFFIT OF ARCH: SEE EXTERIOR ELEVATIONS FOR DIMENSIONS.
- PANTRY / LINEN: (S) SHELVES, EQUAL SPACING. A. FRAMED WITH HINGE DOOR. B. CABINET FACE FRAME OR SIP-IN.
- DASHED LINE INDICATES OUTLINE OF FLOOR ABOVE. SOLID LINE INDICATES OUTLINE OF FLOOR BELOW. SHELVES: (S) SHELVES, EQUAL SPACING.
- WOOD POST: SEE AS NOTED.
- 1 HOUR FIRE WALL WITH UNPROTECTED OPENINGS: SEE DETAIL 8/PFL.
- 2 HOUR COMMON WALL: SEE DETAIL 9/PFL AND SHALL COMPLY WITH CRC 302.4 REQUIREMENT FOR FIRE RATED PENETRATIONS
- 1 HOUR FIRE GARAGE WALL: SEE DETAIL 20/PFL.

Floor Area: Unit A	
LIVING AREA:	553 SQ. FT.
SECOND FLOOR LIVING:	553 SQ. FT.
TOTAL LIVING AREA:	553 SQ. FT.
OTHER AREAS:	
GARAGE:	256 SQ. FT.
COVERED BALCONY:	59 SQ. FT.
Floor Area: Unit B	
LIVING AREA:	
FIRST FLOOR ENTRY STAIRS:	129 SQ. FT.
SECOND FLOOR STAIRS:	121 SQ. FT.
THIRD FLOOR STAIRS:	21 SQ. FT.
THIRD FLOOR LIVING:	668 SQ. FT.
FOURTH FLOOR LIVING:	211 SQ. FT.
TOTAL LIVING AREA:	1,150 SQ. FT.
OTHER AREAS:	
GARAGE:	226 SQ. FT.
PORCH:	8 SQ. FT.
ROOF DECK:	130 SQ. FT.




Northwest Land Park:
Urban Courts

City of Sacramento, California

JDA
JEFFERREY DEMURE + ASSOCIATES
ARCHITECTS • PLANNERS
5905 GRANITE LAKE DRIVE, SUITE 140
F : 916.283.3700
P : 916.283.3711
WWW.JDARCH.COM

Bardis Homes
Northwest Land Park
16300 MATHEE BLVD
MATHER, CA 95655
916.366.3665



JDA - Job Number: 14660

Sheet Revisions


#	DATE	COMMENT
1	01.13.15	INITIAL PLAN CHECK SUBMITTAL
2	02.03.15	PLAN REVIEW 1
3	04.13.15	CLARIFICATION
4	05.29.15	WINDOW MODIFICATIONS
5	06.30.15	FRAME WALK MODIFICATIONS

BUILDING 1
Sheet Description:
SECOND FLOOR
PLAN

Sheet Number:
A3.2

8/27/2015 PERMIT SET





- MATERIAL KEYING LEGEND (SEE SPECIFICATIONS)
- 4.20 UNIT MASONRY
 - 4.20C CONCRETE MASONRY UNITS
 - 8.10 METAL DOORS AND FRAMES
 - 8.10F 16 GAUGE HOLLOW METAL PIPE ENCLOSURE
 - 8.33 ROLLING COUNTER FIRE DOOR
 - 8.33B VERTICAL SIDING PASS WINDOW
 - 8.50 METAL WINDOWS
 - 8.50A ALUMINUM WINDOWS
 - 9.30 TILE
 - SEE ROOM FINISH SCHEDULE*
 - 9.30A GLAZED WALL TILE
 - 9.30D GLAZED CERAMIC TILE WALL BASE
 - 9.30E MARBLE THRESHOLDS - SEE DOOR SCHEDULE
 - 9.30F ACCENT TILE - CONTINUOUS AROUND ROOM
 - 9.65 RESILIENT FLOORING
 - SEE ROOM FINISH SCHEDULE*
 - 9.65B VINYL COVE BASE
 - 10.10 CHALKBOARDS AND TACKBOARDS
 - 10.10B LIQUID MARKER BOARD
 - 10.10C TACKBOARD
 - 10.10F PROJECTION SCREEN
 - 10.62 FOLDING PARTITIONS
 - 10.62A FOLDING PARTITION
 - 10.62B LIQUID MARKER BOARD
 - 10.62E TACKBOARD
 - 10.80 TOILET ACCESSORIES
 - 10.80C MIRROR
 - 10.80D GRAB BARS
 - 11.46 UNIT KITCHENS
 - 11.46A COMPACT KITCHEN UNIT
 - 12.30 CASEWORK
 - SEE DRAWINGS FOR CASEWORK*
 - 12.30A PLASTIC LAMINATE COUNTER WITH 4" BACKSPLASH
 - 12.30B FILLER STRIP - SIZE AS REQUIRED
 - 12.30C BASE CABINET
 - 12.30I LAB COUNTERTOP
 - 12.30K PLASTIC LAMINATE TOP

*SEE REFERENCE NOTES FOR INFORMATION ELABORATING ON-OR WORK IN ADDITION TO - MATERIALS NOTED HERE. PROVIDE ALL MATERIALS AS REQUIRED FOR A COMPLETE AND PROPER INSTALLATION.

DRAWING NOTES

1. PIPE CHASE EXTENDS FROM TOP OF SHELVING TO 3" ABOVE CEILING. REFER TO DRAWING A101 FOR LOCATIONS. PROVIDE CUT OUT IN REAR OF CABINET FOR ACCESS TO ELECTRICAL OUTLET. COORDINATE WITH ELECTRICAL CONTRACTOR.
2. RAISE EXISTING TACKBOARD TO ALLOW INSTALLATION OF NEW DOOR AND FRAME IN EXISTING WALL. PROVIDE RECTANGULAR COORDINATES ON REAR PANEL.
3. PROVIDE POLAR COORDINATES ON REAR PANEL.

No.	REVISIONS/SUBMISSIONS	Date

CWCG
 CATALDO, WATERS and GRIFFITH
 ARCHITECTS, P.C.
 120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION
 FOR THE
 BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT
 ADDITION AND ALTERATIONS AT THE
JR./SR. HIGH SCHOOL
 SED# 01-02-01-04-0-004-006

Drawing Title
**INTERIOR ELEVATIONS
 & INTERIOR ROOM FLOOR PLAN**

Project No. 01020401
 Scale AS NOTED
 Drawing No. **A610**

Designed © 1994
 Drawn DB
 Checked L.J.H.
 Reviewed K.P.G.
 Date 11-11-94

NOT FOR CONSTRUCTION


M	1	2	3	4	5	6	7	8	9	10	11	12	13	14	M
L															L
K															K
J															J
H															H
G															G
F															F
E															E
D															D
C															C
B															B
A															A

- MATERIAL KEYING LEGEND (SEE SPECIFICATIONS*)
- 4.20 UNIT MASONRY
 - 4.20A FACE BRICK - STANDARD MODULAR
 - 5.10 STRUCTURAL STEEL
 - 5.10B STEEL ANGLE
 - 5.30 METAL DECKING
 - 5.30A METAL DECKING
 - 5.30B METAL DECKING
 - 5.30C METAL DECKING
 - 6.10 ROUGH CARPENTRY
 - 6.10A WOOD DECKING
 - 7.50 ROOFING SYSTEM (EPDM)
 - 7.50A ROOFING SYSTEM
 - 7.50B ROOFING SYSTEM
 - 7.50C ROOFING SYSTEM
 - 7.50D THERMAL INSULATION
 - 7.50E THERMAL BARRIER
 - 7.50F VAPOR BARRIER/AIR SEAL
 - 7.50G BALLAST AND PROTECTIVE MAT
 - 7.50H FASMA EXTENDER
 - 7.50I FASMA EXTENDER
 - 7.50J SEALANT
 - 7.50K SEALANT
 - 7.50L SEALANT
 - 7.50M SEALANT
 - 7.50N SEALANT
 - 7.50O SEALANT
 - 7.50P SEALANT
 - 7.50Q SEALANT
 - 7.50R SEALANT
 - 7.50S SEALANT
 - 7.50T SEALANT
 - 7.50U SEALANT
 - 7.50V SEALANT
 - 7.50W SEALANT
 - 7.50X SEALANT
 - 7.50Y SEALANT
 - 7.50Z SEALANT
 - 7.90 CAULKING AND SEALANTS
 - 7.90A CAULKING AND SEALANTS
 - 7.90B CAULKING AND SEALANTS
 - 7.90C CAULKING AND SEALANTS
 - 7.90D CAULKING AND SEALANTS
 - 7.90E CAULKING AND SEALANTS
 - 7.90F CAULKING AND SEALANTS
 - 7.90G CAULKING AND SEALANTS
 - 7.90H CAULKING AND SEALANTS
 - 7.90I CAULKING AND SEALANTS
 - 7.90J CAULKING AND SEALANTS
 - 7.90K CAULKING AND SEALANTS
 - 7.90L CAULKING AND SEALANTS
 - 7.90M CAULKING AND SEALANTS
 - 7.90N CAULKING AND SEALANTS
 - 7.90O CAULKING AND SEALANTS
 - 7.90P CAULKING AND SEALANTS
 - 7.90Q CAULKING AND SEALANTS
 - 7.90R CAULKING AND SEALANTS
 - 7.90S CAULKING AND SEALANTS
 - 7.90T CAULKING AND SEALANTS
 - 7.90U CAULKING AND SEALANTS
 - 7.90V CAULKING AND SEALANTS
 - 7.90W CAULKING AND SEALANTS
 - 7.90X CAULKING AND SEALANTS
 - 7.90Y CAULKING AND SEALANTS
 - 7.90Z CAULKING AND SEALANTS


SEE REFERENCE NOTES FOR INFORMATION ELABORATING ON-OR OFF-DRAWING MATERIALS. MATERIALS SHOWN HEREIN SHALL BE INSTALLED AS REQUIRED FOR A COMPLETE AND PROPER INSTALLATION.

DRAWING NOTES


1. REMOVE EXISTING FASCIA AND RELATED MATERIAL. PULL BACK EXISTING BALLAST AND PROTECTIVE MAT TO ALLOW FOR FLASHING OF NEW WORK.




CANOPY ROOF PLAN
A102, A520




FLOOR PLAN
A520




KEY PLAN
A-14




SCUPPER DRAIN
A520




TYPICAL ROOF SECTION
A520




FLASHING DETAIL
A520




FASCIA DETAIL
A520




EDGE DETAIL
A520




CANOPY ROOF SECTION
A520




DECK TO WALL EXPANSION
A520




ROOF DRAIN DETAIL
A520



EXPANSION JOINT
A502, A504, A520



MECHANICAL CURB
A520



PIPE VENT DETAIL
A520


CWGW CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006
Drawing Title
ROOF PLAN & DETAILS

Designed	© 1994	Project No.	01020401
Drawn	DB	Scale	AS NOTED
Checked	L.J.H.	Reviewed	K.P.G.
Date	11-11-94	Drawing No.	A520

NOT FOR CONSTRUCTION

Unit Key:



FOURTH FLOOR


Sheet Notes:

- FIRE STOPPING SHALL BE PROVIDED IN ALL CONCEALED SPACES. (CBC SECTION R302.11.)
- ALL DIAGONAL WALLS TO BE 45 DEGREE (D/C).
- WALLS SHALL BE 1/2" MIN. THICK UNLESS NOTED OTHERWISE.
 - 1ST FLOOR - 4.8" AFF (UNO)
 - 2ND FLOOR - 8'0" AFF (UNO)
 - 3RD FLOOR - 8'0" AFF (UNO)
 - 4TH FLOOR - 8'0" AFF (UNO)
- ALL DOORS TO BE CENTERED WITHIN ADJACENT WALLS, OR DOOR THRESHOLDS SHALL BE 3" TO 5" BELOW FINISH FLOOR LEVELS, ETC.).
- PROVIDE BACKING FOR ALL HARDWARE FINISHES (TOILET BARS, ETC.).
- REFER TO BASE FLOOR PLAN FOR INFORMATION NOT SHOWN ON PARTIAL FLOOR PLANS. HATCHED WALLS ON PARTIAL FLOOR PLANS INDICATE FRAMING CHANGES FROM BASE FLOOR PLAN.


Floor Plan Keynotes:

- DWELING/GARAGE FIRE SEPARATION ALL SURFACES SHALL BE PROTECTED WITH 1/2" MIN. THICK GYPSUM BOARD APPLIED TO THE GARAGE SIDE. ALL HORIZONTAL SURFACES WITH HABITABLE SPACE ABOVE SHALL BE PROTECTED WITH MINIMUM ONE (1) LAYER 5/8" TYPE X GYPSUM BOARD WITH MINIMUM ONE (1) LAYER 5/8" TYPE X GYPSUM BOARD. (CBC SECTION R702.3.3). WHEN SHEAR WOOD IS INSTALLED AT GARAGE OCCUPANCY SEPARATION LENGTHEN GYPSUM SCREW OR NAILS TO PENETRATE THROUGH GYPSUM BOARD AND INTO THE GARAGED FLOOR JOIST AND SEE LATCHING. (CBC SECTION R702.3.1 EXCEPTION)
- EMERGENCY ESCAPE AND RESCUE OPENINGS: EVERY SLEEPING ROOM SHALL HAVE AT LEAST ONE (1) OPERABLE EMERGENCY ESCAPE AND RESCUE OPENING. EMERGENCY OPENINGS SHALL HAVE THE BOTTOM OF THE CLEAR OPENING NOT GREATER THAN 44" MEASURED FROM THE FLOOR AND A MINIMUM NET CLEAR OPENING OF 5.7 SQUARE FEET. THE MINIMUM NET CLEAR OPENING HEIGHT SHALL BE 24" AND THE MINIMUM NET CLEAR OPENING WIDTH SHALL BE 20". (CBC SECTION R310.1)
- TANKLESS WATER HEATER: SPEC PER ENERGY CALCULATIONS.
- SYSTEMS OF EXTERIOR ADHERED STONE SURFACES: HEIGHT AND WRAP BACK AS NOTED ON ELEVATIONS.
- ATIC ACCESS: PROVIDE A MINIMUM 22"x30" OPENING OR LARGE ENOUGH TO BRIDGE THE LARGEST PIECE OF EQUIPMENT. (CBC SECTION R807.1 & CBC SECTION 924.10) LOCATION APPROXIMATE. COORDINATE IN FIELD WITH TRUSS.
- A/C CONDENSER: PROVIDE MINIMUM 30"x30" CONCRETE PAD, MINIMUM 3" ABOVE GRADE. LOCATE PER FLOT PLAN.
- TEMPERED SAFETY GLASS: PROVIDE TEMPERED GLASS AT HAZARDOUS LOCATION PER REQUIREMENTS. (CBC SECTION R308.4)
- DRYER: VENT DUCT SHALL BE OF METAL AND SHALL HAVE SMOOTH INTERIOR SURFACES. EXTENDING TO EXTERIOR WITH BACKDRAFT DAMPER. (CBC SECTION 804.3). SEE DETAIL 6A/66
- WASHING MACHINE: PROVIDE PRE-FABRICATED CORROSION RESISTANT PAN UNDER WASHING MACHINE LOCATED ON UPPER FLOOR. DRAIN TO EXTERIOR.
- UPPER CABINETS: WALL MOUNTED ABOVE 12" DEEP TYPICAL 24" DEEP ABOVE REFRIGERATOR.
- SHOWERS & TUBS/SHOWER COMBINATIONS: FLOOR AND WALLS SHALL BE FINISHED WITH A NONABSORBANT SURFACE. SUCH WALL SURFACES SHALL EXTEND TO A HEIGHT OF NOT LESS THAN 6 FEET ABOVE THE FLOOR. (CBC SECTION R307.2)
- PROVIDE CEMENT FIBER CEMENT OR GLASS MAT GYPSUM BACKER AS A BASE FOR WALL TILE IN TUB AND SHOWER AREAS. (CBC SECTION R307.4) LOCATE SHOWERHEAD AT 6'-4" AFF.
- LOW WALL: PROVIDE WITH DOUBLE TOP PLATE. HEIGHT AT 4'-2" AFF (UNO)
- UNDER STAR PROTECTION: PROVIDE 1/2" GYPSUM BOARD ON ALL WALLS UNDER STAR SURFACE AND ANY SOFFITS WITHIN ENCLOSED ACCESSIBLE SPACES. (CBC SECTION R307.7)
- STAIRWAYS SHALL NOT BE LESS THAN 36" IN CLEAR WIDTH (AND NOT HAVE A VERTICAL RISE OF MORE THAN 12"). MINIMUM HEADROOM SHALL NOT BE LESS THAN 6'8". MAXIMUM RIBER HEIGHT SHALL BE 7'-3/4" AND MINIMUM HEAD DEPTH SHALL BE 10". (CBC SECTION R311.7)
- HANDRAILS (AND GUARDS WHERE THE TOP OF THE GUARD ALSO SERVES AS A HANDRAIL) HEIGHT SHALL BE NOT LESS THAN 36" MEASURED FROM THE FINISH FLOOR TO THE TOP OF THE FULL LENGTH OF THE RAIL. (CBC SECTION R311.7.8)
- SEE DETAIL 5A/26
- GUARDS SHALL BE NOT LESS THAN 42" IN HEIGHT AND RAIL DESIGN TO COMPLY WITH CODE. (CBC SECTION R312) SEE DETAIL 5A/26
- COOKING SURFACES:
 - A. 30" PANHANDLE WOOD LIGHT EXHAUST FAN ABOVE FAN WITH 100 CFM FOR LOCAL EXHAUST VENTILATION (2013 BUILDING ENERGY EFFICIENCY STANDARDS)
 - B. 30" MICROWAVE IN CABINET.
- INTERIOR FLOOR SOFFIT: FRAME AT 8'-1" AFF (UNO)
- EXTERIOR SOFFIT OF ARCH: SEE EXTERIOR ELEVATIONS FOR DIMENSIONS.
- PANTRY / LINEN: (S) SHELVES, EQUAL SPACING.
 - A. FRAMED WITH HINGE DOOR.
 - B. CABINET FACE FRAME OR SLIP-IN.
- DASHED LINE INDICATES OUTLINE OF FLOOR ABOVE. SOLID LINE INDICATES OUTLINE OF FLOOR BELOW.
- SHELVES: (S) SHELVES, EQUAL SPACING.
- WOOD POST: SEE AS NOTED.
- 1 HOUR FIRE WALL WITH UNPROTECTED OPENINGS: SEE DETAIL 8/11/F1.
- 2 HOUR COMMON WALL: SEE DETAIL 9/11/F1 AND SHALL COMPLY WITH CBC 902.4 REQUIREMENT FOR FIRE RATED PENETRATIONS WITH 1 HOUR FIRE GARAGE WALL. SEE DETAIL 20/F1.
- 1 HOUR FIRE/JOINT WALL: SEE DETAIL 19/F1.
- 1 HOUR FIRE/JOINT WALL: SEE DETAIL 19/F1.


Floor Area: Unit A	
LIVING AREA:	553 SQ. FT.
SECOND FLOOR LIVING:	553 SQ. FT.
TOTAL LIVING AREA:	553 SQ. FT.
OTHER AREAS:	
GARAGE:	256 SQ. FT.
COVERED BALCONY:	59 SQ. FT.
Floor Area: Unit B	
LIVING AREA:	
FIRST FLOOR ENTRY STAIRS:	129 SQ. FT.
SECOND FLOOR STAIRS:	121 SQ. FT.
THIRD FLOOR STAIRS:	21 SQ. FT.
THIRD FLOOR LIVING:	668 SQ. FT.
FOURTH FLOOR LIVING:	211 SQ. FT.
TOTAL LIVING AREA:	1150 SQ. FT.
OTHER AREAS:	
GARAGE:	226 SQ. FT.
PORCH:	8 SQ. FT.
ROOF DECK:	130 SQ. FT.




ELEVATION "A" FOURTH FLOOR PLAN
1/4" = 1'-0"




ELEVATION "B" FOURTH FLOOR PLAN
1/4" = 1'-0"



ELEVATION "C" FOURTH FLOOR PLAN
1/4" = 1'-0"



Sheet Revisions		
#	DATE	COMMENT
1	01.13.15	INITIAL PLAN CHECK SUBMITTAL
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		



MATERIAL KEYING LEGEND (SEE SPECIFICATIONS)

- 4.10 MORTAR AND MASONRY GROUT
- 4.20 UNIT MASONRY
- 4.20A FACE BRICK - STANDARD MODULAR
- 4.20C CONCRETE MASONRY UNITS
- 4.20I REINFORCING BARS
- 4.20K WEEP HOLES (CONCRETE SILL)
- 4.5 PRECAST CONCRETE SILL
- 5.10 STRUCTURAL STEEL DRAWINGS*
- 5.10B ANCHOR BOLT
- 5.10C STEEL ANGLE
- 5.20 STEEL JOINTS
- 5.30 SEE STRUCTURAL DRAWINGS*
- 5.30A METAL ROOF DECKING
- 5.50AX ALUMINUM SLEEVE (.050")
- 6.10 ROUGH CARPENTRY
- 6.10B PLYWOOD
- 7.20 INSULATION
- 7.20B BATT INSULATION
- 7.41 PRE-FORMED WALL PANELS
- 7.41C VERTICAL SIDING
- 7.50 ROOFING SYSTEM (EPDM)
- 7.50A ROOFING MEMBRANE
- 7.50B WEEPING INSULATION
- 7.50H FLASHING AND SHEETMETAL
- 7.60 TO FORM DAM
- 7.90 CALKING AND SEALANTS
- 7.90B FOAM JOINT FILL - WIDTH SHOWN X SIZE REQUIRED TO FILL VOID
- 9.20 SEALANT, BEAD
- 9.25A 5/8" TYPE X GYPSUM WALLBOARD
- 9.25C METAL STUD SYSTEM
- 9.25I GYPSUM SHEATHING
- 9.25K CARRYING CHANNEL
- 9.25L METAL ANGLE RUNNER
- 9.50 ACoustICAL TREATMENT
- SEE ROOM FINISH SCHEDULE SYSTEM
- 9.80A SPECIAL COATING SYSTEM
- 9.80B BASE COAT
- 9.80C REINFORCING MESH
- 9.80D INSULATION
- 9.80E METAL STUDS
- 9.80F SEALANT AND BACKER ROD
- 9.80G SLIDE CLIP JOINT
- 9.80H BENT GALVANIZED METAL (SIZE AND GAUGE AS NOTED)
- 9.90 FINISH SCHEDULE*
- 9.90E-1 PAINT E-1
- 10.62 FOLDING PARTITIONS
- 10.62B TRACK SUPPORT BRACKETS, HANGER ROD AND FINISH TRIM

DRAWING NOTES

1. LOUVER FURNISHED BY HVAC CONTRACTOR, INSTALLED BY G.C. ALUMINUM SLEEVE WITH HEMMED EDGES, FASTEN TO STRUCTURE ON 4 SIDES. AND SEAL EDGES TIGHTLY AT INTERIOR AND EXTERIOR. AT SPECIAL COATING SYSTEM FASTEN LOUVER TO SLEEVE ONLY.
2. LOUVER FURNISHED BY HVAC CONTRACTOR, INSTALLED BY G.C. ALUMINUM SLEEVE WITH HEMMED EDGES, FASTEN TO STRUCTURE ON 4 SIDES. AND SEAL EDGES TIGHTLY AT INTERIOR AND EXTERIOR. AT SPECIAL COATING SYSTEM FASTEN LOUVER TO SLEEVE ONLY.

CWGW
CATALDO, WATERS and GRIFFITH
ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION
FOR THE
BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT
ADDITION AND ALTERATIONS AT THE
JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006


WALL DETAILS

Drawing Title


Designed	© 1994	Project No.	01020401
Drawn	DB	Scale	AS NOTED
Checked H.		Drawing No.	A504
Reviewed K.P.G.		Date	11-11-94
Date	11-11-94		

Elevation Design Details:


THE FOLLOWING DETAILS CONVEY DESIGN INTENT. REFER TO ARCHITECTURAL DETAILS FOR SPECIFIC CONSTRUCTION ASSEMBLIES.




1 WINDOW TRIM, TYP
SCALE 1/2" = 1'-0"




2 DOOR TRIM, TYP
SCALE 1/2" = 1'-0"



3 GARAGE DOOR TRIM, TYP
SCALE 1/2" = 1'-0"



4 EAVE CORBEL
SCALE 1/2" = 1'-0"



5 FOAM CORBEL
SCALE 1/2" = 1'-0"

Sheet Notes:

1. PARTIAL AND OPTION ELEVATIONS SHOW ONLY THE ATTRIBUTES AND DETAILS UNIQUE TO THE PARTIAL OR OPTION ELEVATION. REFER TO BASE ELEVATION FOR INFORMATION NOT SHOWN.

2. WINDOW HEAD HEIGHTS:
- 1ST FLOOR = 6'-8" AFF (UNO)
 - 2ND FLOOR = 10'-0" AFF (UNO)
 - 3RD FLOOR = 13'-2" AFF (UNO)
 - 4TH FLOOR = 16'-4" AFF (UNO)


EXTERIOR WALLS:

3. EXTERIOR COVERING REQUIREMENTS:
- A MINIMUM 24-GAUGE CORROSION-RESISTANT WEEP WATER RESISTANT BARRIER SHALL BE APPLIED TO THE EXTERIOR OF THE BUILDING WHERE THE EXTERIOR LATH COVERS AND TERMINATES ON THE ATTACHMENT FLANGE OF THE WEEP SCREED. THE WEEP SCREED MUST HAVE 4" CLEARANCE ABOVE GRADE AND 2" ABOVE PAVED AREAS (CFC R703.6.2.1).
 - WEEP SCREEDS SHALL INCLUDE A WATER-RESISTIVE VAPOR-PERMEABLE BARRIER WITH A PERFORMANCE OF AT LEAST EQUAL TO TWO LAYERS OF GRADE D PAPER. EXCEPTION: A WATER-RESISTIVE BARRIER EQUAL TO OR GREATER THAN 60 MINUTE GRADE D PAPER AND IS SEPARATED FROM THE STUCCO BY AN INTERVENING INSULATION LAYER SHALL BE ACCEPTABLE. REFER TO DESIGNATED DRAINAGE SPACE (CFC R703.6.3).
 - FINISH MATERIALS PER MSG INSTALLATION INSTRUCTIONS:
 - 1-COAT STUCCO SYSTEM OVER MIN 1" FOAM INSULATION OR EQUAL OVER STUDS OR WOOD-BASED SHEATHING. INSTALL PER THE MANUFACTURER'S SPECIFICATIONS BY THE MANUFACTURER.
 - 2-COAT STUCCO SYSTEM OVER MIN 1" FOAM INSULATION OR EQUAL OVER STUDS OR WOOD-BASED SHEATHING. THE FINISH SHALL COMPLY WITH A MINIMUM OF 1/8" PER SHAFT TERMINATE NOT LESS THAN 4" ABOVE FINISHED GROUND LEVEL. (CFC R703.9) BUILDER SPEC MFG OMEGA, ESR-1194.
 - FIBER CEMENT SIDING OVER ONE LAYER OF APPROVED WATER-RESISTIVE BARRIER OVER STUDS OR SHEATHING. REFER TO ELEVATION KEYNOTES.


- ROOF HEELS: LABELED AS PER TRUSS LAYOUTS.
- RAISED HEEL: INCREASED HEEL TO PLANE FASCIA. REFER TO TRUSS LAYOUTS.
- ELEVATION KEYNOTES:
 - MINIMUM CLASS 'A' ROOFING. REFER TO ROOF PLAN SHEET NOTES.
 - 2x6 FASCIA / BARGE RAFTER.
 - GUTTER, STYLE SPEC PER BUILDER.
 - DOWNSPOUT, STYLE SPEC PER BUILDER.
 - CORROSION RESISTANT ROOF TO WALL FLASHING. REFER TO ROOF DETAILS.
 - EXTERIOR STUCCO, TYPICAL '10' (UNO), STANDARD FINISH.
 - SMOOTH FINISH
 - EXTERIOR SIDING MATERIAL, COMPOSITE WOOD:
 - LAY WITH 2" REVEAL.
 - WOOD PANEL WITH METAL CHANNEL.
 - COMPOSITE WOOD PANEL
 - EXTERIOR ADHERED MASONRY VENEER, SPEC PER BUILDER. HEIGHT AND WRAP-BACK AS NOTED.
 - TRIM, SIZE AS NOTED, HEIGHT X DEPTH OR SEE DETAIL:
 - STUCCO OVER FOAM, LIGHT SAND FINISH.
 - WOOD SYSTEM OVER NOMINAL SIE.
 - PRECAST STONE TRIM.
 - DECORATIVE CORBEL PER DESIGN DETAIL:
 - WOOD STUCCO.
 - WOOD CLIP ON PER DETAIL.
 - WOOD POST, SEE AS NOTED.
 - WOOD KNEE BRACE ATTACHMENT PER DETAIL.
 - DECORATIVE WOOD BEAM, SEE AS NOTED.
 - WROUGHT IRON RAILING PER DETAIL 5/AD5 (ATTACHMENT PER DETAIL 6/AD5).
 - METAL CHANNEL SCREED:
 - STUCCO, VERTICAL SEE DETAIL 9/AD5 / HORIZONTAL SEE DETAIL 11/AD5.
 - WOOD, VERTICAL SEE DETAIL 10/AD5 / HORIZONTAL SEE DETAIL 12/AD5.
 - SEE DETAIL 17/AD5.
 - SCUPPER, SEE DETAIL 19/AD1.
 - ROOF OVERFLOW, SEE DETAIL 20/AD1.
 - EXTERIOR COACH LIGHT, MOUNT AT 4'-0" AFF (UNO).
 - ADDRESS NUMBER, MOUNT AT 4'-6" AFF (UNO).
 - UTILITY CONNECTIONS (TYPICAL), PER MUNICIPAL CODES.

Elevation Keynotes:

- MINIMUM CLASS 'A' ROOFING. REFER TO ROOF PLAN SHEET NOTES.
- 2x6 FASCIA / BARGE RAFTER.
- GUTTER, STYLE SPEC PER BUILDER.
- DOWNSPOUT, STYLE SPEC PER BUILDER.
- CORROSION RESISTANT ROOF TO WALL FLASHING. REFER TO ROOF DETAILS.
- EXTERIOR STUCCO, TYPICAL '10' (UNO), STANDARD FINISH.
 - SMOOTH FINISH
- EXTERIOR SIDING MATERIAL, COMPOSITE WOOD:
 - LAY WITH 2" REVEAL.
 - WOOD PANEL WITH METAL CHANNEL.
 - COMPOSITE WOOD PANEL
- EXTERIOR ADHERED MASONRY VENEER, SPEC PER BUILDER. HEIGHT AND WRAP-BACK AS NOTED.
- TRIM, SIZE AS NOTED, HEIGHT X DEPTH OR SEE DETAIL:
 - STUCCO OVER FOAM, LIGHT SAND FINISH.
 - WOOD SYSTEM OVER NOMINAL SIE.
 - PRECAST STONE TRIM.
- DECORATIVE CORBEL PER DESIGN DETAIL:
 - WOOD STUCCO.
 - WOOD CLIP ON PER DETAIL.
- WOOD POST, SEE AS NOTED.
- WOOD KNEE BRACE ATTACHMENT PER DETAIL.
- DECORATIVE WOOD BEAM, SEE AS NOTED.
- WROUGHT IRON RAILING PER DETAIL 5/AD5 (ATTACHMENT PER DETAIL 6/AD5).
- METAL CHANNEL SCREED:
 - STUCCO, VERTICAL SEE DETAIL 9/AD5 / HORIZONTAL SEE DETAIL 11/AD5.
 - WOOD, VERTICAL SEE DETAIL 10/AD5 / HORIZONTAL SEE DETAIL 12/AD5.
 - SEE DETAIL 17/AD5.
- SCUPPER, SEE DETAIL 19/AD1.
- ROOF OVERFLOW, SEE DETAIL 20/AD1.
- EXTERIOR COACH LIGHT, MOUNT AT 4'-0" AFF (UNO).
- ADDRESS NUMBER, MOUNT AT 4'-6" AFF (UNO).
- UTILITY CONNECTIONS (TYPICAL), PER MUNICIPAL CODES.



'CALIFORNIA' (COMPOSITION)
FRONT ELEVATION "A"
3/16" = 1'-0"




'CALIFORNIA' (COMPOSITION)
REAR ELEVATION "A"
3/16" = 1'-0"



Northwest Land Park: Urban Courts

City of Sacramento, California



10430 MATHER BLVD
MATHER, CA 95645
916.366.3665


Sheet Revisions	
#	DATE: COMMENT
01.13.15	INITIAL PLAN CHECK SUBMITTAL
02.03.15	PLAN REVIEW 1
02.11.15	OWNER MODIFICATIONS
04.13.15	CLARIFICATION
06.30.15	FRAME WALK MODIFICATIONS

BUILDING 1
EXTERIOR ELEVATIONS
"A" (FRONT / REAR)

Sheet Number:
A5.010

Elevation Design Details:

THE FOLLOWING DETAILS CONVEY DESIGN INTENT. REFER TO ARCHITECTURAL DETAILS FOR SPECIFIC CONSTRUCTION ASSEMBLIES.





Sheet Notes:

- PARTIAL AND OPTION ELEVATIONS SHOW ONLY THE ATTRIBUTES AND DETAILS UNIQUE TO THE PARTIAL OR OPTION ELEVATION. REFER TO BASE ELEVATION FOR INFORMATION NOT SHOWN.
- WINDOW HEAD - HEIGHTS:
 - 1ST FLOOR = 6'-8" AFF (UNO)
 - 2ND FLOOR = 10'-0" AFF (UNO)
 - 3RD FLOOR = 6'-8" AFF (UNO)
 - 4TH FLOOR = 8'-0" AFF (UNO)
- EXTERIOR WALLS:
 - EXTERIOR COVERING REQUIREMENTS:
 - A. MINIMUM 26 GAUGE CORROSION-RESISTANT WEEP SCREED SHALL BE APPLIED OVER THE EXTERIOR WALLS AND WATER TRAPPED BEHIND THE STUCCO TO DRAIN TO THE EXTERIOR OF THE BUILDING WHERE THE EXTERIOR LATH COVERS AND TERMINATES ON THE ATTACHMENT FLANGE OF THE WEEP SCREED. THE WEEP SCREED MUST HAVE 4" CLEARANCE ABOVE GRADE AND 2" ABOVE PAVED AREAS (CFC R703.6.2.1)
 - B. WEEP SCREED BARRIERS APPLIED OVER WOOD-BASED SHEATHING SHALL INCLUDE A WATER-RESISTIVE VAPOR-PERMEABLE BARRIER WITH A PERFORMANCE OF AT LEAST EQUAL TO TWO LAYERS OF GRADE D PAPER. EXCEPTION: A WATER-RESISTIVE BARRIER EQUAL TO OR GREATER THAN 60 MINUTE GRADED PAPER AND IS SEPARATED FROM THE STUCCO BY AN INTERVENING WEATHER RESISTIVE INSULATION (WRI) LAYER OR DESIGNATED DRAINAGE SPACE. (CFC R703.6.3)
 - C. FINISH MATERIALS PER MFG INSTALLATION INSTRUCTIONS:
 - A. 1-COAT STUCCO SYSTEM OVER MIN 1" FOAM INSULATION (EPS). OVER ONE LAYER OF 60-MINUTE GRADE D PAPER OR EQUAL OVER STUDS OR WOOD-BASED SHEATHING. INSTALL PER THE MANUFACTURER'S SPECIFICATIONS BY THE MANUFACTURER.
 - B. FINISH MATERIAL SHALL COMPLY WITH ASTM E 568. THESE SHALL TERMINATE NOT LESS THAN 4" ABOVE FINISHED GROUND LEVEL. (CFC R703.9) BUILDER SPEC MFG OMEGA, ESR-1194.
 - C. FIBER CEMENT SIDING: OVER ONE LAYER OF APPROVED WATER-RESISTIVE BARRIER OVER STUDS OR SHEATHING. (CFC R703.9) BUILDER SPEC PER NOTES.
 - WINDOWS: MIN. SPEC PER BUILDER.
 - GRID / DIVIDED LITES AS SHOWN.
 - ENTRY DOORS: PASED PANEL. SPEC PER BUILDER.
 - OVER HEAD GARAGE DOORS:
 - STEEL SECTIONAL SPEC PER BUILDER.
 - PAVED PANEL AND GLASS INSERTS AS SHOWN.
 - WINDUPOOR: WINDUPOOR SPEC PER BUILDER.
 - ELASTOMERIC CHECKING OVER PLYWOOD SUBSTRATE.
 - RIPPED FLOOR JOISTS FOR SLOPE TO DRAIN.
 - FASCIA BOARD: 2x6, UNLESS NOTED OTHERWISE. REFER TO ELEVATION KEYNOTES.
 - BARGE RAFTER: 2x6, UNLESS NOTED OTHERWISE. REFER TO ELEVATION KEYNOTES.
 - ADDRESS NUMBER: ADDRESS NUMBER THAT IS VISIBLE FROM THE STREET OR ROAD FRONTING PROPERTY (CFC R819.1) SHALL BE LEGIBLE.
 - A. NUMBERS SHALL CONTRAST WITH THEIR BACKGROUND AND BE LEGIBLE.
 - B. NUMBERS SHALL BE A MINIMUM 4" HIGH WITH A MINIMUM STROKE WIDTH OF 1/2".
 - ROOF HEELS: LABELED AS SUCH AND SHALL BE INCREASED HEEL TO PLANE FASCIA. REFER TO RAISED HEEL TRUSS LAYOUTS.

Elevation Keynotes:

- MINIMUM CLASS "A" ROOFING. REFER TO ROOF PLAN SHEET NOTES.
- 2x6 FASCIA / BARGE RAFTER.
- GUTTER, STYLE SPEC PER BUILDER.
- DOWNSPOUT, STYLE SPEC PER BUILDER.
- CORROSION RESISTANT ROOF TO WALL FLASHING. REFER TO ROOF DETAILS.
- EXTERIOR STUCCO, TYPICAL 4" (UNO), STANDARD FINISH.
 - A. SMOOTH FINISH
- EXTERIOR SIDING MATERIAL, COMPOSITE WOOD:
 - A. LAY WHITE REVEAL PANELS WITH METAL CHANNEL.
 - B. COMPOSITE WOOD PANEL
- EXTERIOR ADHERED MASONRY VENEER. SPEC PER BUILDER. HEIGHT AND WRAP-SACK AS NOTED.
- TRIM, SIZE AS NOTED. HEIGHT, X, DEPTH OR SEE DETAIL:
 - A. STUCCO OVER FOAM, LIGHT SAND FINISH.
 - B. COMPOSITE WOOD (NOMINAL SIZE).
 - C. PRECAST STONE TRIM.
- DECORATIVE CORBEL. PER DESIGN DETAIL:
 - A. WOOD CORBEL PER DETAIL.
 - B. WOOD POST. SIZE AS NOTED.
- WOOD KNEE BRACE ATTACHMENT PER DETAIL.
- DECORATIVE WOOD BEAM. SIZE AS NOTED.
- WROUGHT IRON RAILING PER DETAIL 5/AD5 (ATTACHMENT PER DETAIL 6/AD5).
- METAL CHANNEL SCREED:
 - A. STUCCO, VERTICAL. SEE DETAIL 9/AD5 / HORIZONTAL. SEE DETAIL 11/AD5.
 - B. WOOD. VERTICAL. SEE DETAIL 10/AD5 / HORIZONTAL. SEE DETAIL 12/AD5.
 - C. SCUPPER. SEE DETAIL 17/AD1.
- ROOF OVERLAP. SEE DETAIL 20/AD1.
- EXTERIOR COACH LIGHT: MOUNT AT 4'-0" AFF (UNO).
- ADDRESS NUMBER: MOUNT AT 4'-6" AFF (UNO).
- UTILITY CONNECTIONS (TYPICAL) PER MUNICIPAL CODES.




JEFFREY DEVUERE + ASSOCIATES
ARCHITECTS + PLANNERS
5905 GRANITE LAKE DRIVE, SUITE 140
GRANITE BAY, CA 95748
P: 916.283.3700
F: 916.283.3711
WWW.JDAARCH.COM

Northwest Land Park: Urban Courts

City of Sacramento, California



10430 MATHER BLVD
MATHER, CA 95655
916.366.3665




© 2014 Jeffrey Devuere + Associates Architects, Planners, Inc. All rights reserved. These designs, drawings, and specifications are the intellectual property of Jeffrey Devuere + Associates Architects, Planners, Inc. and shall remain in the sole custody of Jeffrey Devuere + Associates Architects, Planners, Inc.

JDA Job Number: 14060

Sheet Revisions	
#	DATE: COMMENT
01.13.15	INITIAL PLAN CHECK SUBMITTAL
02.03.15	PLAN REVIEW 1
02.11.15	OWNER MODIFICATIONS
06.30.15	FRAME WALK MODIFICATIONS

BUILDING 1
Sheet Description:
EXTERIOR ELEVATIONS
"A" (RIGHT/LEFT)

Sheet Number:
A5.011



MATERIAL KEYING LEGEND FOR SPECIFICATIONS*

- 2.60 PAVEMENTS AND WALKS
- 2.60D CONCRETE WALK/PAVING
- 3.30 CONCRETE
- SEE STRUCTURAL DRAWINGS*
- 3.30A CAST-IN-PLACE CONCRETE
- 4.20 UNIT MASONRY
- 4.20A FACE BRICK - STANDARD MODULAR
- 4.20C CONCRETE MASONRY UNITS
- 4.20D ANCHOR BOLTS
- 5.10 STRUCTURAL STEEL
- SEE STRUCTURAL DRAWINGS*
- 5.10A STEEL BEAM
- 5.90 MISCELLANEOUS METALS
- 5.90E MC 12 X 10.6 STRINGER
- 6.10 ROUGH CARPENTRY
- 6.10A WOOD BLOCKING
- 6.10B PLYWOOD
- 7.20 INSULATION
- 7.20C CAVITY WALL INSULATION
- 7.20H METAL Z FURRING
- 7.50 ROOFING SYSTEM (EPDN)
- 7.50A ROOFING MEMBRANE
- 8.15 PLASTIC DOORS
- SEE DOOR SCHEDULE*
- 8.15A PLASTIC DOOR
- 8.50 METAL WINDOWS
- 8.50A ALUMINUM WINDOWS
- 9.25 GYPSUM WALLBOARD
- 9.25A 5/8" TYPE "X" GYPSUM WALLBOARD
- 9.25C METAL STUD SYSTEM
- 9.80 SPECIAL COATING SYSTEM
- 9.80A SPECIAL COATING SYSTEM
- 9.80J ROUTED JOINT
- 9.80K EXPANSION JOINT
- 12.17 ENTRANCE MATS
- 12.17A RECESSED ENTRANCE MAT

* SEE REFERENCES NOTED FOR INFORMATION ELABORATING ON-OR WORK IN ADDITION TO MATERIALS NOTED HERE. PROVIDE ALL MATERIALS AS REQUIRED FOR A COMPLETE AND PROPER INSTALLATION.

DRAWING NOTES

1. CONCRETE MASONRY UNIT SOLDER COURSE AT EXPOSED AREAS. CUT CONCRETE MASONRY UNIT TO DIMENSIONS NOTED. PROVIDE SOLDER COURSE WITH AN ANCHOR HAS OPTION TO CUT BLOCK TO 5" HEIGHT. COORDINATE WITH DRAWING A301.

No	REVISIONS/SUBMISSIONS	Date

CWVG
CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
 120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE
BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT
ADDITION AND ALTERATIONS AT THE
JR./SR. HIGH SCHOOL
 SED# 01-02-01-04-0-004-006

WALL SECTIONS

Designed	© 1994	Project No.	01020401
Drawn	DB	Scale	AS NOTED
Checked	L.J.H.	Drawing No.	A502
Reviewed	K.P.G.	Date	11-11-94

WALL SECTION (STAIR #1)
 A101, A102
 A-14
 3/4" = 1'-0"

FIREWALL SECTION
 A101, A102
 A-8
 3/4" = 1'-0"

WALL SECTION
 A101, A102
 A-4
 3/4" = 1'-0"


NOT FOR CONSTRUCTION

Sheet Revisions	
#	DATE COMMENT
01	01.15.15 INITIAL PLAN CHECK SUBMITTAL
02	02.03.15 PLAN REVIEW 1
03	03.30.15 FRAME WALK MODIFICATIONS


- Sheet Notes:**
1. THESE DRAWINGS ARE INTENDED TO DEPICT VOLUME SPACE ONLY. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE NOTED. THESE DRAWINGS REPRESENT ELEVATION "A" FOR THE STANDARD BASE PLAN ONLY. REFER TO ELEVATION SHEETS AND ROOF PLAN FOR VARIATIONS IN OTHER ELEVATIONS AND STRUCTURAL OPTIONS. OVERSIGHTS AND OMISSIONS ARE THE RESPONSIBILITY OF THE ARCHITECT. MANDATORY CODE MINIMUMS LISTED BELOW PER CBC SECTION 150:
 - INSULATION AT ATTIC CEILING: R-30
 - INSULATION AT EXTERIOR WALL: R-13 (241 R-19 (246))
 - INSULATION AT EXTERIOR WINDOW: R-5
 - INSULATION AT HOUSE / GARAGE CEILING: R-30
 - INSULATION AT HOUSE / GARAGE WALL: R-13 (241 R-19 (246))
 - INSULATION AT BASED FLOOR: R-19
 REFER TO ENERGY SHEETS & T24 CALCULATIONS FOR SPECIFIC INSULATION VALUES AND DESIGN CRITERIA.
 2. ROOF ASSEMBLY PER ELEVATION OVER ROOF SHEATHING, PER STRUCTURAL DRAWINGS.
 3. MANUFACTURED TRUSS PER TRUSS CALCULATIONS.
 4. EXTERIOR WALL, EXTERIOR FINISH PER ELEVATIONS.
 5. INSULATION PER MODEL ENERGY CODE REQUIREMENTS.
 6. FLOOR SHEATHING OVER MANUFACTURED FLOOR TRUSSES, PER STRUCTURAL DRAWINGS.
 7. CONCRETE FOUNDATION PER STRUCTURAL DRAWINGS.
 8. 30" MINIMUM CLEARANCE FOR ATTIC ACCESS.
 9. BUILT-UP ROOF BY OTHERS.
 10. 1" BUILT-UP FLOOR TOPPING.

Section Keynotes:


1. ROOF ASSEMBLY PER ELEVATION OVER ROOF SHEATHING, PER STRUCTURAL DRAWINGS.
2. MANUFACTURED TRUSS PER TRUSS CALCULATIONS.
3. EXTERIOR WALL, EXTERIOR FINISH PER ELEVATIONS.
4. INSULATION PER MODEL ENERGY CODE REQUIREMENTS.
5. FLOOR SHEATHING OVER MANUFACTURED FLOOR TRUSSES, PER STRUCTURAL DRAWINGS.
6. CONCRETE FOUNDATION PER STRUCTURAL DRAWINGS.
7. 30" MINIMUM CLEARANCE FOR ATTIC ACCESS.
8. BUILT-UP ROOF BY OTHERS.
9. 1" BUILT-UP FLOOR TOPPING.




BUILDING SECTION BB
3/16" = 1'-0"



BUILDING SECTION AA
3/16" = 1'-0"



BUILDING SECTION DD
3/16" = 1'-0"



BUILDING SECTION CC
3/16" = 1'-0"

MATERIAL KEYING LEGEND FOR SPECIFICATIONS*

- 2.20 SITE PREPARATION & EARTHWORK
- 2.20F CRUSHED GRAVEL
- 2.20G 4" PERFORATED P.V.C.
- 3.30 CONCRETE
- SEE STRUCTURAL DRAWINGS*
- 3.30A CAST-IN-PLACE CONCRETE
- 3.30C EXPANSION JOINT FILLER
- 4.20 UNIT MASONRY
- 4.20A FACE BRICK - STANDARD MODULAR
- 4.20C CONCRETE MASONRY UNITS
- 4.20D HORIZONTAL JOINT REINFORCING
- 4.20E FLEXIBLE MASONRY ANCHORS
- 4.20F CONCRETE SLATE CHAMFER AT EXPOSED EDGES
- 4.20P SLATE SILL - 1/4" CHAMFER AT EXPOSED EDGES
- 4.20Y PRECAST CONCRETE BAND
- 5.10 STRUCTURAL STEEL
- SEE STRUCTURAL DRAWINGS*
- 5.10A STEEL BEAM
- 5.10B STEEL ANGLE
- 5.20 STEEL JOISTS
- SEE STRUCTURAL DRAWINGS*
- 6.10 ROUGH CARPENTRY
- 6.10A WOOD BLOCKING
- 6.10C WOOD FORMING
- 7.20 INSULATION
- 7.20A EXTERIOR FOUNDATION WALL INSULATION
- 7.20C CAVITY WALL INSULATION
- 7.60 FLASHING AND SHEETMETAL
- 7.60A FLASHING AND SHEETMETAL TURN-UP AT ENDS AT WALL OPENINGS TO FORM DAM
- 8.50 METAL WINDOWS
- 8.50A ALUMINUM WINDOWS
- 9.25 GYPSUM WALLBOARD
- 9.25A GYPSUM WALLBOARD
- 9.25B METAL STUD SYSTEM
- 9.25G METAL STUD RUNNER - 2" DEEP TO PROVIDE 1" EXPANSION SPACE FOR STUDS
- 9.50 ACOUSTICAL TREATMENT
- SEE ROOM FINISH SCHEDULE*
- 9.50A SUSPENDED CEILING SYSTEM
- 9.80 SPECIAL COATING SYSTEM
- 9.80A SPECIAL COATING SYSTEM
- 9.80C EXPANSION JOINT
- 10.50 LOCKERS
- 10.50A SINGLE TIER LOCKERS
- 10.50B DOUBLE TIER LOCKERS
- 10.50H METAL BASE
- 10.50I RECESSED TRIM

* SEE REFERENCES NOTED FOR INFORMATION ELABORATING ON-OR WORK IN ADDITION TO MATERIALS NOTED HERE. PROVIDE ALL MATERIALS AS REQUIRED FOR A COMPLETE AND PROPER INSTALLATION.

DRAWING NOTES

- BASE BID: INCLUDE LOCKERS WITH SLOPING TOP AND METAL BASE. PAINT WALLS BEHIND LOCKERS. TYPICAL FOR BOTH CORRIDORS 106 AND 208. REFER TO C-14/A101 ALTERNATE #102.
- ALTERNATE #102: INCLUDE RECESSED LOCKERS WITH TRIM. CONCRETE BASE. VINYL COVE BASE. CONCRETE MASONRY UNIT WALL. METAL STUDS. GYPSUM WALLBOARD AND RELATED WORK. TYPICAL FOR BOTH CORRIDORS 106 AND 208. REFER TO G-5/101 AND G-5/A102.

CWG CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305




ADDITION - ALTERATIONS AND RECONSTRUCTION

FOR THE
BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT
ADDITION AND ALTERATIONS AT THE
JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006

WALL SECTIONS

Project No. 01020401
Scale A5 NOTED
Drawing No. A501


Designed DB
Drawn DB
Checked L.J.H.
Reviewed K.F.G.
Date 11-11-94



1 2 3 4 5 6 7 8 9 10 11 12 13 14

M L K J H G F E D C B A
















NOT FOR CONSTRUCTION




© 2024 JDA, Jeffrey Demure & Associates Architects, Planners, Inc. All rights reserved. These designs, drawings, and specifications are the property of Jeffrey Demure & Associates Architects, Planners, Inc. and shall remain confidential. No part of these documents or the contents herein is to be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Jeffrey Demure & Associates Architects, Planners, Inc.

Sheet Revisions	
#	DATE / COMMENT
01	01.13.15 INITIAL PLAN CHECK SUBMITTAL
02	02.03.15 PLAN REVIEW 1
03	
04	
05	
06	06.15.15 FRAME WALK MODIFICATIONS


JDA Job Number: 14040
ALL PLANS
 Sheet Description:
DETAILS
FIRE PROTECTION
 Sheet Number:
FP1





- MATERIAL KEYING LEGEND (SEE SPECIFICATIONS*)
- 4.20 UNIT MASONRY
 - 4.20C CONCRETE MASONRY UNITS
 - 5.50 MISCELLANEOUS METALS
 - 5.50A MISCELLANEOUS STEEL - SHAPE AND SIZE AS NOTED
 - 5.50B HANGING NOMINAL STEEL PIPE (1.66" O.D.)
 - 5.50C HANGING NOMINAL STEEL PIPE (1.66" O.D.)
 - 5.50AM 1" NOMINAL STEEL PIPE HANDRAIL (1.315" O.D.)
 - 5.50AP STEEL WALL BRACKET, JULIUS BLUM #622, OR EQUAL
 - 8.10 METAL DOORS AND FRAMES
 - 8.10E METAL ACCESS DOOR
 - 9.25 GYPSUM WALLBOARD
 - 9.25A 5/8" TYPE "X" GYPSUM WALLBOARD
 - 9.50 ACOUSTICAL TREATMENT
 - SEE ROOM FINISH SCHEDULE*
 - 9.50A SUSPENDED CEILING SYSTEM
 - 9.90 PAINTING
 - SEE ROOM FINISH SCHEDULE*
 - 9.90P-2 PAINT P-2
 - 10.25 FIREFIGHTING DEVICES
 - 10.25A FIRE EXTINGUISHER CABINET, PAINT P-2, MODEL #2408, BY HANSON MANUFACTURING CO. OR APPROVED EQUAL, BOTTOM AT 8" ABOVE FLOOR.
 - 10.42 SIGNAGE AND GRAPHICS
 - 10.42C INTERIOR HANDICAP SIGN (TYPE AS NOTED)
 - 12.17 ENTRANCE MATS
 - 12.17A RECESSED ENTRANCE MAT

- DRAWING NOTES
- CONCRETE MASONRY UNIT SOLDIER COURSE AT EXPOSED AREAS. CUT CONCRETE MASONRY UNIT TO DIMENSION INDICATED TO MAINTAIN NOMINAL COURSING. AT CONCEALED AREAS CONTRACTOR HAS OPTION TO CUT BLOCK TO 5" HEIGHT. COORDINATE WITH SECTION A-8/A502. REFER TO ROOM FINISH SCHEDULE FOR STAIR AND FLOOR FINISHES.
 - INDICATE ALL EXPOSED STEEL STAIR CONSTRUCTION WITH 9.90P-C.



CWVG
CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305





ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006

STAIR PLANS & SECTIONS

Designed	© 1994	Project No.	O1020401
Drawn	DB	Scale	AS NOTED
Checked	L.J.H.	Drawing No.	A301
Reviewed	K.P.G.	Date	11-11-94

NOT FOR CONSTRUCTION


1 2 3 4 5 6 7 8 9 10 11 12 13 14



MATERIAL KEYING LEGEND (SEE SPECIFICATIONS*) 4.20 UNIT MASONRY 4.20C CONCRETE MASONRY UNITS 9.25 GYPSUM WALLBOARD 9.25A 5/8" TYPE "X" GYPSUM WALLBOARD 9.40 TERRAZZO 9.40C TERRAZZO COVE BASE 9.65 RESILIENT FLOORING 9.65B VINYL COVE BASE 10.10 CHALKBOARD AND TACKBOARDS 10.10B LIQUID MARKER BOARD 10.10C TACKBOARD 10.25 FIREFIGHTING DEVICES MODEL #2409-R2 BY LARSON MANUFACTURING CO., OR APPROVED EQUAL, BOTTOM AT 8" ABOVE FLOOR 10.50 LOCKERS 10.50A SINGLE TIER LOCKERS 10.50I RECESSED TRIM 10.62 FOLDING PARTITIONS 10.62A FOLDING PARTITION 11.46 UNIT KITCHENS 11.46A COMPACT KITCHEN UNIT 12.30 CASEWORK SEE DRAWINGS FOR CASEWORK 14.20 ELEVATORS 14.20A ELEVATOR	
DRAWING NOTES 1. PROVIDE OPENING IN EXISTING WALL FOR NEW DOOR AND FINISH WITH INTERIOR WALL FINISH AND PAINT. PROVIDE EXPANSION JOINT COVERS AT FLOOR JAMB AND HEAD OF DOOR FRAME. FLOOR TILE AND BASE IMMEDIATELY ADJACENT TO NEW OPENING TO BE REMOVED BY ASBESTOS ABATEMENT CONTRACTOR. 2. AREA OF RESCUE ASSISTANCE FOR WHEELCHAIR BOUND PERSONS. PROVIDE SIGNAGE; SEE SPEC SECTION 8.70. PROVIDE SIGNAGE FOR WHEELCHAIR BOUND PERSONS IN ALTERNATE NO. 6. FLOOR TILE AND BASE REMOVAL BY ASBESTOS ABATEMENT CONTRACTOR. 3. PROVIDE SIGNAGE; SEE SPEC SECTION 8.70. PROVIDE SIGNAGE FOR WHEELCHAIR BOUND PERSONS IN ALTERNATE NO. 6. FLOOR TILE AND BASE REMOVAL BY ASBESTOS ABATEMENT CONTRACTOR.	

CWG CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C. 120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305	
ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL SED# 01-02-01-04-0-004-006 Drawing Title	
SECOND FLOOR PLAN	
Seal	Project No. 01020401 Scale AS NOTED Drawing No. A102
Designed © 1994 Drawn DB Checked L.J.H. Reviewed K.T.G. Date 11-11-94	No REVISIONS/SUBMISSIONS Date

SECOND FLOOR PLAN A101 1/8" = 1'-0"		KEY PLAN A-14 1" = 120'-0"	
SECOND FLOOR PLAN		KEY PLAN	
ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL SED# 01-02-01-04-0-004-006 Drawing Title		SECOND FLOOR PLAN	
Seal		Project No. 01020401 Scale AS NOTED Drawing No. A102	
Designed © 1994 Drawn DB Checked L.J.H. Reviewed K.T.G. Date 11-11-94		No REVISIONS/SUBMISSIONS Date	




MATERIAL KEYING LEGEND (SEE SPECIFICATIONS*)

- 4.20 UNIT MASONRY
- 4.20C CONCRETE MASONRY UNITS
- 8.10 METAL DOORS AND FRAMES
- 8.10F 16 GAUGE HOLLOW METAL PIPE ENCLOSURE
- 9.25 GYPSUM WALLBOARD
- 9.25A 5/8" TYPE 'X' GYPSUM WALLBOARD
- 9.40 TERRAZZO
- 9.40C TERRAZZO COVE BASE
- 9.65 RESILIENT FLOORING
- 9.65B VINYL COVE BASE
- 10.10 CHALKBOARD AND TACKBOARDS
- 10.10B LIQUID MARKER BOARD
- 10.10C TACKBOARD
- 10.25 FIREFIGHTING DEVICES
- 10.25A FIRE EXTINGUISHER CABINET, PAINT P-2, MODEL # 4200 BY LARSON MANUFACTURING ABOVE FLOOR.
- 10.50 LOCKERS
- 10.50A SINGLE TIER LOCKERS
- 10.50I RECESSED TRIM
- 10.62 FOLDING PARTITIONS
- 10.62A FOLDING PARTITION
- 11.46 UNIT KITCHENS
- 11.46A COMPACT KITCHEN UNIT
- 12.30 CASEWORK FOR CASEWORK
- SEE DRAWINGS FOR CASEWORK
- 14.20 ELEVATORS
- 14.20A ELEVATOR

*SEE REFERENCE NOTED FOR INFORMATION ELABORATING ON-OR WORK IN ADDITION TO - MATERIALS NOTED HERE. PROVIDE ALL MATERIALS AS REQUIRED FOR A COMPLETE AND PROPER INSTALLATION.

DRAWING NOTES

1. PROVIDE OPENING IN EXISTING WALL FOR NEW DOOR AND FRAME. PROVIDE FINISH SURFACES TO MATCH MATERIALS ADJACENT TO OPENING. PROVIDE FINISH TO MATCH MATERIALS IMMEDIATELY ADJACENT TO NEW OPENING TO BE REMOVED. REMOVE AND REPLACE GYPSUM WALLBOARD ABOVE LOCKERS, EACH SIDE OF CORRIDOR. COORDINATE WORK WITH PLUMBING AND HVAC CONTRACTORS.




CWGW CATALDO, WATERS and GRIFFITH ARCHITECTS, P.C.
120 ERIE BOULEVARD, SCHENECTADY, N.Y. 12305

ADDITION - ALTERATIONS AND RECONSTRUCTION FOR THE BERNE-KNOX-WESTERLO, CENTRAL SCHOOL DISTRICT

ADDITION AND ALTERATIONS AT THE JR./SR. HIGH SCHOOL
SED# 01-02-01-04-0-004-006


FIRST FLOOR PLAN	
Designed	Project No. 01020401
Drawn	Scale AS NOTED
Checked	L.J.H.
Reviewed	K.P.G.
Date	11-11-94
Drawing No. A101	

FIRST FLOOR PLAN
A101




KEY PLAN
A-14
1/8" = 1'-0"

WALL TYPES
A101-A102



WALL TYPES
A101-A102
1/8" = 1'-0"


FIRST FLOOR PLAN
A101




KEY PLAN
A-14
1/8" = 1'-0"

WALL TYPES
A101-A102
1/8" = 1'-0"


CORRIDOR ELEV. (ALT. #1)
A101
1/8" = 1'-0"



CORRIDOR PLAN (ALT. #1)
A101
1/8" = 1'-0"




(E) CORRIDOR ELEVATION
A101
1/8" = 1'-0"




(E) CORRIDOR PLAN
A101
1/8" = 1'-0"


(E) CORRIDOR PLAN
A101
1/8" = 1'-0"




1 FLOOR SHEAR TRANSFER
 SCALE: 3/4" = 1'-0"




2 FLOOR SHEAR TRANSFER
 SCALE: 3/4" = 1'-0"




3 INTERIOR SHEAR TRANSFER
 SCALE: 3/4" = 1'-0"




4 INTERIOR SHEAR TRANSFER
 SCALE: 3/4" = 1'-0"




5 PARALLEL JOISTS
 SCALE: 3/4" = 1'-0"




6 PERPENDICULAR JOISTS
 SCALE: 3/4" = 1'-0"




7 FLOOR SHEAR TRANSFER
 SCALE: 3/4" = 1'-0"




8 FLOOR SHEAR TRANSFER
 SCALE: 3/4" = 1'-0"




9 FLOOR SHEAR TRANSFER
 SCALE: 3/4" = 1'-0"




10 FLOOR SHEAR TRANSFER
 SCALE: 3/4" = 1'-0"




11 ROOF TO WALL
 SCALE: 3/4" = 1'-0"




12 ROOF TO WALL
 SCALE: 3/4" = 1'-0"




13 TYPICAL COLLECTOR DETAIL
 SCALE: 3/4" = 1'-0"




14 FLOOR STRAP HOLDOWN
 SCALE: 3/4" = 1'-0"




15 FLOOR STRAP HOLDOWN
 SCALE: 3/4" = 1'-0"




16 SHEAR TRANSFER @ LOW ROOF
 SCALE: 3/4" = 1'-0"



17 SHEAR TRANSFER @ TALL BEAM
 SCALE: 3/4" = 1'-0"




18 SHEAR TRANSFER @ TALL BEAM
 SCALE: 3/4" = 1'-0"




19 FLOOR FRAMING @ PLATFORM
 SCALE: 3/4" = 1'-0"




20 FLOOR FRAMING @ PLATFORM
 SCALE: 3/4" = 1'-0"



21 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








22 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








23 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"









24 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








30 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








36 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








42 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"









48 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








54 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








60 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








66 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"









72 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








78 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








84 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








90 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"









96 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








102 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








108 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"








114 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"









120 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"



126 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"



132 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"



138 FLOOR FRAMING @ FLUSH BEAM
 SCALE: 3/4" = 1'-0"

